

PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.05.01.10351.1	5	

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0196000000-E	0264000000-E	1099500000-E	1099700000-E	1220000000-E	1260000000-E	1297000000-E	1308000000-E	1330000000-E	1523000000-E	1575000000-E	1704000000-E	8150000000-E	2550000000-E	7444000000-E		
											GEOTEXTILE FOR SOIL STABILIZATION	SHOULDER GRADING	SHALLOW UNDERCUT	CLASS IV SUBGRADE STABILIZATION	INCIDENTAL STONE BASE	AGGREGATE SHOULDER BORROW	1 1/2" MILLING	0" TO .5" MILLING	0" TO 1.5" MILLING	INCIDENTAL MILLING	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJUST DROP INLET	PORTABLE LIGHTING	INDUCTIVE LOOP SAWCUT	
											MI	FT	SY	SMI	CY	TON	TONS	TON	SY	SY	SY	SY	TONS	TON	TONS	EA	LS
2020CPT.05.01.10351.1	Franklin	1	US HWY 1 SB	VANCE CO TO WAKE CO	1	2	NO	NO	11.82	30	1,200.00	23.57	400	800	589	732	234,341	369		7,850	28,588	1,715	447		*	986	
2020CPT.05.01.10351.1	Franklin	2	US HWY 1 NB	WAKE CO TO VANCE CO	1	2	NO	NO	11.8	30		22.96			579	2,138			1,503	12,963	22,223	1,333	1,056	7	*		
TOTAL FOR PROJ NO. 2020CPT.05.01.10351.1											23.62	1,200.00	46.53	400	800	1,168	2,870	234,341	369	1,503	20,813	50,811	3,048	1,503	7	1	986
GRAND TOTAL											23.62	1,200.00	46.53	400	800	1,168	2,870	234,341	369	1,503	20,813	50,811	3,048	1,503	7	1	986

Refer to standard drawing 1205.06 for pavement marking lane drops.

### THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	13000000-E	700000-E	4510000000-N	4685000000-E		4686000000-E	4695000000-E	4700000000-E	4705000000-E	71000000-E	7210000000-E	4725000000-E				4770000000-E		4810000000-E				82000000-E	85000000-E	4845000000-N				8500000000-E	9050000000-E	
									WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	LAW ENFORCEMENT	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	4" X 120 M WHITE THERMO	8" X 90 M WHITE THERMO	12" X 90 M WHITE THERMO	16" X 120 M WHITE THERMO	24" X 120 M WHITE THERMO	THERMO RXR 120 M	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR ARROW 90 M	THERMO STR & LT ARROW 90 M	4" YELLOW COLD APPLIED PLASTIC, TYPE II	4" WHITE COLD APPLIED PLASTIC, TYPE II	4" YELLOW PAINT	4" WHITE PAINT	8" WHITE PAINT	24" WHITE PAINT	PAINT LT ARROW	PAINT RT ARROW	PAINT STR ARROW	PAINT STR & LT ARROW	4" LINE REMOVAL	SNOW PLOWABLE MARKERS			
									MI	FT	SF	LS	HR	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2020CPT.05.01.10351.1	Franklin	1	US HWY 1 SB	VANCE CO TO WAKE CO	1	2	11.82	30-52	1,324	0.49	120	62,576	61,194	29,142	2,602	320		667		95	23	28	2	327	411	61,194	91,718	2,602	667	95	23	28	2	738	1,126			
2020CPT.05.01.10351.1	Franklin	2	US HWY 1 NB	WAKE CO TO VANCE CO	1	2	11.8	30-52	1,322	0.51	120	63,484	61,194	31,035	2,294	721	50	588	2	89	47	24	2	334	415									749	1,130			
TOTAL FOR PROJ NO. 2020CPT.05.01.10351.1											23.62	2,646	1.00	240	126,060	122,388	60,177	4,896	1,041	50	1,255	2	184	70	52	4	661	826	61,194	91,718	2,602	667	95	23	28	2	1,487	2,256
GRAND TOTAL											23.62	2,646	1.00	240	126,060	122,388	60,177	4,896	1,041	50	1,255	2	184	70	52	4	661	826	61,194	91,718	2,602	667	95	23	28	2	1,487	2,256