

PROJECT NO.	SHEET NO.	TOTAL NO.
2019CPT.13.03.10571,		
2019CPT.13.03.20571	10	

### THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	441300000-E	445700000-N	468700000-E	470500000-E	471000000-E	472100000-E	481000000-E		4847010000-E		485000000-E	490500000-N														
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	THERMOPLASTIC PAVEMENT MARKING LINES (4", 240 MILS) WHITE	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS) WHITE	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) WHITE	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS) RXR	PAINT PAVEMENT MARKING LINES (4") WHITE	PAINT PAVEMENT MARKING LINES (4") YELLOW	POLYUREA PAVEMENT MARKING LINES WHITE (4", 20 MILS) (HIGHLY REFLECTIVE MEDIA)	POLYUREA PAVEMENT MARKING LINES YELLOW (4", 20 MILS) (HIGHLY REFLECTIVE MEDIA)	REMOVAL OF PAVEMENT MARKING LINES (4")	SNOWPLOWABLE PAVEMENT MARKERS														
									SF	LS	LF	LF	LF	EA	LF	LF	LF	LF	LF	EA															
2019CPT.13.03.10571	Madison	1	US 25-70	FROM NC 208 TO BEG PASSING LANE AT TOP OF THE MTN (MP 15.92 TO MP 17.85)	1	2	2WU	1.93	26			300							20,381	20,381		145													
2019CPT.13.03.10571	Madison	2	NC 209	FROM PVMNT JOINT NORTH OF SR 1175 TO PVMNT JOINT AT SPRING CREEK UNITED METHODIST CHURCH (MP 13.91 TO MP 8.63)	1	2	2WU	5.28	20	1,147	*								56,813	56,813		700													
2019CPT.13.03.10571	Madison	3	US 25/70	FROM THE END OF MAP 1 TO THE R/ TRACKS IN HOT SPRINGS (MP 17.85 TO MP 20.86)	1,2,6	2	2WU	3.01	34				40	132	4				34,000	32,550		365													
<b>TOTAL FOR PROJ NO. 2019CPT.13.03.10571</b>												<b>1,147</b>	<b>1</b>	<b>300</b>	<b>40</b>	<b>132</b>	<b>4</b>			<b>111,194</b>	<b>109,744</b>		<b>1,210</b>												
										<b>220,938</b>																									
2019CPT.13.03.20571	Madison	4	SR 1502	FROM SR 1503 TO SR 1501 (MP 0.01 TO MP 3.62)	3	2	2WD	3.61	22	3,251	*																								
2019CPT.13.03.20571	Madison	5	SR 1531	FROM SR 1530 TO SR 1530 (MP 0.00 TO MP 4.25)	4	2	2WU	4.25	18																							76,243	76,243		
2019CPT.13.03.20571	Madison	6	SR 1001	FROM BRIDGE #328 TO SR 1118 (MP 8.37 TO MP 5.94)	5	2	2WU	2.43	20																										102644
2019CPT.13.03.20571	Madison	7	SR 1390	FROM NC 213 TO JOINT AT BRIDGE #59 (MP 1.47 TO MP 0.07)	3	2	2WU	1.4	20																							29,568	29,568		
2019CPT.13.03.20571	Madison	8	SR 1501	FROM SR 1502 TO EOM (MP 0.01 TO MP 0.58)	3	2	2WU	0.57	21																							12,038	12,038		
2019CPT.13.03.20571	Madison	9	SR 1503	FROM US 23 TO SR 1502 (MP 0.01 TO MP 0.24)	3	2	2WU	0.23	20																							4,858	4,858		
2019CPT.13.03.20571	Madison	10	SR 1549	FROM SR 1631 TO NC 213 (MP 0.06 TO MP 1.41)	3	2	2WU	1.35	22																							28,512	28,512		
2019CPT.13.03.20571	Madison	11	SR 1347	FROM US 23 TO EOP (MP 0.00 TO MP 2.15)	4	2	2WU	2.15	19																							45,408	45,408		
2019CPT.13.03.20571	Madison	12	SR 1314	FROM SR 1316 TO NC 212 (MP 0.01 TO MP 3.43)	5	2	2WU	3.42	19																							72,230	72,230		144460
2019CPT.13.03.20571	Madison	13	SR 1393	FROM US 25/70 TO SR 1198 (MP 0.76 TO MP 0.01)	4	2	2WU	0.75	18																							15,840	15,840		
2019CPT.13.03.20571	Madison	14	SR 1530	FROM SR 1527 TO YANCEY COUNTY LINE (MP 5.37-MP 7.13)	3	2	2WU	1.76	19																							37,171	37,171		
2019CPT.13.03.20571	Madison	15	SR 1399	FROM SR 1395 TO SR 1388 (MP 0.01 TO MP 1.31)	4	2	2WU	1.3	18																							27,456	27,456		
2019CPT.13.03.20571	Madison	16	SR 1569	FROM SR 1570 TO SR 1574 (MP 1.4 TO MP 2.17P)	4	2	2WU	0.77	17																							16,262	16,262		
2019CPT.13.03.20571	Madison	17	SR 1119	FROM SR 1118 TO SR 1116 (MP 0.00 TO MP 1.05)	4	2	2WU	1.05	18																							22,176	22,176		
2019CPT.13.03.20571	Madison	18	SR 1458	FROM SR 1313 TO EOP (MP 0.00 TO MP 0.68)	4	2	2WU	0.68	17																										
2019CPT.13.03.20571	Madison	19	SR 1505	FROM SR 1503 TO EOP (MP 0.00 TO MP 1.94)	4	2	2WU	1.94	18																							40,973	40,973		
2019CPT.13.03.20571	Madison	20	SR 1502	FROM SR 1501 TO EOP (MP 3.62 TO MP 4.92)	3	2	2WU	1.3	21																							27,456	27,456		
<b>TOTAL FOR PROJ NO. 2019CPT.13.03.20571</b>																									<b>28.96</b>		<b>3,251</b>	<b>1</b>				<b>597,273</b>	<b>597,273</b>		<b>247,104</b>
																							<b>1,194,546</b>												
<b>GRAND TOTAL</b>																									<b>39.18</b>		<b>4,398</b>	<b>1</b>	<b>300</b>	<b>40</b>	<b>132</b>	<b>4</b>	<b>597,273</b>	<b>597,273</b>	<b>111,194</b>
										<b>1,194,546</b>																									
										<b>220,938</b>																									