

## ECONOLITE ASC/3-2070 ACTION PLAN PROGRAMMING DETAIL

### ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT. PHASING DURING FREE RUN - PROGRAM CHANGES (SHOWN BELOW) IN A TIME BASED ACTION PLAN. SCHEDULE A DAY PLAN THAT INCLUDES THE ACTION PLAN PROGRAMMED TO SELECT VEH DET PLAN 2 AND ENABLE SF BIT 5.

TO RUN ALT. PHASING DURING COORDINATION - SELECT THE TIME BASED ACTION PLAN THAT IS PROGRAMMED TO SELECT VEH DET PLAN 2 AND ENABLE SF BIT 5.

PHASING	VEH DET PLAN	SF BITS ENABLED
ACTIONS REQUIRED TO RUN <u>DEFAULT PHASING</u>	1	NONE
ACTIONS REQUIRED TO RUN <u>ALTERNATE PHASING</u>	2	5

**IMPORTANT:** IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX. FREE RUN EVENT SHOULD END BEFORE COORDINATION PLAN EVENT STARTS AND VICE-VERSA).

ALTERNATE PHASING CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN SF BIT 5 AND VEH DET PLAN 2 ACTIVATE TO CALL THE "ALTERNATE PHASING":

SF BIT 5:           Modifies overlap parent phases for head 51 to run protected turns only.

VEH DET PLAN 2:   Disables phase 2 call on loop 5A and reduces delay time for phase 5 call on loop 5A to 0 seconds.

1. From Main Menu select 5. TIME BASE
2. From TIME BASE Submenu select 2. ACTION PLAN

```

ACTION PLAN...[ 1]
PATTERN.....AUTO  SYS OVERRIDE.... NO
TIMING PLAN..... 0  SEQUENCE..... 0
VEH DETECTOR PLAN.. 2  DET LOG.....NONE
FLASH..... --  RED REST..... NO
VEH DET DIAG PLN... 0  PED DET DIAG PLN..0
DIMMING ENABLE.. NO  PRIORITY RETURN. NO
PED PR RETURN.. NO  QUEUE DELAY..... NO
PMT COND DELAY  NO
  PHASE  1  2  3  4  5  6  7  8  9  0  1  2  3  4  5  6
PED RCL  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
WALK 2   .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
VEX 2    .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
VEH RCL  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
MAX RCL  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
MAX 2    .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
  PHASE  1  2  3  4  5  6  7  8  9  0  1  2  3  4  5  6
MAX 3    .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
CS INH   .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
OMIT     .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
SPC FCT  .  .  .  .  X  .  .  .  .  .  .  .  .  .  .  .
AUX FCT  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
          1  2  3  4  5  6  7  8  9  0  1  2  3  4  5
LP 1-15  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 16-30 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 31-45 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 46-60 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 61-75 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 76-90 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 91-100 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
    
```

THIS ELECTRICAL DETAIL IS FOR  
THE SIGNAL DESIGN: 06-0334T1  
DESIGNED: March 2018  
SEALED: 03-29-2018  
REVISED: N/A

Temporary Design 1 - TMP Phase I  
Electrical Detail - Sheet 3 of 3

**DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED**

<p>Stantec Consulting Services Inc. 801 Jones Franklin Road-Suite 300 Raleigh, NC 27606 Tel. (919) 851-6866 Fax. (919) 851-7024 www.stantec.com License No. F-0672</p>	<p style="text-align: center; font-size: small;">ELECTRICAL AND PROGRAMMING DETAILS FOR:</p> <p style="text-align: center; font-size: x-small;">Prepared in the Offices of:</p> <div style="text-align: center;">   <small>750 N. Greenfield Pkwy, Garner, NC 27529</small> </div>	<p><b>US 401 Business (Raeford Road) at Montclair Drive</b></p> <p>Division 6    Cumberland County    Fayetteville</p> <table border="1" style="width: 100%; border-collapse: collapse; font-size: x-small;"> <tr> <td>PLAN DATE: <b>March 2018</b></td> <td>REVIEWED BY: <b>L Overn</b></td> </tr> <tr> <td>PREPARED BY: <b>R M Muncey</b></td> <td>REVIEWED BY:</td> </tr> </table> <table border="1" style="width: 100%; border-collapse: collapse; font-size: x-small;"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	PLAN DATE: <b>March 2018</b>	REVIEWED BY: <b>L Overn</b>	PREPARED BY: <b>R M Muncey</b>	REVIEWED BY:	REVISIONS	INIT.	DATE				<p>SEAL</p> <div style="border: 1px solid black; border-radius: 50%; width: 60px; height: 60px; margin: 0 auto; display: flex; align-items: center; justify-content: center;"> <p style="font-size: 8px; text-align: center;">NORTH CAROLINA PROFESSIONAL ENGINEER LAURENCE E. OVERN</p> </div> <p style="font-size: 8px;">3/29/2018</p> <p style="font-size: 8px;">DATE</p> <p style="font-size: 8px;">SIG. INVENTORY NO. 06-0334T1</p>
PLAN DATE: <b>March 2018</b>	REVIEWED BY: <b>L Overn</b>												
PREPARED BY: <b>R M Muncey</b>	REVIEWED BY:												
REVISIONS	INIT.	DATE											

DATE: U:\Projects\Signal\Signal\Detail\Signal\Phase 1\U-4405\Sig\ele\_06-0334T1.dgn  
User: rlmuncey