

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

# CROSS SECTION SUMMARY SHEET

Note: Embankment does not include backfill for undercut.

Station	Uncl. Exc. (LT)	Undercut (LT)	Embt (LT)	Uncl. Exc. (CL)	Undercut (CL)	Embt (CL)	Uncl. Exc. (RT)	Undercut (RT)	Embt (RT)
-L-	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)
227+50.00	5		7				22		
228+00.00	6		9				25		
228+50.00	24		10				34		
229+00.00	65		10				20		1
229+50.00	47		4				23		
230+00.00							15		1
230+50.00	1		6				56		
231+00.00	19		7				92		
231+50.00	39		1				55		
232+00.00	28						35		
232+50.00	20						33		
233+00.00	23						17		1
233+50.00	21						16		1
234+00.00	17		3				9		6
234+50.00	19		3	3		3	8		6
235+00.00	25			6		10	13		4
235+50.00	25			5		15	15		8
236+00.00	22			4		18	15		17
236+50.00	22			4		19	16		14
237+00.00	21			3		19	14		8
237+50.00	14		2	3		20	10		15
238+00.00	8		6	3		21	6		24
238+50.00	6		7	2		22	3		45
239+00.00	8		4	1		24	4		65
239+50.00	8		6	1		26	3		74
240+00.00	8		8	2		24	2		68
240+50.00	10		4	3		21	3		46
241+00.00	16		1	5		16	7		30
241+50.00	22			6		11	9		34
242+00.00	18		1	5		7	15		11
242+50.00	14		1	5		4	15		10
243+00.00	14		2	3		2	15		14
243+50.00	18		1				13		13
244+00.00	24						10		12
244+50.00	15		8				13		10
245+00.00	7		9				13		3
245+50.00	13		2				19		1
246+00.00	13		2				18		1
246+50.00	10		5				17		1
247+00.00	6		3				16		
247+50.00							7		
248+00.00	9						10		10
248+50.00	19						19		10
249+00.00	21			2		4	22		
249+50.00	23			5		9	15		1
250+00.00	26		1	5		14	9		1
250+50.00	32			4		24	4		
251+00.00	37		1	3		21			
251+50.00	40		1	1		38			
252+00.00	22					33			
252+50.00	3								
253+00.00	7						3		2
253+50.00	7		1				6		4

Station	Uncl. Exc. (LT)	Undercut (LT)	Embt (LT)	Uncl. Exc. (CL)	Undercut (CL)	Embt (CL)	Uncl. Exc. (RT)	Undercut (RT)	Embt (RT)
-L-	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)
254+00.00	4		1					13	2
254+50.00	4		1					14	
255+00.00	6		1					4	2
255+50.00	8							1	7
256+00.00	10								22
256+50.00	20								16
257+00.00	20								2
257+50.00	18					30			61
258+00.00	23		3	1		55			30
258+50.00	24		5	2		44			91
259+00.00	29		4	3		36			87
259+50.00	25		17	3		34	1		83
260+00.00	22		34	3		32	3		37
260+50.00	32		66	2		27	8		12
261+00.00	35		49	2		22	13		2
261+50.00	29		6	1		16	12		
262+00.00	22		11	2		17	9		1
262+50.00	12		17	2		10	8		2
263+00.00	11		16				6		3
263+50.00	37		11				4		5
264+00.00	47		14				3		9
264+50.00	25		22				3		10
265+00.00	32		23				4		8
265+50.00	53		19				5		7
266+00.00	45		17				5		6
266+50.00	18		25				3		3
267+00.00			33						
267+50.00			23						
268+00.00	9		14					13	5
268+50.00	12		19					23	5
269+00.00	10		20					45	3
269+50.00	15		18					69	3
270+00.00	22		22					65	3
270+50.00	28		16					62	5
271+00.00	15		31					36	5
271+50.00	24		29					32	
272+00.00	48		1					10	3
272+50.00	54		1					13	4
273+00.00	49		1					14	2
273+50.00	38		1					14	3
274+00.00	21		8					18	1
274+50.00	2		15					8	4
275+00.00	9		17					17	1
275+50.00	16		21					6	4
276+00.00	10		26					4	11
276+50.00	5		33						22
277+00.00	5		38					1	14
277+50.00	3		38					1	17
278+00.00	2		34						40
278+50.00	1		29						44
279+00.00	2		22					1	36
279+50.00	5		15					2	27
280+00.00	9		7					3	19

Note: "Quantities are approximate only. The Resident Engineer will re-cross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid. The Embankment Column does not include backfill for Undercut"