


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)

1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2, and 3.
2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).



LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

OUTPUT REFERENCE SCHEDULE
OUTPUT 30 = Overlap C Red
OUTPUT 31 = Overlap C Yellow
OUTPUT 32 = Overlap C Green

Note: All outputs shown above have been remapped. See sheet 3 of this electrical detail.

OVERLAP PROGRAMMING DETAIL *(program controller as shown below)*

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).
PRESS '+' TWICE

```

PAGE 1: VEHICLE OVERLAP 'C' SETTINGS
PHASE:      |12345678910111213141516
VEH OVL PARENTS: |      XX
VEH OVL NOT VEH: |
VEH OVL NOT PED: |
VEH OVL GRN EXT: |
STARTUP COLOR:  | _ RED _ YELLOW _ GREEN
FLASH COLORS:   | _ RED _ YELLOW X GREEN
SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC)...0
YELLOW CLEAR (0=PARENT,3-25.5 SEC)...0.0
RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)...0
    
```

← NOTICE GREEN FLASH

OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 10-1619T2
DESIGNED: December 2017
SEALED: 04-23-2018
REVISED: N/A

Electrical Detail - Sheet 2 of 3
Signal Upgrade
Temporary Design 2

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

<p style="font-size: xx-small;">ELECTRICAL AND PROGRAMMING DETAILS FOR:</p> <p style="font-size: xx-small;">Prepared in the Office of:</p> <p style="font-size: xx-small;">750 N. Greenfield Pkwy, Corner, NC 27529</p>	<p style="font-weight: bold; font-size: small;">SR 2136 (Gilead Road) at I-77 NB Ramps</p> <p style="font-size: x-small;">Division 10 Mecklenburg Co. Huntersville</p> <p style="font-size: x-small;">PLAN DATE: December 2017 REVIEWED BY: A.D. Klinksiek</p> <p style="font-size: x-small;">PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="font-size: xx-small;">REVISIONS</th> <th style="font-size: xx-small;">INIT.</th> <th style="font-size: xx-small;">DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REVISIONS	INIT.	DATE				<p style="font-size: xx-small;">SEAL</p> <p style="font-size: xx-small;">DocuSigned by: <i>Natasha R. Simmons</i> 4/23/2018</p> <p style="font-size: xx-small;">SIGNATURE DATE</p>
REVISIONS	INIT.	DATE						
<p style="text-align: center;">HNTB HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997</p>		<p style="text-align: center;">SIG. INVENTORY NO. 10-1619 T2</p>						