PROJECT NO.	SHEET NO.	TOTAL NO.
I-5952_Resurfacing_FORSYTH	3B-3	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1577000000-E POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	1840000000-E MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	2099000000-E SHOULDER DRAIN	2110000000-E 4" SHOULDER DRAIN PIPE	2121000000-E 4" OUTLET PIPE FOR SHOULDER DRAINS	2286000000-N MASONRY DRAINAGE STRUCTURES	2308000000-E MASONRY DRAINAGE STRUCTURES	2407000000-N STEEL FRAME W/ TWO GRATES (STD. 840.37)	2703000000-E CONCRETE BARRIER, TYPE T1	2710000000-N CONCRETE BARRIER TRANSITION SECTION	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJ. OF METER OR VALVE BOX	2905000000-N CONVERT EX D.I. JUNCTION BOX	2910000000-N CONVERT EX T.B. D.I. TO T.B. JUNCTION BOX	3030000000-E STEEL BEAM GUARDRAIL	3210000000-N GUARDRAIL END UNITS, TYPE CAT 1	3317000000-N GUARDRAIL END UNITS, TYPE B-77	3360000000-E REMOVE EXISTING GUARDRAIL	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE
										MI	FT	TONS	LF	LF	LF	LF	EA	LF	EA	LF	EA	EA	EA		EA	LF	EA	EA	LF	LF	LF
I-5952_Resurfacing	Forsyth	1	I-40 EAST BOUND SURFACE ALL LANES INCLUDES SHOULDERS AND RAMPS AT LEWISVILLE-CLEMMONS RD. SR 1103	BEGIN APPROXIMATELY 1770' EAST OF HARPER RD. SR 1101 EASTERN RAMP GORE TO BRIDGE NO.448 APPROACH OVER WESTGATE CENTER DR.	1,2	3	MD	NO	NO	6.225	38	1,596	68,855									2	1							2,296	230
TOTAL FOR MAP NO. 1										**6.225**		**1,596**	**68,855**									**2**	**1**							**2,296**	**230**
I-5952_Resurfacing	Forsyth	2	I-40 EAST BOUND TRAVEL LANES ONLY I19.0C	BEGIN APPROXIMATELY 1770' EAST OF HARPER RD. SR 1101 EASTERN RAMP GORE TO BRIDGE NO.448 APPROACH OVER WESTGATE CENTER DR.	1,2	3	MD	NO	NO	6.225	24																						
TOTAL FOR MAP NO. 2										**6.225**																					
I-5952_Resurfacing	Forsyth	3	I-40 WEST BOUND SURFACE ALL LANES INCLUDES SHOULDERS AND RAMPS AT LEWISVILLE-CLEMMONS RD. SR 1103	BEGIN BRIDGE NO.449 OVER WESTGATE CENTER DR. TO APPROXIMATELY 1770' EAST OF EASTERN RAMP GORE TO HARPER RD. SR 1101	1,2	3	MD	NO	NO	6.226	44	1,819	65,685																	1,855	186
TOTAL FOR MAP NO. 3										**6.226**		**1,819**	**65,685**																	**1,855**	**186**
I-5952_Resurfacing	Forsyth	4	I-40 WEST BOUND TRAVEL LANES ONLY I19.0C	BEGIN BRIDGE NO.449 OVER WESTGATE CENTER DR. TO APPROXIMATELY 1770' EAST OF EASTERN RAMP GORE TO HARPER RD. SR 1101	1,2	3	MD	NO	NO	6.226	24																						
MEDIAN	Forsyth	5	MEDIAN WORK	MEDIAN	1	0	MD	NO	NO	1.246	13			1,180	1,180	50	35	22	67	5,735	6			1	1	630	1	1	13,850	200	
TOTAL FOR PROJ NO. I-5952_Resurfacing_FORSYTH												**3,415**	**134,540**	**1,180**	**1,180**	**50**	**35**	**22**	**67**	**5,735**	**6**	**2**	**1**	**1**	**1**	**630**	**1**	**1**	**13,850**	**4,351**	**416**
GRAND TOTAL										**6.226**		**3,415**	**134,540**	**1,180**	**1,180**	**50**	**35**	**22**	**67**	**5,735**	**6**	**2**	**1**	**1**	**1**	**630**	**1**	**1**	**13,850**	**4,351**	**416**

NOTE: All Quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities received.