

RAILROAD PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)


From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions).

PREEMPTION #1	SETTINGS (NEXT:1-10)
INTERVAL/TIMING	CLEAR/DWELL PHASES
GRN YEL RED	12345678910111213141516
1 31 5.1 1.0	X X
2 255 0.0 0.0	X X
3 0 0.0 0.0	
4 0 0.0 0.0	
5 1 0.0 0.0	X X

EXIT CALLS	OPTIONS
PRIORITY (Y/N TO SELECT)HIGH
DELAY TIMER (0-255 SEC)0
MIN GREEN BEFORE PRE (0= DEFAULT)	...1
PED CLEAR BEFORE PRE (0= DEFAULT)	...0
YELLOW CLEAR BEFORE PRE (0= DEFAULT)	..0
RED CLEAR BEFORE PRE (0= DEFAULT)	..0
DWELL MIN TIMER (0-255 SEC)12
DWELL MAX TIMER (0=OFF,1-255MIN)0
DWELL HOLD-OVER TIMER (0-255)0
LATCH CALL?N
LINK TO NEXT PREEMPT?N
ENABLE BACKUP PROTECTION?N
HOLD CLEAR 1 PHASES DURING DELAY?	...N
FAST GREEN FLASH DWELL PHASES?N
PED CLEARANCE THROUGH YELLOW?N
INHIBIT OVERLAP GREEN EXTENSION?	...N
SERVICE DURING SOFTWARE FLASH?N
REST IN RED DURING DWELL INTERVAL?	..N
FLASH DWELL INTERVAL?N
ALLOW PEDS IN DWELL INTERVAL?N
RE-TIME DWELL INTERVAL?N
OVERLAPS:ABCDEFGHIJKLMN
DWELL INT FLASH YELLOW
OMIT OVERLAPS:X

RAILROAD PREEMPTION WIRING DETAIL


(wire as shown below)



NOTES


- Relay K1 is shown in the energized (Preempt not active) normal operation state.
- Relay K1 is a DPDT with 120VAC coil with octal base.
- Relay SSR1 is a SPST (normally open) Solid State Relay with AC input and AC (25 amp) output.
- AC Isolator Card shall activate preemption upon removal of AC+ from the input (as shown above). To accomplish this set invert dip switch on AC Isolator Card.
- IMPORTANT!! A jumper must be added between input file terminals J14-E and J14-K if not already present. Also, terminal TB9-12 (on input panel) shall be connected to AC neutral (jumper may have to be added).

FRONT VIEW



PREEMPT 1 AC ISOLATOR (MODEL 252) OUTPUT PROGRAMMING DETAIL

(set DIP switches as shown below)



NOTE: IF ANOTHER MANUFACTURER TYPE OF AC ISOLATOR IS USED, OUTPUT PROGRAMMING IS LIKELY NOT TO EQUATE TO THAT SHOWN ABOVE.

This plan supersedes the one signed and sealed on 2/15/2017.

NC Dept of Transportation
Division of Highways
Final Drawing Date: 7/10/2018
R. N. Zinner
ITS & Signals Unit

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0196T1
DESIGNED: JULY 2018
SEALED: 7/10/2018
REVISED:

STV 100 Years
STV Engineers, Inc.
900 West Trade St., Suite 715
Charlotte, NC 28202
(704) 372-1885
NC License Number F-0991

SIGNAL UPGRADE - TEMPORARY ELECTRICAL DETAIL SHEET 3 OF 3

ELECTRICAL AND PROGRAMMING DETAILS FOR:
SR 1547 (Old Airport Road) / SR 1551 (Mills Gap Road) at SR 1545 (Cane Creek Road)
Division 14 Henderson County NE of Fletcher
PLAN DATE: July 2018 REVIEWED BY: R Dubnicka
PREPARED BY: J Trueblood REVIEWED BY: J Carroll

REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL
NORTH CAROLINA PROFESSIONAL ENGINEER
SEAL 030005
J. CARROLL
7/10/2018
SIG. INVENTORY NO. 14-0196T1