PROJ. REFERENCE NO.	SHEET NO.
U-5840	X-1B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, borrow excavation, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Phase II		
Station	Uncl. Exc.	Embt
L Right	(cu. yd.)	(cu. yd.)
12+18.43	0	0
12+50.00	9	0
13+00.00	9	10
13+50.00	17	30
14+00.00	14	45
14+50.00	7	55
15+00.00	2	66
15+50.00	5	71
16+00.00	5	118
16+50.00	9	91
17+00.00	22	9
17+50.00	35	1
18+00.00	47	0
18+50.00	51	0
19+00.00	33	13
19+50.00	12	20
20+00.00	8	16
20+50.00	8	18
21+00.00	5	29
21+50.00	0	56
22+00.00	2	52
22+50.00	3	15
23+00.00	7	14

Phase IV		
Station	Uncl. Exc.	Embt
L Left	(cu. yd.)	(cu. yd.)
12+00.00	0	0
12+18.43	9	3
12+50.00	23	10
13+00.00	19	16
13+50.00	9	15
14+00.00	5	25
14+50.00	2	37
15+00.00	0	38
15+50.00	0	35
16+00.00	7	33
16+50.00	26	30
17+00.00	44	24
17+50.00	51	20
18+00.00	54	15
18+50.00	48	13
19+00.00	21	24
19+50.00	7	32
20+00.00	11	41
20+50.00	19	60
21+00.00	18	109
21+50.00	5	141
22+00.00	2	76
22+50.00	11	10
23+00.00	26	0
23+50.00	32	0
24+00.00	42	0

Phase IV		
Station	Uncl. Exc.	Embt
L Left	(cu. yd.)	(cu. yd.)
24+50.00	72	0
25+00.00	65	0
25+50.00	25	0
26+00.00	25	0
26+50.00	39	0
27+00.00	27	1
27+50.00	10	30
28+00.00	9	44
28+50.00	10	38
29+00.00	11	34
29+50.00	17	10
30+00.00	21	0
30+50.00	20	2
31+00.00	13	10
31+50.00	8	8
32+00.00	6	24
32+50.00	5	39
33+00.00	10	27
33+50.00	9	37
34+00.00	5	49
34+50.00	6	38
35+00.00	9	19
35+50.00	13	24
36+00.00	13	39
36+50.00	6	78
37+00.00	4	92
37+50.00	9	50
38+00.00	10	34
38+50.00	9	37
39+00.00	8	33
39+50.00	7	14
40+00.00	3	6

Phase IV		
Station	Uncl. Exc.	Embt
L Left	(cu. yd.)	(cu. yd.)
40+00.00	0	0
40+50.00	4	44
41+00.00	7	61
41+50.00	10	44
42+00.00	11	44
42+50.00	10	56
43+00.00	14	51
43+50.00	19	28
44+00.00	13	26
44+50.00	8	22
45+00.00	24	7
45+50.00	27	0
46+00.00	14	1
46+50.00	10	34
47+00.00	4	80
47+50.00	4	95
48+00.00	6	97

Phase IV		
Station	Uncl. Exc.	Embt
L Left	(cu. yd.)	(cu. yd.)
48+50.00	11	49
49+00.00	13	5
49+50.00	11	5
50+00.00	11	7
50+50.00	10	18
51+00.00	10	18
51+50.00	7	16
52+00.00	2	25
52+50.00	0	33
53+00.00	11	72
53+50.00	12	170
54+00.00	5	251
54+50.00	9	236
55+00.00	16	176
55+50.00	19	135
55+94.70	12	89
56+00.00	0	0
56+04.70	0	0
56+50.00	5	130
57+00.00	4	128
57+50.00	5	64
58+00.00	6	74
58+40.00	5	58

Phase IV		
Station	Uncl. Exc.	Embt
L Left	(cu. yd.)	(cu. yd.)
59+30.00	0	0
59+50.00	2	1
60+00.00	4	1
60+50.00	4	0
61+00.00	6	2
61+50.00	7	5
62+00.00	6	6
62+50.00	5	8
63+00.00	4	7
63+50.00	2	6
64+00.00	5	5
64+50.00	5	1
65+00.00	5	0

Phase VI		
Station	Uncl. Exc.	Embt
L Right	(cu. yd.)	(cu. yd.)
65+50.00	0	0
66+00.00	1	0
66+50.00	1	0
67+00.00	1	0
67+50.00	1	0
68+00.00	1	0
68+50.00	1	0