



MAP 15  
 Rainey St. SR 2530  
 Faith Rd. SR 1006 to end of Curb and Gutter  
 Mill 1½" Depth  
 Pave back with 1½" S9.5B

From End of Curb and Gutter to Yates Rd. SR 2531  
 Mill 5½" Depth 3 ft. Each side,  
 2 ft. into existing pavement,  
 1 ft. of shoulder.  
 Pave 3 ft. widening with 5½" B25.0C  
 Overlay new width with 1½" S9.5B