PROJECT NO.	SHEET NO.	TOTAL NO.
2019CPT.12.01.10231, etc	12	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	PORTABLE LIGHTING	AGGREGATE SHOULDER BORROW	INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	1½" MILLING	3" - 5" MILLING	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	LEVELING COURSE, S9.5B	SURFACE COURSE, S9.5C	LEVELING COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MATCOAT, #6M STONE	EMULSION FOR ASPHALT SURFACE TREATMENT	ADJ. OF COMMUNICATIONS MANHOLES	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOXES	FRAME W/ GRATE & HOOD STD 840.03 TYPE	CONVERT EXISTING DROP INLET TO CATCH BASIN	JUNCTION BOX (STANDARD SIZE)	INDUCTIVE LOOP SAWCUT	LEAD-IN CABLE (14-2)
										MI	FT	LS	TON	TONS	SMI	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	SY	GAL	EA	EA	EA	EA	EA	EA	LF	LF
2019CPT.12.01.10231	Cleveland	1	NC 18 (FALLSTON RD)	END C&G TO 512' S OF SR 1800	8	2	2WU	NO	NO	5.03	24-61		1,900	360	10.06			330			7,238	1,087	500	1,530	85,628	34,251								
		2	NC 180 (S. POST ROAD)	NC 18 TO NC 226 / NC 180	1	2	2WU	NO	NO	3.56	21-33	1	1,246	106	7.12			500			4,724	232	297	897			1					1	550	250
		3	NC 182 (STAGECOACH TR)	NC 226 TO SR 1004	1 2	2 2	2WU	NO	NO	4.23 0.89	24-26 30-37		1,484	311	8.46		20,610	160			8,262	1,371	578	1,371			3			3	3	1	190	80
		4	NC 226 (EARL RD)	US 74 TO 790' N OF SR 2427 (TROUTMAN LN)	1 4	2 2	2WU	NO	NO	1.85 0.17	21-24 21-36	1	648	122	3.70	3,800		475			2,522	234	165	695								1	520	220
TOTAL FOR PROJ NO. 2019CPT.12.01.10231										**15.73**		**1**	**5,278**	**899**	**29.34**	**3,800**	**20,610**	**1,465**			**22,746**	**2,924**	**1,540**	**4,493**	**85,628**	**34,251**	**4**			**3**	**3**	**3**	**1,260**	**550**
2019CPT.12.01.20231	Cleveland	5	SR 1005 (BALL PARK RD)	NC 182 TO SR 1809 (EXCEPTING THAT 0.07 MILE PORTION WITHIN THE LIMITS OF NEW BRIDGE CONSTRUCTION)	1	2	2WU	NO	NO	2.45	20-22		882	150	4.90			210			2,779	197	179	465										
		6	SR 1614 (CARPENTER'S GROVE RD)	NC 18 TO SR 1621	1	2	2WU	NO	NO	4.31	20-21		1,509	259	8.62			500			4,912	741	339	786										
		7	SR 1621 (CARPENTER'S GROVE RD)	NC 10 TO SR 1614	1	2	2WU	NO	NO	0.59	20		207	19	1.18			75			644	97	44	97										
		8	SR 1645 (FLAT ROCK RD)	SR 1650 TO SR 1612	1	2	2WU	NO	NO	1.61	17-18		564	97	3.22			140			1,582	238	109	317										
		9	SR 1669 (CARPENTERS GROVE CH RD)	SR 1614 TO NC 18	1	2	2WU	NO	NO	0.05	20-21		18		0.10			70			57	3	4	8										
		10	SR 1808 (E. DOUBLE SHOALS RD)	NC 18 TO SR 1005	1	2	2WU	NO	NO	2.22	21-22		777	70	4.44			90			2,638	133	166	318										
		11	SR 1809 (W. DOULBLE SHOALS RD)	SR 1005 TO NC 226	1	2	2WU	NO	NO	3.31	19-22		1,159	198	6.62			600			3,629	291	235	762										
		12	SR 1810 (CHAMPION ST)	SR 1876 TO SR 1856	3	2	2WU	NO	NO	0.12	19			12					81	5			6	12										
		13	SR 1856 (OLD MILL RD)	SR 1809 TO DEAD END	1	2	2WU	NO	NO	0.47	19-20		165	89	0.94						464	42	30	84										
		14	SR 1857 (HOLY RD)	SR 1809 TO SR 1856	1	2	2WD	NO	NO	0.07	19-20		24		0.14						73	4	5	10										
		15	SR 1876 (MOSS RD)	SR 1809 TO SR 1856	1	2	2WU	NO	NO	0.19	17-18		67	23	0.38						186	10	12	21										
		16	SR 1908 (NEW PROSPECT CH RD)	NC 18 TO SR 1913	1	2	2WU	NO	NO	4.51	19-30		1,579	195	9.02			890			5,238	1,185	385	1,205										
		17	SR 1950 (WYKE RD)	NC 150 TO NC 18	1 5	2 2	2WU	NO	NO	0.87 0.16	24-37 30	1	304		1.74		3,098	910			1,727	170	114	298				3	4			1	490	200
		18	SR 2396 (STAR DR)	US 29 TO END MAINT	6	2	2WU	NO	NO	0.09	18			8					58	2			4	6										
		19	SR 2397 (SERVICE RD)	US 29 TO US 29	6	2	2WU	NO	NO	0.17	18			13					109	5			8	10										
		20	SR 2398 (SERVICE RD)	SR 2397 TO DEAD END	6	2	2WU	NO	NO	0.1	18			10					64	5			5	9										
		21	SR 2417 (N. MAIN ST.)	NC 226 TO SR 2233	7	2	2WU	NO	NO	0.24	18		42		0.24			120		10	236		14	20										
		22	SR 2698 (FAIRMONT DR.)	SR 2685 TO CULDESAC	6	2	2WU	NO	NO	0.2	18-20								142	36			12	28										
		23	SR 2313 (GAGE RD.)	I-85 ON-RAMP TO END PAVEMENT	1	2	2WU	NO	NO	0.5	18-19		235	30	1.00			70			505	130	38	101										
		24	SR 2390 (SERVICE RD.)	US 29 TO DEAD END	1	2	2WU	NO	NO	0.11	18		38		0.22						108	5	7	12										
TOTAL FOR PROJ NO. 2019CPT.12.01.20231										**22.34**		**1**	**7,570**	**1,173**	**42.76**		**3,098**	**3,675**	**454**	**63**	**24,778**	**3,246**	**1,716**	**4,569**				**3**	**4**			**1**	**490**	**200**
GRAND TOTAL										**38.07**		**1**	**12,848**	**2,072**	**72.10**	**3,800**	**23,708**	**5,140**	**454**	**63**	**47,524**	**6,170**	**3,256**	**9,062**	**85,628**	**34,251**	**4**	**3**	**4**	**3**	**3**	**4**	**1,750**	**750**