

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
1-5823	36-1

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

SURVEY LINE	BEG. STATION	END STATION	AGGREGATE TYPE ASU/AST	AGGREGATE THICKNESS (INCHES)	SHALLOW UNDERCUT (CUBIC YARDS)	CLASS IV SUBGRADE STABILIZATION (TONS)	GEOTEXTILE FOR SOIL STABILIZATION (SQ. YARDS)	STABILIZER AGGREGATE (TONS)	CLASS IV AGGREGATE STABILIZATION (TONS)
			ASU		12,900	17,200	26,300		
			AST					500	
			TOTALS		12,900	17,200	26,300	500	

*ASU = AGGREGATE SUBGRADE
 *AST = AGGREGATE STABILIZATION
 **TOTAL SQUARE YARDS OF "GEOTEXTILE FOR SOIL STABILIZATION" IS ONLY THE ESTIMATED QUANTITY FOR ASU/AST AND MAY ONLY REPRESENT A PORTION OF THE GEOTEXTILE QUANTITY SHOWN IN THE ITEM SHEETS OF THE PROPOSAL
 NOTE: UNDERCUT QUANTITY APPROXIMATES 1' DEPTH OF MATERIAL REMOVAL BELOW EXISTING DITCH LINE

I:\NOV_2018\Development\TIP_Projects\1-5823-140-Devie\Roadway\DesignFiles\5823.dde_30-1-geo.tech.dgn