PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.05.14.10921.1, etc.	18	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000 WK ZONE ADVANCE / GEN. WARNING SIGNING	4457000 TEMP. TRAFFIC CONTROL	4510 LAW ENFORCEMENT		4685000000-E 4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	4686000000-E 4" X 120 M YELLOW THERMO	4" X 120 M WHITE THERMO	4688000000-E 6" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	469000 6" X 120 M WHITE THERMO	469500 8" X 90 M YELLOW THERMO	4697000 8" X 120 M WHITE THERMO	4700000000 12" X 90 M WHITE THERMO	12" X 90 M YELLOW THERMO	470500 16" X 120 M WHITE THERMO	4710000 24" X 120 M WHITE THERMO	4721000000-E THERMO MSG ONLY 120 M	THERMO RXR 120 M	THERMO MSG BUS (120 MILS)	THERMO MSG LANE 120 M	THERMO MSG SCHOOL 120 M	4725000000-E THERMO LT ARROW 90	THERMO RT ARROW	THERMO STR & RT ARROW	THERMO STR ARROW 90 M	THERMO LT STR RT ARROW	THERMO STR & LT ARROW	THERMO LT & RT ARROW 90 M	4810000000-E 4" YELLOW PAINT	4" WHITE PAINT	4820000 8" WHITE PAINT	4835000 24" WHITE PAINT	4840000000-N PAINT MSG ONLY	PAINT MSG LANE	PAINT MSG SCHOOL	4845000000-N PAINT LT ARROW	PAINT STR & RT ARROW	PAINT LT STR RT ARROW	PAINT RT ARROW	PAINT STR ARROW	PAINT STR & LT ARROW	PAINT LT & RT ARROW	4905...-N SNOW PLOW. MARKERS
							MI	FT	SF	LS	HR		LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2020CPT.05.14.10921.1	Wake	1	US 264A	NC 39 - JOHNSTON CO.	1	2	0.53	22	74				5,189		5,628	115									40						2							5,628	115		40				2								60
		2	NC 39	JOHNSTON CO - US 264A	2	3	0.67	38	75	*			6,496		5,084	1,111				64				100	91	12	4				8	3																						130
TOTAL FOR PROJ NO. 2020CPT.05.14.10921.1							1.2		149				11,685		10,712	1,226				64				100	131	12	4				10	3						5,628	115		40				2								190
													11,685		11,938													16										5,743							2							
2020CPT.05.14.10922.1	Wake	3	US 64	SR 1003 (ROLESVILLE RD) - US 64 BUS - WEST BOUND LANE	3	3	0.43	44	48	*							2,052	2,245	1,904			865															2,245	2,051														140
TOTAL FOR PROJ NO. 2020CPT.05.14.10921.1																	4,297					865															4,296															
		4	SR 2216 (RALEIGH BEACH RD)	SR 2293 (CARP RD) - END OF MAINTENANCE/ALLEN DR	4	2	0.75	32	84				5,079		5,101	42									25																													
		5	SR 2387 (E JUDD ST)	US 64 BUS - SR 2406 (SHEPARD SCHOOL RD)	5	2	0.3	24	34				2,787																																									
		6	SR 2397 (RIVERVIEW DR)	NC 97 - DEAD END	6	2	0.36	20	40																																													
		7	SR 2398 (TEDDY LN)	SR 2397 (RIVERVIEW DR) - SR 2399 (SAN PADEE DR)	6	2	0.05	21	6																																													
		8	SR 2399 (SAN PADEE DR)	NC 97 - SR 2398 (TEDDY LN)	6	2	0.15	24	17																																													
		9	SR 2400 (DEBBIE LN)	SR 2399 (SAN PADEE DR) - DEAD END	6	2	0.06	23	7																																													
		10	SR 2404 (OLD US 264)	NC 97 - NC 39	1	2	1.65	25	185			40	17,318		16,557								29		61													16,557			61														
		11	SR 2421 (WINCHESTER DR)	SR 2321 (RILEY HIGH SCHOOL RD) - CUL-DE-SAC	7	2	0.75	20	84																																													
		12	SR 2538 (MECHANICAL BLVD)	SR 4753 (OLD MECHANICAL CT) - US 70	8	3	0.36	28	43			40	3,031		4,020	294				164					40							11		2					4,020	294		40				11	2							
		13	SR 2548 (AUBURN CHURCH RD)	SR 5220 (JONES SAUSAGE RD) - SR 5225 (G ST) - SKIP FIRST 450 FT FROM SR 5220	5, 9	3	1.71	28	192			40	16,577		18,933	389							127									29			1																				
		14	SR 2576 (DANIEL CIR)	SR 2516 (HODGE RD) - SR 2516 (HODGE RD)	1	2	0.28	18	31																																													
		15	SR 2589 (WESTOVER DR)	JOINT BEFORE US 64 BUS - SR 2593 (WHITFIELD ST)	7	2	0.37	20	41				196		114										29										1				114			29						1							
		16	SR 2590 (SATTERWHITE DR)	SR 2516 (HODGE RD) - SR 2589 (WESTOVER DR)	13	2	0.5	20	56																																													
		17	SR 2591 (HINTON ST)	SR 2590 (SATTERWHITE DR) - SR 2593 (WHITFIELD)	7	2	0.2	22	22																																													
		18	SR 2592 (GREEN ST)	SR 2516 (HODGE RD) - SR 2591 (HINTON ST)	7	2	0.13	20	15																																													
		19	SR 2593 (WHITFIELD ST)	SR 2516 (HODGE RD) - SR 2589 (WESTOVER DR)	7	2	0.33	20	37																																													
		20	SR 2603 (KIRVIN CT)	SR 2590 (SATTERWHITE DR) - CUL-DE-SAC	13	2	0.11	23	12																																													
		21	SR 2610 (POOLE CT)	SR 2593 (WHITFIELD ST) - CUL-DE-SAC	13	2	0.13	21	15																																													
		22	SR 2611 (DEAN PL)	SR 2610 (POOLE CT) - CUL-DE-SAC	13	2	0.13	21	15																																													
		23	SR 2624 (ALLEN CT)	SR 2589 (WESTOVER DR) - CUL-DE-SAC	13	2	0.06	26	7																																													
		24	SR 2627 (ALLISON DR)	SR 2589 (WESTOVER DR) - SR 2658 (MILBURNIE RD)	13	2	0.27	20	30																																													
		25	SR 2628 (SCOTT CT)	SR 2627 (ALLISON DR) - CUL-DE-SAC	13	2	0.05	30	6																																													
		26	SR 2658 (MILBURNIE RD)	SR 2627 (ALLISON DR) - SR 4164 (CLIFFVIEW DR)	13	2	0.19	20	21																																													
		27	SR 2663 (GRAYSON CT)	SR 2627 (ALLISON DR) - CUL-DE-SAC	13	2	0.11	23	12																																													
		28	SR 2674 (MEADOW RUN)	SR 2233 (S SMITHFIELD RD) - SR 4133 (WALTON HILL RD)	10	2	0.8	21	90																																													
		29	SR 2675 (N BEND DR)	CUL-DE-SAC - CUL-DE-SAC	16	2	0.38	22	43																																													
		30	SR 2685 (SANDY RUN)	SR 2233 (S SMITHFIELD RD) - END OF MAINTENANCE AT MAILBOX #5951	17	2	0.72	21	81																																														
		31	SR 2685 (SANDY RUN)	SR 2689 (PINE RUN) - SR 2233 (S SMITHFIELD RD)	16	2	0.55	23	62																																														
		32	SR 2686 (COY PL)	SR 2685 (SANDY RUN) - CUL-DE-SAC	16	2	0.04	30	4																																														
		33	SR 2687 (S BEND DR)	SR 2685 (SANDY RUN) - CUL-DE-SAC	16	2	0.3	26	34																																														
		34	SR 2688 (LINK RD)	SR 2675 (N BEND DR) - SR 2685 (SANDY RUN)	16	2	0.09	20	10																																														
		35	SR 2689 (PINE RUN)	SR 2685 (SANDY RUN) - SR 4118 (DWELLING PL)	16	2	0.28	20	31																																														
		36	SR 2690 (WOODS RUN)	CUL-DE-SAC - CUL-DE-SAC	16	2	0.42	22	47																																														
		37	SR 2695 (BLALOCK CT)	SR 2590 (SATTERWHITE DR) - CUL-DE-SAC	20	2	0.04	31	4																																														
		38	SR 2715 (WOODLAND RD)	SR 2812 (TIMBER DR) - SR 2713 (VANDORA SPRINGS RD)	11	2	0.68	29	76				3,871		5,992	183										4						1			2																						
		39	SR 4118 (DWELLING PL)	CUL-DE-SAC - CUL-DE-SAC	16	2	0.2	26	22																																														
		40	SR 4133 (WALTON HILL RD)	SR 2233 (S SMITHFIELD RD) - SR 2674 (MEADOW RUN)	10	2	0.74	21	83																																														
		41	SR 4134 (RENEE CT)	SR 4133 (WALTON HILL RD) - CUL-DE-SAC	10	2	0.08	28	9																																														
		42	SR 4135 (RANCO RUN)	SR 4133 (WALTON HILL RD) - CUL-DE-SAC	10	2	0.03	34	3																																														
		43	SR 4137 (FAIRBLUFF LN)	SR 4133 (WALTON HILL RD) - CUL-DE-SAC	10	2	0.04	33	4																																														
2020CPT.05.14.20921.1	Wake	44	SR 4144 (LANTIS LN)	SR 4133 (WALTON HILL RD) - CUL-DE-SAC	10	2	0.03	38	3	*																																														
		45	SR 4145 (BONAIRE WAY)	SR 2674 (MEADOW RUN) - SR 2685 (SANDY RUN)	7	2	0.34	21	38																																															
		46	SR 4146 (WINDWARD PAGE)	SR 4145 (BONAIRE WAY) - DEAD END	7	2	0.38	22	43																																															
		47	SR 4147 (MARGARITA LN)	SR 4146 (WINDWARD PAGE) - CUL-DE-SAC	7	2	0.18	23	20																																															
		48	SR 4148 (ANTIGUA RUN)	SR 4146 (WINDWARD PAGE) - SR 5241 (AMBER ACRES LN)	7	2	0.16	22	18																																															
		49	SR 4149 (JENNIFER CT)	SR 2674 (MEADOW RUN) - CUL-DE-SAC	7	2	0.16	24	18																																															
		50	SR 4150 (ARUBA CT)	SR 2685 (SANDY RUN) - CUL-DE-SAC	17	2	0.15	23	17																																															
		51	SR 4151 (ROCKPORT PL)	SR 4152 (BERMUDA RUN) - CUL-DE-SAC	7	2	0.1	26	11																																															
		52	SR 4152 (BERMUDA RUN)	SR 2674 (MEADOW RUN) - SR 2685 (SANDY RUN)	7	2	0.36	22	127																																															
		53	SR 4164 (CLIFFVIEW DR)	SR 4165 (THOMAS PL) - CUL-DE-SAC	13	2	0.19	25	21																																															
		54	SR 4165 (THOMAS PL)	SR 4164 (CLIFFVIEW DR) - CUL-DE-SAC	13	2	0.08	25	9																																															
		55	SR 4182 (COVINGTON CROSS DR)	SR 2233 (S SMITHFIELD RD) - SR 4194 (TROUBADORE LN)	15	2	0.34	30	38																																																
		56	SR 4183 (DAMES CT)	SR 4182 (N IVY DR) - CUL-DE-SAC	14	2	0.03	23	3																																																
		57	SR 4184 (MOAT CT)	SR 4182 (COVINGTON CROSS DR) - CUL-DE-SAC	15	2	0.03	42	3																																																
		58	SR 4185 (ROUNDTABLE CT)	SR 4182 (COVINGTON CROSS DR) - CUL-DE-SAC	15	2	0.1	28	11																																																
		59	SR 4186 (SORCERER CT)	SR 4182 (COVINGTON CROSS DR) - CUL-DE-SAC	14	2	0.06	30	7																																																
		60	SR 4187 (KILT CT)	SR 4182 (COVINGTON CROSS DR) - CUL-DE-SAC	15	2	0.03	35	3																																																
		61	SR 4189 (AMBERSTONE DR)	SR 2685 (SANDY RUN) - CUL-DE-SAC	16	2	0.06	22	7																																																
		62	SR 4191 (HENCHMAN CT)	SR 4182 (COVINGTON CROSS DR) - CUL-DE-SAC	15	2	0.11	26	12																																																
		63	SR 4193 (MEDIEVAL CT)	SR 4191 (HENCHMAN CT) - CUL-DE-SAC	14	2	0.08	28	9																																																
		64	SR 4194 (TROUBADORE LN)	DEAD END - SR 5251 (FRIARWOOD WAY)	15	2	0.36	24	40																																																
		65	SR 4195 (CHIVALRY CT)	SR 4194 (TROUBADORE LN) - CUL-DE-SAC	14	2	0.03	36	3																																																
		66	SR 4196 (SWORDSMAN CT)	SR 4194 (TROUBADORE LN) - CUL-DE-SAC	15	2	0.06	30	7																																																
		67	SR 4197 (HERALDY)	SR 4194 (TROUBADORE LN) - CUL-DE-SAC	15	2	0.03	39	3																																																
		68	SR 4746 (CENTENNIAL PKWY)	SR 1321 (AVENT FERRY RD) - SR 1009 (LAKE WHEELER RD) - SKIP NEW PAVEMENT	18	4	1.87	67	419			240			3,891	6,224					1,930				3,787	16		12	16		31	12	2	30		6		3,891	6,224	1,930	3,787	28	16		31	2		12	30	6			
		69	SR 4753 (OLD MECHANICAL CT)	SR 2538 (MECHANICAL BLVD) - END OF MAINTENANCE	5	2	0.21	34	19				2,212		2,849	89				142											2		2																						
		70	SR 5218 (ROCKWOOD DOWNS DR)	SR 2505 (LAKE MYRA RD) - CUL-DE-SAC	7	2	0.42	21	47																																																
		71	SR 5219 (JONATHAN DR)	BEGIN MAINTENANCE - DEAD END	7	2	0.34	18	38																																																
		72	SR 5228 (JOUSTER PL)	SR 4194 (TROUBADORE LN) - CUL-DE-SAC	10	2	0.02	46	2																																																
		73	SR 5229 (SCABBARD)	SR 4194 (TROUBADORE LN) - CUL-DE-SAC	10	2	0.03	35	3																																																
		74	SR 5230 (NOBLEMAN TR)	CUL-DE-SAC - CUL-DE-SAC	10	2	0.27	22	30																																																
		75	SR 5231 (KNIGHTHOOD LN)	SR 5230 (NOBLEMAN TR) - DEAD END	17	2	0.07	19	8																																																
		76	SR 5232 (LEE CT)	SR 4164 (CLIFFVIEW DR) - CUL-DE-SAC	1	2	0.04	26	4																																																
		77	SR 5233 (OLD POOLE RD)	SR 1007 (POOLE RD) - SR 1007 (POOLE RD)	12	2	1	30	112			80	7,728		9,802	421									104						4			2	2	2	9,802	421		104						2	4		2	2	
		78	SR 5241 (AMBER ACRES LN)	SR 4148 (ANITGUA RUN) - CUL-DE-SAC	17	2	0.54	21	60																																																
		79	SR 5242 (HATCH ST)	SR 5241 (AMBER ACRES LN) - SR 5243 (SPAWN PL)	17	2	0.09	24	10																																																
		80	SR 5243 (SPAWN PL)	CUL-DE-SAC - CUL-DE-SAC	17	2	0.16	26	18																																																
		81	SR 5244 (WOOF PL)	SR 5241 (AMBER ACRES LN) - CUL-DE-SAC	17	2	0.2	26	11																																																
		82	SR 5245 (PRESENTATION ST)	SR 5241 (AMBER ACRES LN) - SR 5260 (BALLSTON PL)	17	2	0.66	21	74																																																	
		83	SR 5250 (MYLADY CT)	SR 4194 (TROUBADORE LN) - CUL-DE-SAC	10	2	0.02	34	4																																																	
		84	SR 5251 (FRIARWOOD WAY)	SR 4194 (TROUBADORE LN) - CUL-DE-SAC	10	2	0.04	33	4																																																	
		86	SR 2355 (THIRD ST)	SR 1007 (WENDELL FALLS PKWY) - SR 2353 (MORPHUS BRIDGE RD)	12	2	1.19	31	134			40	4,150	3,560	12,362						236				207					6								15,922	4,150	236	207			6											
TOTAL FOR PROJ NO. 2020CPT.05.14.20921.1							25.01		3,083			480	62,949	3,560	79,621	7,642				306	2,166		156		4,253	20		12	16	6	73	17	6	31	3	10	2	50,306	11,089	2,166	4,228	28	16	6	42	4	3	16	30	8	2	
													66,509		87,263								156					54					142				61,395					50				105					
TOTAL FOR 5C.092140	Wake	85	SR 1003 (EAGLE ROCK RD)	SR 1007 (POOLE RD) - JOHNSTON CO.	19	2	2.14	4	240	*																																														
GRAND TOTAL							28.78		3,520	1		480	74,634	3,560	90,333	8,868	2,052	2,245	1,904	370	2,166	865	156	100	4,384	32	4	12	16	6	83	20	6	31	3	10	2	58,179	13,255	2,166	4,268	28	16	6	44	4	3	16	30	8	2	330
													78,194		99,201		4,297					1,021					70					155				71,434					50				107					