PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.10.09.10041, 2020CPT.10.09.20041 2020CPT10.09.20042	15	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	1176000000-E SOIL CEMENT BASE (FDR)	1187000000-E PORTLAND CEMENT FOR SOIL CEMENT BASE	1220000000-E INCIDENTAL STONE BASE	1243000000-E SHOULDER CONSTRUCTION	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1503000000-E INTERMEDIATE COURSE, I19.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1524000000-E LEVELING COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX
										MI	FT	CY	SY	TON	TON	SMI	SMI	SY	SY	SY	TON	TON	TON	TON	TON	TON
2020CPT.10.09.10041	Anson	1	US 52 NORTH ROUTE 20000052	FROM PAVEMENT JOINT AT SR 1641 BROWN CREEK CHURCH ROAD TO PAVEMENT JOINT 2050 FEET SOUTH OF SR 1649 DENNIS ROAD **MILEPOST 15.8 TO 19.2**	1	2	2WU	NO	NO	3.4	30	1,385			125		6.80			600				6,105	1,360	455
TOTAL FOR MAP NO. 1										**3.4**		**1,385**			**125**		**6.80**			**600**				**6,105**	**1,360**	**455**
2020CPT.10.09.10041	Anson	2	US 74 ROUTE 20000052	FROM US 52 NORTH TO SR 1423 KITTY BENNETT ROAD **MILEPOST 14.62 TO 15.15**	2	3	MU	NO	NO	0.53	66							20,945						1,935		116
TOTAL FOR MAP NO. 2										**0.53**								**20,945**						**1,935**		**116**
TOTAL FOR PROJ NO. 2020CPT.10.09.10041										**3.93**		**1,385**			**125**		**6.80**	**20,945**		**600**				**8,040**	**1,360**	**571**
2020CPT.10.09.20041	Anson	3	SR 1220 LONG PINE CHURCH ROAD ROUTE 40001220	FROM SR 1217 LITTLE HUNTLEY ROAD TO NC 109 SOUTH **MILEPOST 0 TO 2.9**	3	2	2WU	NO	NO	2.9	20	300			25		5.80			240			2,095			140
TOTAL FOR MAP NO. 3										**2.9**		**300**			**25**		**5.80**			**240**			**2,095**			**140**
2020CPT.10.09.20041	Anson	4	SR 1003 DEEP CREEK ROAD ROUTE 40001003	FROM SR 1113 CEDAR CREEK ROAD TO NC 742 SOUTH **MILEPOST 11.22 TO 14.21**	5	2	2WU	NO	NO	3	20	280			200		6.00			380	2,200			3,475	1,125	381
TOTAL FOR MAP NO. 4										**3**		**280**			**200**		**6.00**			**380**	**2,200**			**3,475**	**1,125**	**381**
2020CPT.10.09.20041	Anson	5	SR 1400 OLD US 74 ROUTE 40001400	FROM US 74 TO UNION COUNTY LINE **MILEPOST 0-0.4**	6,7	2	2WU	NO	NO	0.44	27.5	260			100	0.10	0.60		70	460	270	995		585		95
TOTAL FOR MAP NO. 5										**0.44**		**260**			**100**	**0.10**	**0.60**		**70**	**460**	**270**	**995**		**585**		**95**
2020CPT.10.09.20041	Anson	6	SR 1403 PASSIAC STREET ROUTE 40001403	FROM US 74 TO SR 1240 CLINTON AVENUE **MILEPOST 0.99-1.64**	4,8,9	2	2WU	NO	NO	0.65	32.5	85			65		1.10		834	560				915	270	72
TOTAL FOR MAP NO. 6										**0.65**		**85**			**65**		**1.10**		**834**	**560**				**915**	**270**	**72**
2020CPT.10.09.20041	Anson	7	SR 1401 PULPWOOD YARD ROAD ROUTE 40001401	FROM SR 1404 GERMAN HILL ROAD TO SR 1400 OLD US 74 **MILEPOST 0 TO 0.9**	6	2	2WU	NO	NO	0.9	24	355			125		1.70			400		1,915		1,130		160
TOTAL FOR MAP NO. 7										**0.9**		**355**			**125**		**1.70**			**400**		**1,915**		**1,130**		**160**
TOTAL FOR PROJ NO. 2020CPT.10.09.20041										**7.89**		**1,280**			**515**	**0.10**	**15.20**		**904**	**2,040**	**2,470**	**2,910**	**2,095**	**6,105**	**1,395**	**848**
2020CPT.10.09.20042	Anson	3	SR 1220 LONG PINE CHURCH ROAD ROUTE 40001220	FROM SR 1217 LITTLE HUNTLEY ROAD TO NC 109 SOUTH **MILEPOST 0 TO 2.9**	3	2	2WU	NO	NO	2.9	20		37,296.00	1,305.00												
TOTAL FOR MAP NO. 3										**2.9**			**37,296.00**	**1,305.00**												
TOTAL FOR PROJ NO. 2020CPT.10.09.20042										**2.9**			**37,296.00**	**1,305.00**												
GRAND TOTAL										**14.72**		**2,665**	**37,296.00**	**1,305.00**	**640**	**0.10**	**22.00**	**20,945**	**904**	**2,640**	**2,470**	**2,910**	**2,095**	**14,145**	**2,755**	**1,419**