PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.10.09.10041, 2020CPT.10.09.20041 2020CPT10.09.20042	16	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1704000000-E PATCHING EXISTING PAVEMENT	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	1803500000-E ASPHALT SURFACE TREATMENT, DOUBLE SEAL	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1838500000-N VACUUM TRUCK	2600000000-N RETROFIT EXISTING CURB RAMP	2612000000-E 6" DRIVEWAYS	2845000000-N ADJ. OF METER OR VALVE BOX	5255000000-N PORTABLE LIGHTING	6000000000-E TEMPORARY SILT FENCE	6009000000-E STONE FOR EROSION CONTROL, CLASS B	6012000000-E SEDIMENT CONTROL STONE	6071010000-E WATTLE	6071020000-E POLYACRYLAMIDE (PAM)
										MI	FT	TON	SY	SY	GAL	WK	EA	SY	EA	LS	LF	TON	TON	LF	LB
2020CPT.10.09.10041	Anson	1	US 52 NORTH ROUTE 20000052	FROM PAVEMENT JOINT AT SR 1641 BROWN CREEK CHURCH ROAD TO PAVEMENT JOINT 2050 FEET SOUTH OF SR 1649 DENNIS ROAD **MILEPOST 15.8 TO 19.2**	1	2	2WU	NO	NO	3.4	30	1,700	49,415		19,390	0.60		100	1		510	68	34	510	1
TOTAL FOR MAP NO. 1										**3.4**		**1,700**	**49,415**		**19,390**	**0.60**		**100**	**1**		**510**	**68**	**34**	**510**	**1**
2020CPT.10.09.10041	Anson	2	US 74 ROUTE 20000052	FROM US 52 NORTH TO SR 1423 KITTY BENNETT ROAD **MILEPOST 14.62 TO 15.15**	2	3	MU	NO	NO	0.53	66	240								1					
TOTAL FOR MAP NO. 2										**0.53**		**240**								**1**					
TOTAL FOR PROJ NO. 2020CPT.10.09.10041										**3.93**		**1,940**	**49,415**		**19,390**	**0.60**		**100**	**1**	**1**	**510**	**68**	**34**	**510**	**1**
2020CPT.10.09.20041	Anson	3	SR 1220 LONG PINE CHURCH ROAD ROUTE 40001220	FROM SR 1217 LITTLE HUNTLEY ROAD TO NC 109 SOUTH **MILEPOST 0 TO 2.9**	3	2	2WU	NO	NO	2.9	20										870	87	44	870	2
TOTAL FOR MAP NO. 3										**2.9**											**870**	**87**	**44**	**870**	**2**
2020CPT.10.09.20041	Anson	4	SR 1003 DEEP CREEK ROAD ROUTE 40001003	FROM SR 1113 CEDAR CREEK ROAD TO NC 742 SOUTH **MILEPOST 11.22 TO 14.21**	5	2	2WU	NO	NO	3	20	1,200						25			900	90	45	900	2
TOTAL FOR MAP NO. 4										**3**		**1,200**						**25**			**900**	**90**	**45**	**900**	**2**
2020CPT.10.09.20041	Anson	5	SR 1400 OLD US 74 ROUTE 40001400	FROM US 74 TO UNION COUNTY LINE **MILEPOST 0-0.4**	6,7	2	2WU	NO	NO	0.44	27.5	240						125			60	8	4	60	
TOTAL FOR MAP NO. 5										**0.44**		**240**						**125**			**60**	**8**	**4**	**60**	
2020CPT.10.09.20041	Anson	6	SR 1403 PASSIAC STREET ROUTE 40001403	FROM US 74 TO SR 1240 CLINTON AVENUE **MILEPOST 0.99-1.64**	4,8,9	2	2WU	NO	NO	0.65	32.5	200					1		1		100	14	7	100	
TOTAL FOR MAP NO. 6										**0.65**		**200**					**1**		**1**		**100**	**14**	**7**	**100**	
2020CPT.10.09.20041	Anson	7	SR 1401 PULPWOOD YARD ROAD ROUTE 40001401	FROM SR 1404 GERMAN HILL ROAD TO SR 1400 OLD US 74 **MILEPOST 0 TO 0.9**	6	2	2WU	NO	NO	0.9	24	700							1		130	18	9	130	
TOTAL FOR MAP NO. 7										**0.9**		**700**							**1**		**130**	**18**	**9**	**130**	
TOTAL FOR PROJ NO. 2020CPT.10.09.20041										**7.89**		**2,340**					**1**	**150**	**2**		**2,060**	**217**	**109**	**2,060**	**4**
2020CPT.10.09.20042	Anson	3	SR 1220 LONG PINE CHURCH ROAD ROUTE 40001220	FROM SR 1217 LITTLE HUNTLEY ROAD TO NC 109 SOUTH **MILEPOST 0 TO 2.9**	3	2	2WU	NO	NO	2.9	20			33,905	18,650	0.40									
TOTAL FOR MAP NO. 3										**2.9**				**33,905**	**18,650**	0.40									
TOTAL FOR PROJ NO. 2020CPT.10.09.20042										**2.9**				**33,905**	**18,650**	**0.40**									
GRAND TOTAL										**14.72**		**4,280**	**49,415**	**33,905**	**38,040**	**1.00**	**1**	**250**	**3**	**1**	**2,570**	**285**	**143**	**2,570**	**5**