PROJECT NO.	SHEET NO.	TOTAL NO.
2019CPT.08.04.10191		
2019CPT.08.04.10191	18	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 2.5" MILLING	1297000000-E 1.5" MILLING	1297000000-E 2" MILLING	1308000000-E 0" TO 1.5" MILLING	1308000000-E 0" TO 2" MILLING	1330000000-E INCIDENTAL MILLING	1503000000-E INTERMEDIATE COURSE, I19.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #78 STONE	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1840000000-E MILLED RUMBLE STRIPS	1838500000-N VACUUM TRUCK
										MI	FT	SMI	TON	SY	SY	SY	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	SY	SY	GAL	LF	WK
TOTAL FOR MAP NO. 29										**1.576**		**3.15**	**441**						**111**		**1,410**		**94**	**40**					
2019CPT.08.04.20191	Chatham	30	SR 1954 (GADE BRYANT RD.)	FROM SR 1955 (MTN VIEW CHURCH RD) TO END MAINTANCE	21	2		NO	NO	1.84	20	3.68	515						56		1,645		110	200					
TOTAL FOR MAP NO. 30										**1.84**		**3.68**	**515**						**56**		**1,645**		**110**	**200**					
2019CPT.08.04.20191	Chatham	31	SR 1956 (E. GARGUS RD.)	FROM SR 1955 (MTN VIEW CHURCH RD.) TO END MAINTANCE	20	2		NO	NO	1.505	20	3.01	421						56		1,345		90	10					
TOTAL FOR MAP NO. 31										**1.505**		**3.01**	**421**						**56**		**1,345**		**90**	**10**					
2019CPT.08.04.20191	Chatham	32	SR 1910 (NEW ELAM CHURCH RD.)	FROM SR 1011 (OLD US 1) TO SR 1972 (PEA RIDGE RD.)	20	2		NO	NO	2.52	20	5.04	706						333		2,250		151	5					
TOTAL FOR MAP NO. 32										**2.52**		**5.04**	**706**						**333**		**2,250**		**151**	**5**					
2019CPT.08.04.20191	Chatham	33	SR 1520 (RUSSELLS CHAPEL RD.)	FROM SR 1545 (CHICKEN BRIDGE RD.) TO SR 1516 (OLD GRAHAM RD)	21	2		NO	NO	5.002	22	10.00	1,401						978		8,300		556	200					
TOTAL FOR MAP NO. 33										**5.002**		**10.00**	**1,401**						**978**		**8,300**		**556**	**200**					
2019CPT.08.04.20191	Chatham	34	SR 1520 (RUSSELLS CHAPEL RD.)	FROM SR 1516 (OLD GRAHAM RD.) TO US 15/501	21	2		NO	NO	2.184	20	4.37	612						111		2,340		157	100					
TOTAL FOR MAP NO. 34										**2.184**		**4.37**	**612**						**111**		**2,340**		**157**	**100**					
2019CPT.08.04.20191	Chatham	35	SR 2225 (ROBERSON RD.)	FROM US 64 BUS. TO SR 2226 (REAVES RD.)	23	2		NO	NO	0.58	19	1.16	162						53		495		33	40		6,470.00	2,588		
TOTAL FOR MAP NO. 35										**0.58**		**1.16**	**162**						**53**		**495**		**33**	**40**		**6,470.00**	**2,588**		
2019CPT.08.04.20191	Chatham	36	SR 2226 (REAVES RD.)	FROM SR 2225 ROBERSON RD.) TO END MAINTANCE	20	2		NO	NO	0.159	19	0.32	45								135		9	10					
TOTAL FOR MAP NO. 36										**0.159**		**0.32**	**45**								**135**		**9**	**10**					
2019CPT.08.04.20191	Chatham	37	SR 1557 (EPPS CLARK RD.)	FROM SR 1506 (WHITE SMITH RD.) TO SR 1556 (IRVING LINDLEY RD.)	20	2		NO	NO	0.998	20	2.00	279						111		890		60	50					
TOTAL FOR MAP NO. 37										**0.998**		**2.00**	**279**						**111**		**890**		**60**	**50**					
2019CPT.08.04.20191	Chatham	38	SR 1557 (EPPS CLARK RD.)	FROM SR 1556 (IRVING LINDLEY RD.) TO SR 1003 (SH LINDLEY MILL RD.)	19	2		NO	NO	2.205	18	4.41	617						25		1,775		119	50	23,300.00		8,200		
TOTAL FOR MAP NO. 38										**2.205**		**4.41**	**617**						**25**		**1,775**		**119**	**50**	**23,300.00**		**8,200**		
2019CPT.08.04.20191	Chatham	39	SR 1132 (JOE BROWN RD.)	FROM SR 1133 (WILDLIFE RD.) TO SR 1130 (OAKLEY CHURCH RD.)	24	2		NO	NO	1.52	20	3.04	426						100		2,180		147	10		17,900.00	7,160		
TOTAL FOR MAP NO. 39										**1.52**		**3.04**	**426**						**100**		**2,180**		**147**	**10**		**17,900.00**	**7,160**		
2019CPT.08.04.20191	Chatham	40	SR 1132 (JOE BROWN RD.)	FROM SR 1006 (SC GLENDON RD.) TO SR 1133 (WILDLIFE RD.)	23	2		NO	NO	0.831	20	1.66	233						111		745		50			9,800.00	3,920		
TOTAL FOR MAP NO. 40										**0.831**		**1.66**	**233**						**111**		**745**		**50**			**9,800.00**	**3,920**		*
TOTAL FOR PROJ NO. 2019CPT.08.04.20191										**49.046**		**98.09**	**13,736**		**80,989**				**4,996**		**53,280**		**3,645**	**3,225**	**71,300.00**	**60,170.00**	**47,606**		
															80,989														
GRAND TOTAL										**73.785**		**147.57**	**17,548**	**15,700**	**476,439**	**21,140**	**180**	**610**	**14,230**	**900**	**56,870**	**44,430**	**6,594**	**4,885**	**71,300.00**	**60,170.00**	**47,606**	**71,700**	**7**