



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

February 11, 2019

Addendum No. 2

RE: Contract # C204286

WBS # 45930.3.1, Etc.

STBGIM-0040(090), NHPIM-0040(085)

Haywood County (I-5922, I-5923)

I-40 FROM THE TENNESSEE STATE LINE TO MP-15

February 19, 2019 Letting

To Whom It May Concern:

Reference is made to the plans (Sketch Maps) and proposal form furnished to you on this project.

The following revisions have been made to the Sketch Maps:

Sheet No.	Revisions
4	Note added to clarify areas of 0" to 1-1/2" Milling and revised quantity for Portable Queue Warning System in Summary of Quantities.

Please void the above listed sheet in your plans and staple the revised sheet thereto.

The following revisions have been made to the proposal:

Page No.	Revisions
Proposal Cover	Note added that reads "Includes Addendum No. 2 Dated 02-11-2019".

Please void the above listed pages in your proposal and staple the revised pages thereto.

On the item sheets the following pay item quantity has been revised:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
0048-4609000000-N-SP	Portable Queue Warning System	150 DAY	272 DAY

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT
1591 MAIL SERVICE CENTER
RALEIGH, NC 27699-1591

Telephone: (919) 707-6900
Fax: (919) 250-4127
Customer Service: 1-877-368-4968

Location:
1020 BIRCH RIDGE DR.
RALEIGH, NC 27610

Website: www.ncdot.gov

The Contractor's bid must include this pay item revision.

The electronic bidding file has been updated to reflect these revisions. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied

The contract will be prepared accordingly.

Sincerely,

DocuSigned by:

F81B6038A47A442...
Ronald. E. Davenport, Jr., PE
State Contract Officer

RED/jjr
Attachments

cc:	Mr. Lamar Sylvester, PE	Mr. Ray Arnold, PE
	Mr. Brian Burch, PE	Ms. Jaci Kincaid
	Mr. Ron Hancock, PE	Mr. Mike Gwyn
	Mr. Jon Weathersbee, PE	Ms. Lori Strickland
	Mr. Ken Kennedy, PE	Mr. Alex Foster
	Mr. Mitchell Dixon	Ms. Penny Higgins
	Project File (2)	Mr. Alex Foster

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH, N.C.

PROPOSAL

INCLUDES ADDENDUM No.2 DATED 02-11-2019

DATE AND TIME OF BID OPENING: **FEBRUARY 19, 2019 AT 2:00 PM**

CONTRACT ID C204286
WBS 45930.3.1, 45932.3.1

FEDERAL-AID NO. STBGIM-0040(090), NHPIM-0040(085)
COUNTY HAYWOOD
T.I.P. NO. I-5922, I-5923
MILES 15.000
ROUTE NO. I 40
LOCATION I-40 FROM THE TENNESSEE STATE LINE TO MP-15.

TYPE OF WORK PAVEMENT REHAB, CONC BARRIER, AND GUARDRAIL.

NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0996000000-N	350	PIPE CLEAN OUT	120 EA		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	23.18 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	254,815 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/4")	484,586 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	18,888 SY		
0008	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	8,000 TON		
0009	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	13,107 TON		
0010	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	53,560 TON		
0011	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,174 TON		
0012	1577000000-E	620	POLYMER MODIFIED ASPHALT BIN- DER FOR PLANT MIX	3,828 TON		
0013	1662000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED	12,696 TON		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	24,000 TON		
0015	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	316,800 LF		
0016	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	77 EA		
0017	2473000000-N	SP	GENERIC DRAINAGE ITEM STEEL PLATE FOR PULL BOXES	6 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (SINGLE SLOPE DOUBLE FACED)	22,176 LF		
0019	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (SINGLE SLOPE)	2,400 LF		
0020	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	8 EA		
0021	2850000000-N	858	GENERIC DRAINAGE ITEM ADJUSTMENT OF OPEN THROAT CATCH BASIN	64 EA		
0022	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING DROP INLET TO TRAFFIC BEARING DROP INLET	77 EA		
0023	3030000000-E	862	STEEL BEAM GUARDRAIL	50,500 LF		
0024	3060000000-E	862	STEEL BEAM GUARDRAIL, DOUBLE FACED	200 LF		
0025	3075000000-E	862	TRIPLE CORRUGATED STEEL BM GUARDRAIL	50 LF		
0026	3090000000-N	862	TRIPLE CORRUGATED STEEL BEAM GUARDRAIL TERMINAL SECTIONS	2 EA		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0028	3180000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	7 EA		
0029	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	25 EA		
0030	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	102 EA		
0031	3360000000-E	863	REMOVE EXISTING GUARDRAIL	50,800 LF		
0032	3435000000-N	SP	GENERIC GUARDRAIL ITEM MEDIAN BARRIER REMOVABLE GATE	3 EA		
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,355 SF		
0034	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	261 SF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	15 SF		
0036	4415000000-N	1115	FLASHING ARROW BOARD	3 EA		
0037	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		
0038	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	40 DAY		
0039	4430000000-N	1130	DRUMS	250 EA		
0040	4434000000-N	SP	SEQUENTIAL FLASHING WARNING LIGHTS	30 EA		
0041	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	32 EA		
0042	4480000000-N	1165	TMA	3 EA		
0043	4485000000-E	1170	PORTABLE CONCRETE BARRIER	42,640 LF		
0044	4510000000-N	1190	LAW ENFORCEMENT	1,000 HR		
0045	4516000000-N	1180	SKINNY DRUM	300 EA		
0046	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM PORTABLE QUEUE WARNING SYSTEM DEPLOYMENT	Lump Sum	L.S.	
0047	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM CONNECTED LANE CLOSURE DEVICE	6 EA		
0048	4609000000-N	SP	GENERIC TRAFFIC CONTROL ITEM PORTABLE QUEUE WARNING SYSTEM	272 DAY		
0049	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	25,600 LF		
0050	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	359,740 LF		
0051	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,000 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	444 LF		
0053	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	64 EA		
0054	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	73 EA		
0055	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	17,200 LF		
0056	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	372,150 LF		
0057	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	3,200 LF		
0058	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	200 LF		
0059	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4 EA		
0060	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	27,650 LF		
0061	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	6,076 EA		
0062	0257000000-E	SP	GENERIC GRADING ITEM EXISTING BARRIER WALL REMOVAL	24,576 LF		

1249/Feb08/Q2204305.18/D203725700000/E62

Total Amount Of Bid For Entire Project :

