

PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.04.05.10511, etc	10	

SUMMARY OF QUANTITIES

PROJECT	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGT		INCIDENTAL STONE BASE	1½"	INCI-DENTAL MILLING	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	CONCRETE CURB RAMPS	REMOVE AND REPLACE CURB RAMPS	ADJ. OF MANHO LES	ADJ. OF METER OR VALVE BOXES	PORTABLE LIGHTING	INDUCTIVE LOOP		
										MI	FT		TONS											SY	SY
2020CPT.04.05.10511	Johnston	1	NC 39	FROM US 301 TO JOINT NEAR ROUNDABOUT @ NC 42	2	2	2WU	NO	NO	8.52	24	100	128,679			11,121	667								
		2	NC 222	FROM WAYNE CL TO BEGIN CURB & GUTTER	2	2	2WU	NO	NO	3	24	50	45,321			3,883	233								
		"	"	FROM BEGIN CURB & GUTTER TO END CURB & GUTTER	3	2	2WU	NO	NO	0.7	40			18,381			1,575	95	16	18	9	11		600	
		"	"	FROM END CURB & GUTTER TO NC 42	2	2	2WU	NO	NO	7.4	24	50	111,403			9,545	573								
		TOTAL FOR MAP NO. 2									11.1		100	175,105			15,003	901	16	18	9	11		600	
		3	NC 50 (5 LANE)	FROM BEGIN CURB & GUTTER TO FAYETTEVILLE ST.	3	5	MU	NO	NO	0.4	60			14,402			1,209	73							1,000
		"	"	FROM FAYETTEVILLE ST. TO N. DUNN ST	3	4	MU	NO	NO	0.05	50			1,500			126	8							
		"	"	FROM N. DUNN ST. TO 150' EAST OF US 301	4	3	MU	NO	NO	0.45	30			10,634			963	58			14	15			4,000
		TOTAL FOR MAP NO. 3									0.9			26,536			2,298	139			14	17		5,000	
		TOTAL FOR PROJ NO. 2020CPT.04.05.10511									20.52		200	330,320			28,422	1,707	16	18	23	28			5,600
2020CPT.04.05.20511	Johnston	4	SR 1171 - HANNAH CREEK RD.	FROM US 301 TO SR 1143	1	2	2WU	NO	NO	3.1	21			1,300	3,462		232			1					
		5	SR 1180 - GO CART RD.	FROM SR 1153 TO SR 1150	1	2	2WU	NO	NO	0.98	20			250	974		65								
		6	SR 1183 - THUNDER RD. (SANDERS ST.)	FROM US 301 TO SR 1162 (MAIN ST.)	1	2	2WU	NO	NO	2.9	22			250	3,249		218	2	4						
		7	SR 1190 - BATTLEFIELD RD.	FROM SR 1188 TO SR 1008	1	2	2WU	NO	NO	1.7	20			250	1,689		113								
		8	SR 1303 - BENSON HARDEE RD.	FROM SR 1360 TO HARNETT CL	1	2	2WU	NO	NO	9.4	21			1,350	10,170		681								
		9	SR 1555 - BARBER MILL RD.	FROM SR 1010 TO NC 42	1	2	2WU	NO	NO	5.65	22			750	6,883		461								
TOTAL FOR PROJ NO. 2020CPT.04.05.20511									23.73			4,150			26,427	1,770	2	4	1						
GRAND TOTAL									44.25		200	330,320			4,150	26,427	28,422	3,477	18	22	24	28	1	5,600	