



**\*Note Mill and Fill between rumble strips and fog seal paved shoulder**

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
C2	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
F	PROPOSED ASPHALT SURFACE TREATMENT, FOG SEAL
F1	PROPOSED ASPHALT SURFACE TREATMENT, SINGLE SEAL
EM	EXIST. MILLED RUMBLE STRIPS
AS	AGGREGATE SHOULDER BORROW
U	EXISTING PAVEMENT.
V1	MILLING 1.5" IN DEPTH