ROOM FINISH SCHEDULE									
					WALLS				
						WAINSCOT			
NUMBER	NAME	COLOR SCHEME	FLOOR	BASE	WALL FINISH	FINISH	HEIGHT	CEILING FINISH	REMARKS
101	CONTROL ROOM		VCT	VB	PNT			ACT	
102	TOILET		VCT	VB	PNT			ACT	

TOILET ACCESSORY SCHEDULE				
No.	DESCRIPTION	MOUNTING	MANUFACTURER	MODEL
1	SOAP DISPENSER	44" MAX TO PUSH BUTTON	OWNER FURNISHED GC INSTALLED	
2	TOILET PARTITION	AS SPECIFIED	AS SPECIFIED	
3	TOILET PAPER DISPENSER	TISSUE ACCESS AT 18" MIN AFF	OWNER FURNISHED GC INSTALLED	
4	MIRROR 18" x 30" w/ SS FRAME	40" AFF TO BOTTOM EDGE OF REFLECTING SURFACE		B-165 (1830)
5	SURFACE-MOUNTED SANITARY NAPKIN DISPOSAL	Satin Finish	Bobrick Washroom Equipment, Inc.	B-270



1 / A6.1 LARGE SCALE TOILET PLAN
1/2" = 1'-0"

LEGEND

MATERIALS

- UNDISTURBED EARTH
- CONTROLLED FILL
- CONCRETE
- GRANULAR FILL
- CONC MASONRY UNIT
- FACE MASONRY UNITS
- WOOD BLOCKING
- RIGID INSULATION
- BATT INSULATION

ARCHITECTURAL DRAWING NO. DESIGNATIONS

A1.1 — INDICATES FLOOR PLANS / INDICATES SHEET NUMBER
A2.1 — INDICATES ELEVATIONS / INDICATES SHEET NUMBER
A3.1 — INDICATES SECTIONS / INDICATES SHEET NUMBER
A4.1 — INDICATES LARGE SCALE PLANS / INDICATES SHEET NUMBER
A5.1 — INDICATES GENERAL DETAILS / INDICATES SHEET NUMBER
A6.1 — INDICATES SCHEDULES AND FRAME ELEVATIONS / INDICATES SHEET NUMBER
I4.1 — INDICATES INTERIOR LARGE SCALE LAYOUTS / INDICATES SHEET NUMBER
I7.1 — INDICATES FLOOR PATTERN LAYOUTS / INDICATES SHEET NUMBER

SYMBOLS

SECTION
A / A3.5 — SECTION OR DETAIL NO. / SHEET NO.

BUILDING SECTION
A / A3.5 — SECTION INDICATOR / BUILDING SECTION SHEET NO.

DETAIL
A / A5.1 — DETAIL NO. / DETAIL SHEET NO.

INTERIOR ELEVATION
C / I4.6 — ELEVATION NO. / ELEVATION SHEET NO.

DOOR TAG
A101 — DOOR NUMBER

WINDOW TAG
W1 — WINDOW ELEVATION

WALL TYPE TAG
W1 — WALL IDENTIFICATION

MILLWORK SECTION
A / A3.5 — SECTION OR DETAIL NO. / DETAIL SHEET NO.

ROOM TAG
OFFICE / A101 — ROOM NAME / BLDG. & ROOM NO.

NORTH ARROW

ARCHITECTURAL ABBREVIATIONS

THIS ABBREVIATION LIST IS A STANDARD AND NOT ALL ABBREVIATIONS ARE NECESSARILY USED ON THIS PROJECT

ABV	ABOVE
AC	ACOUSTICAL
ACT	ACOUSTICAL CEILING TILE
AED	AUTOMATED EXTERNAL DEFIBRILLATOR
AFF	ABOVE FINISH FLOOR
ALUM	ALUMINUM
ALT	ALTERNATE
AP	ACCESS PANEL
ARCH	ARCHITECT(URAL)
BD	BOARD
BIT	BITUMINOUS
BLDG	BUILDING
BLK	BLOCK(ING)
BM	BENCH MARK
BOT	BOTTOM
BRG	BEARING
BSMT	BASEMENT
CLR	CLEAR
CL	CENTERLINE
CJ	CONTROL JOINT
CLG	CEILING
CMU	CONCRETE MASONRY UNIT
COL	COLUMN
CONC	CONCRETE
CONT	CONTINUOUS
CONST	CONSTRUCTION
CONTR	CONTRACTOR
COORD	COORDINATE
CT	CERAMIC TILE
DEMO	DEMOLITION
DET	DETAIL
DF	DRINKING FOUNTAIN
DIM	DIMENSION
DN	DOWN
DR	DOOR
DS	DOWNSPOUT
DWG	DRAWING
EA	EACH
EC	ELECTRICAL CONTRACTOR
EJ	EXPANSION JOINT
EL	ELEVATION
ELEC	ELECTRICAL
ELEV	ELEVATOR
ENT	ENTRANCE
EQ	EQUAL
EQUIP	EQUIPMENT
EX	EXISTING
EXP	EXPOSED
EXT	EXTERIOR
EW	EACH WAY
FD	FLOOR DRAIN
FE	FIRE EXTINGUISHER (CABINET)
FFE	FINISHED FLOOR ELEVATION
FIN	FINISH(ED)
FL	FLOOR
FRP	FIBERGLASS REINFORCED PANEL
FRT	FIRE RETARDANT
FT	FOOT or FEET
GA	GAUGE
GALV	GALVANIZED
GC	GENERAL CONTRACTOR
GFCMU	GROUND FACE CONCRETE MASONRY UNIT
GL	GLASS
GCMU	GLAZED CONCRETE MASONRY UNIT
GWB	GYPSUM WALL BOARD
GWBAR	GYPSUM WALL BOARD ABUSE RESISTANT
GWBMR	GYPSUM WALL BOARD MOISTURE RESISTANT
GWBFR	GYPSUM WALL BOARD FIRE RATED
HC	HANDICAPPED
HDW	HARDWARE
HGT	HEIGHT
HP	HIGH POINT
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HVAC	HEATING, VENTILATION & AIR CONDITIONING
ID	INSIDE DIAMETER
INFO	INFORMATION
INSUL	INSULATION
INT	INTERIOR
INV	INVERT
JST	JOIST
JT	JOINT
KIT	KITCHEN(ETTE)
LAM	LAMINATE
LAV	LAVATORY
LB	POUND
LF	LINEAL FEET
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LP	LOW POINT
MFR	MANUFACTURER
MAT	MATERIAL
MAX	MAXIMUM
MC	MECHANICAL CONTRACTOR
MECH	MECHANICAL
MEP	MECHANICAL, ELECTRICAL, PLUMBING
MIN	MINIMUM
MISC	MISCELLANEOUS
MO	MASONRY OPENING
MTD	MOUNTED or MOUNTING
NIC	NOT IN CONTRACT
NO	NUMBER
NOM	NOMINAL
NTS	NOT TO SCALE
OC	ON CENTER
OD	OUTSIDE DIAMETER
OPNG	OPENING
OPP	OPPOSITE
PTN	PARTITION
PC	PLUMBING CONTRACTOR
PL	PLATE
PLAM	PLASTIC LAMINATE
PLWD	PLYWOOD
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PTD	PAINTED
QT	QUARRY TILE
R	RISER or RADIUS
RD	ROOF DRAIN
REC	RECESSED
RECT	RECTANGLE
REINF	REINFORCED or REINFORCING
REQD	REQUIRED
RM	ROOM
RO	ROUGH OPENING
RWC	RAIN WATER CONDUCTOR
SCH	SCHEDULE
SECT	SECTION
SF	SQUARE FEET
SFCMU	SPLIT FACE CONCRETE MASONRY UNIT
SFRM	SPRAY-APPLIED FIRE RESISTIVE MATERIAL
SH	SHEATHING
SIM	SIMILAR
SJ	SCORE JOINT
SPECS	SPECIFICATIONS
SQ	SQUARE
SS	STAINLESS STEEL
STD	STANDARD
STR	STRUCTURAL
SYN	SYNTHETIC
T	TREAD
TG	TEMPERED GLASS
THK	THICK(NESS)
TOM	TOP OF MASONRY
TOP	TOP OF PLANK
TOS	TOP OF STEEL
TYP	TYPICAL
UL	UNDERWRITERS LABORATORIES
UNO	UNLESS NOTED OTHERWISE
VCT	VINYL COMPOSITION TILE
VERT	VERTICAL
VIF	VERIFY IN FIELD
WP	WATERPROOFING
W/	WITH
WD	WOOD
WG	WIRE GLASS

ABBREVIATION SYMBOLS

@	AT
℄	CENTER LINE
Ø	DIAMETER
+/-	PLUS OR MINUS

ALL REPORTS, PLANS SPECIFICATIONS AND COMPUTER FILES RELATING TO THIS PROJECT ARE THE PROPERTY OF CRABTREE, ROHRBAUGH & ASSOCIATES. CRABTREE, ROHRBAUGH & ASSOCIATES RESERVES ALL COMMON LAW, STATUTE AND OTHER RESERVED RIGHTS INCLUDING THE COPYRIGHT THERETO. REPRODUCTION OF THE MATERIAL HEREIN OR SUBSTANTIAL USE WITHOUT WRITTEN PERMISSION OF CRABTREE, ROHRBAUGH & ASSOCIATES VIOLATES THE COPYRIGHT LAWS OF THE UNITED STATES AND WILL BE SUBJECT TO LEGAL PROSECUTION.
© CRABTREE, ROHRBAUGH & ASSOCIATES, INC 2018

REVISIONS

	MM-DD-YR	NAME	DESCRIPTION OF CHANGES

CRABTREE ROHRBAUGH & ASSOCIATES - ARCHITECTS
401 EAST WINDING HILL ROAD
MECHANICSBURG PA 17055
717-458-0272
www.cra-architects.com
BALTIMORE, MARYLAND
CHARLOTTESVILLE, VIRGINIA
WHITE SULPHUR SPRINGS, WEST VIRGINIA

RENOVATIONS TO THE ISABEL HOLMES BRIDGE

ROOM FINISH SCHEDULE, SIGNAGE SCHEDULE, LARGE SCALE TOILET PLAN AND GENERAL INFORMATION

PLOT SCALE: 1/2" = 1'-0"
FILENAME:
DATE: November 9, 2018

PROJECT 3133

A6.1