



**NOTES:**

- UNLESS OTHERWISE NOTED:  
 -ATTACH NEW MESSENGER CABLE MINIMUM 40 INCHES BELOW POWER.  
 -ATTACH ON FRONT SIDE (FS) OF POLE.
- SEAL ALL CONDUIT ENTRANCES WITH DUCT AND CONDUIT SEALER AT ALL JUNCTION BOX/CABINET ENTRANCES.
- TWO (2) WEEKS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM, CONTACT THE CITY OF WILMINGTON SIGNAL SYSTEMS MANAGEMENT ENGINEER, DENYS VIELKANOWITZ AT (910) 341-4676 TO ARRANGE FOR THE CITY OF WILMINGTON TO PROGRAM THE NEW FIELD ETHERNET SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO: THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK AND VLAN ID INFORMATION. NOTIFY THE SENIOR SIGNAL SYSTEM OPERATOR AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND FUNCTIONAL.

**HNTB**  
 HNTB NORTH CAROLINA, P.C.  
 343 E. Six Forks Road, Suite 200  
 Raleigh, North Carolina 27609  
 NC License No: C-1554  
 (919) 546-8997

TMP - FINAL Plans Prepared for: 		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
US 17 (MARKET ST) CABLE ROUTING PLAN		Division 03 New Hanover Co. Wilmington	
PLAN DATE: February 2018 PREPARED BY: N.K. Vlanich		REVIEWED BY: T.R. Terrell REVIEWED BY: N.R. Simmons	
REVISIONS _____ _____ _____		INIT. DATE _____ _____ _____	
0 SCALE 50 1" = 50'		SEAL  Documented by: <i>Natasha R. Simmons</i> 8/1/2018 SIGNATURE DATE CADD File name: U4902D_SCP_21.dgn	