PROJECT REFERENCE NO.	SHEET NO.
U-6038	Sig 12.2

ECONOLITE ASC/3-2070 OVERLAP PROGRAMMING DETAIL

(program controller as shown)

1. From Main Menu select [2. CONTROLLER]
2. From CONTROLLER Submenu select [2. VEHICLE OVERLAPS]

OVERLAP A

Select TMG VEH OVLP [A] and 'PPLT FYA'

```
TMG VEH OVLP...[A] TYPE: .....PPLT FYA

PROTECTED LEFT TURN....    PHASE    1
OPPOSING THROUGH.......    PHASE    2

FLASHING ARROW OUTPUT.....CH9  ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0
ACTION PLAN SF BIT DISABLE........... 0
```

END PROGRAMMING

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 12-1688
DESIGNED: December 2018
SEALED: February 7, 2019
REVISED: N/A

Electrical Detail - Sheet 2 of 2

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared in the Office of:

SUMMIT DESIGN AND ENGINEERING SERVICES

NC FIRM LICENSE No: P-0339
504 Meadowlands Drive
Hillsborough, NC 27278
(919) 732-3883
(919) 732-6676 (FAX)

ELECTRICAL AND PROGRAMMING DETAILS FOR:

Prepared For: Transportation Mobility and Safety Division, Traffic Engineering Branch, Signals Management Section, Signal Operations Unit, Department of Transportation, State of North Carolina

750 N.Greenfield Pkwy,Garner,NC 27529

NC 273 (Beatty Drive)
at
Gaston Gateway YMCA Entrance

Division 12 Gaston County Belmont

PLAN DATE:	December 2018	REVIEWED BY:	
PREPARED BY:	J. Smith	REVIEWED BY:	E. Sirgany

REVISIONS	INIT.	DATE

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 018174 ENGINEER EDWARD W. SIRGANY

DocuSigned by: Edward W Sirgany 2/7/2019
39DF5C86A6984E9...
DATE

SIG. INVENTORY NO. 12-1688

$$$$$$SETTINGS$$$$$
$$$$$$USERNAME$$$$$