

## ECONOLITE ASC/3-2070 OVERLAP PROGRAMMING DETAIL

(program controller as shown)

1. From Main Menu select 2. CONTROLLER
2. From CONTROLLER Submenu select 2. VEHICLE OVERLAPS

### OVERLAP A

Select TMG VEH OVLP [A] and 'PPLT FYA'

TMG VEH OVLP...[A] TYPE: ....PPLT FYA

PROTECTED LEFT TURN.... PHASE 1

OPPOSING THROUGH..... PHASE 2

FLASHING ARROW OUTPUT.....CH9 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

Toggle Twice

### OVERLAP C

Select TMG VEH OVLP [C] and 'PPLT FYA'

TMG VEH OVLP...[C] TYPE: ....PPLT FYA

PROTECTED LEFT TURN.... PHASE 5

OPPOSING THROUGH..... PHASE 6

FLASHING ARROW OUTPUT.....CH11 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

END PROGRAMMING

THIS ELECTRICAL DETAIL IS FOR  
 THE SIGNAL DESIGN: 12-1734  
 DESIGNED: December 2018  
 SEALED: February 7, 2019  
 REVISED: N/A

Electrical Detail - Sheet 2 of 2

DOCUMENT NOT CONSIDERED  
FINAL UNLESS ALL  
SIGNATURES COMPLETED

Prepared in the Office of:



NC FIRM LICENSE No: P-0339  
 504 Meadowlands Drive  
 Hillsborough, NC 27278  
 (919) 732-3883  
 (919) 732-6676 (FAX)

ELECTRICAL AND PROGRAMMING  
DETAILS FOR:




US 29-74 (Wilkinson Boulevard)  
 at  
 Mercy Drive/Caldwell Farm Road

Division 12 Gaston County Belmont

PLAN DATE: December 2018 REVIEWED BY:  
 PREPARED BY: J. Smith REVIEWED BY: E. Sirgany

REVISIONS	INIT.	DATE



DocuSigned by:  
 Edward W Sirgany 2/7/2019  
 DATE

SIG. INVENTORY NO. 12-1734

\$\$\$\$SYTIME\$\$\$\$  
 \$\$\$DOCS\$\$\$\$  
 \$\$\$SUFNAME\$\$\$\$