

- 1 INSTALL 3-WIRE COPPER SERVICE ENTRANCE CONDUCTORS
- 2 INSTALL 4-WIRE COPPER FEEDER CONDUCTORS
- 3 INSTALL 3-WIRE COPPER FEEDER CONDUCTORS
- 4 INSTALL SMFO CABLE
- 5 INSTALL CAT 5e CCTV CABLE
- 6 INSTALL FIBER OPTIC DROP CABLE
- 7 INSTALL TRACER WIRE
- 8 TRENCH
- 9 INSTALL PVC CONDUIT
- 10 INSTALL RIGID, GALVANIZED STEEL CONDUIT
- 11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
- 12 INSTALL RIGID, GALVANIZED STEEL RISER WITH HEAT-SHRINK TUBING
- 13 INSTALL HEAT-SHRINK TUBING RETROFIT KIT
- 14 INSTALL POLYETHYLENE CONDUIT
- 15 DIRECTIONAL DRILL CONDUIT
- 16 BORE AND JACK CONDUIT
- 17 INSTALL CABLE(S) IN EXISTING CONDUIT
- 18 INSTALL CABLE(S) IN NEW CONDUIT
- 19 INSTALL CABLE(S) IN EXISTING RISER
- 20 INSTALL CABLE(S) IN NEW RISER
- 21 INSTALL CABLE(S) IN EXISTING CONDUIT ENTRANCE
- 22 INSTALL NEW CONDUIT INTO NEW CABINET BASE (USE EXISTING CONDUIT STUBOUTS WHEN AVAILABLE)
- 23 INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUBOUTS WHEN AVAILABLE)
- 24 INSTALL NEW CONDUIT INTO POLE MOUNTED CABINET
- 25 INSTALL NEW RISER INTO POLE MOUNTED CABINET
- 26 TERMINATE FIBER-OPTIC CABLE ON INTERCONNECT CENTER IN CCTV EQUIPMENT CABINET
- 27 INSTALL NEW ETHERNET EDGE SWITCH IN CABINET
- 28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPlice CABLE IN CABINET
- 29 INSTALL UNDERGROUND SPlice ENCLOSURE
- 30 INSTALL AERIAL SPlice ENCLOSURE
- 31 INSTALL SPlice CABINET
- 32 MODIFY EXISTING SPlice ENCLOSURE OR INTERCONNECT CENTER
- 33 REMOVE EXISTING SPlice CABINET
- 34 INSTALL CABINET FOUNDATION
- 35 REMOVE EXISTING CABINET FOUNDATION
- 36 INSTALL CCTV CAMERA ASSEMBLY

- 37 REMOVE EXISTING DMS, CABINET AND STRUCTURE
- 38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
- 39 INSTALL STANDARD (ELECTRICAL) JUNCTION BOX
- 40 INSTALL OVERSIZED JUNCTION BOX
- 41 INSTALL SPECIAL OVERSIZED JUNCTION BOX
- 42 INSTALL CELL MODEM
- 43 REMOVE EXISTING METAL POLE AND FOUNDATION
- 44 INSTALL AERIAL GUY ASSEMBLY
- 45 INSTALL STANDARD GUY ASSEMBLY
- 46 INSTALL SIDEWALK GUY ASSEMBLY
- 47 INSTALL MESSENGER CABLE
- 48 REMOVE EXISTING COMMUNICATIONS CABLE
- 49 EXISTING SIGNAL CABINET
- 50 CONDUITS INSTALLED IN BRIDGE STRUCTURE (SEE ROADWAY PLANS)
- 51 INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE
- 52 INSTALL DELINEATOR MARKERS
- 53 STORE 30 FEET OF COMMUNICATIONS CABLE (EACH CABLE), EXCEPT AS NOTED ON PLANS
- 54 REMOVE EXISTING CABINET
- 55 LASH CABLE(S) TO EXISTING SIGNAL /COMMUNICATION CABLE
- 56 LASH CABLES TO NEW MESSENGER CABLE
- 57 MODIFY EXISTING ELECTRICAL SERVICE
- 58 INSTALL NEW ELECTRICAL SERVICE
- 59 BOND TRACER WIRE TO EQUIPMENT GROUND BUS ON ONE END
- 60 BOND MESSENGER TO POLE GROUND
- 61 BOND RISER TO POLE GROUND
- 62 INSTALL DMS, PEDESTAL STRUCTURE, ACCESS LADDER AND DMS FOUNDATION
- 63 INSTALL POLE MOUNTED CABINET
- 64 INSTALL NEW EQUIPMENT CABINET DISCONNECT
- 65 INSTALL GROUND MOUNTED CABINET
- 66 INTERCEPT EXISTING JUNCTION BOX
- 67 INSTALL CCTV CAMERA EXTENSION POLE
- 68 INSTALL SOLAR PANEL ASSEMBLY
- 69 REMOVE WOOD POLE
- 70 INSTALL WOOD POLE
- 71 REMOVE EXISTING CCTV CAMERA

LEGEND

	FD	NEW FIBER OPTIC COMMUNICATIONS CABLE
	EXI	EXISTING COMMUNICATIONS CABLE
	REM	EXISTING COMMUNICATIONS CABLE TO BE REMOVED
		NEW CONDUIT
		EXISTING CONDUIT
	DD	NEW DIRECTIONAL DRILLED CONDUIT
		EXISTING GUARDRAIL
		NEW GUARDRAIL
		NEW CHAIN LINK FENCE
		EXISTING METAL POLE WITH MASTARM
		NEW METAL POLE WITH MASTARM
		EXISTING RIGHT OF WAY
		NEW OVERSIZED HEAVY DUTY JUNCTION BOX
		EXISTING JUNCTION BOX
		NEW OVERSIZED HEAVY DUTY JUNCTION BOX WITH SPlice ENCLOSURE
		EXISTING OVERSIZED HEAVY DUTY JUNCTION BOX WITH NEW SPlice ENCLOSURE
		NEW SPECIAL OVERSIZED HEAVY DUTY JUNCTION BOX WITH SPlice ENCLOSURE
		EXISTING SPECIAL OVERSIZED HEAVY DUTY JUNCTION BOX WITH NEW SPlice ENCLOSURE
		NEW WOOD POLE
		EXISTING WOOD POLE
		NEW AERIAL SPlice
		EXISTING AERIAL SPlice
		NEW SPlice ENCLOSURE
		EXISTING SPlice ENCLOSURE
		NEW METAL POLE
		EXISTING METAL POLE
		NEW DMS
		EXISTING DMS
		NEW CCTV CAMERA ASSEMBLY
		EXISTING CCTV CAMERA ASSEMBLY
		NEW STANDARD GUY ASSEMBLY
		NEW SIGNAL CABINET
		EXISTING STANDARD GUY ASSEMBLY
		EXISTING SIGNAL CABINET
		NEW ITS EQUIPMENT CABINET
		EXISTING ITS EQUIPMENT CABINET
		NEW SOLAR PANEL ASSEMBLY
		NEW ELECTRICAL SERVICE
		EXISTING ELECTRICAL SERVICE
	SP	SIGNAL POLE
	XXX-#	CCTV/DMS NUMBER
	XX-XXXX	SIGNAL INVENTORY NUMBER

ATTACHMENT POINT:

DISTANCE ABOVE INCHES REFERENCE POINT

REFERENCE POINT DISTANCE BELOW INCHES

CONSTRUCTION NOTE SYMBOLOGY KEY

NUMBER OF CABLE(S), LOOPS, ETC. NUMBER OF FIBERS / TWISTED PAIRS PER CABLE, ETC.

NUMBER OF RISER(S) / CONDUIT(S) DIAMETER OF RISER(S) / CONDUIT(S) (INCH)

NUMBER OF DEVICES NUMBER OF FIBERS

NUMBER OF CABLES REMOVE OR MODIFY CABLE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

	I-4400BB CONSTRUCTION NOTES AND LEGEND	
	Division 14 Henderson Asheville	REVIEWED BY: T.R. Terrell
PLAN DATE: November 2018	PREPARED BY: Atizaz Ali	REVIEWED BY: N.R. Simmons
SCALE: NONE	REVISIONS	INIT. DATE
DocuSigned by: Rakesh Nune 4/26/2019		SIGNATURE DATE
CADD File Name: I4400BB ITS-03.dgn		