

**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**


**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

HENDERSON AND BUNCOMBE COUNTIES

LOCATION: I-26 FROM 0.5 MI EAST OF US 25 (ASHEVILLE HIGHWAY)
TO 0.3 MI EAST OF NC 280 (AIRPORT ROAD)
TYPE OF WORK: TRAFFIC SIGNALS & CABLE ROUTING



Project: I-4400C



Contract: C204265

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

Joseph S. Olsen, PE - Project Manager
Natasha R. Simmons, PE, PTOE - Project Task Leader
Andrew D. Klinksiek, PE, PTOE - Project Engineer
Alex H. Thornburg, PE - Project Engineer
James T. Thibault, EI - Design Engineer
Tracey R. Terrell - Senior Design Technician

Index of Plans

| Sheet # | Reference # | Location/Description |
|----------------|-------------|---|
| Sig. 1.0 | ----- | Title Sheet |
| Sig. 2.0-3.2 | 14-1050 | US 25 Business (Asheville Highway) at SR 1534 (Naples Road) / Skyland Drive |
| Sig. 4.0-10.3 | 14-0901 | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps |
| Sig. 11.0-15.3 | 14-0902 | US 25 (Asheville Highway) at I-26 WB Ramps |
| Sig. 16.0-17.3 | 14-0742 | US 25 (Asheville Highway) / US 25 (Hendersonville Road) at SR 1345 (Butler Bridge Road) |
| Sig. 18.0-18.3 | 14-1307 | SR 1345 (Butler Bridge Road) at SR 1365 (N. Rugby Road) |
| Sig. 19.0 | ----- | Standard Drawing for Electrical Service Grounding and Wood Poles |
| Sig. 20.0 | ----- | Standard Drawing for Pedestals |
| Sig. M1-M8 | ----- | Standard Drawing for Metal Poles |
| SCP. 1-20 | ----- | Signal Communication Plans |

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

LEGEND

##-#### SIGNAL INVENTORY NUMBER

INTELLIGENT TRANSPORTATION AND SIGNALS UNIT



Contacts:
Tim Williams, PE - Western Region Signals Engineer
Todd Joyce, PE - Signal Equipment Design Engineer
D.D. (Bucky) Galloway, PE - Western Region Field Operations Engineer

NCDOT - DIVISION 13
Contacts:
Anna G. Henderson, PE - Division Traffic Engineer

NCDOT - DIVISION 14
Contacts:
Steven Buchanan - Division Traffic Engineer

Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.

Prepared for the Office of:
DIVISION OF HIGHWAYS
TRANSPORTATION MOBILITY AND SAFETY
DIVISION



DocuSigned by:
Natasha R. Simmons 4/26/2019
DATE

PHASING DIAGRAM





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | |
|-------------|-------|------|------|-------|
| | 01+6 | 02+6 | 04+8 | LOCAL |
| 11 | — | Y | R | Y |
| 21 | Y | Y | R | Y |
| 22,23 | R | G | R | Y |
| 41,42 | R | R | G | R |
| 61,62 | G | G | R | Y |
| 81 | R | R | G | R |
| 82 | Y | R | G | R |

SIGNAL FACE I.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | SYSTEM LOOP | NEW CARD | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|--------------|-------------|----------|------------|
| | | | | | PHASE | CALLING | EXTENSION | STRETCH TIME | | | DELAY TIME |
| 1A | 6X40 | 0 | * | Y | 1 | Y | Y | - | 15 | - | * |
| 1B | 6X40 | 0 | * | Y | 1 | Y | Y | - | 15 | - | * |
| 2A | 6X6 | 300 | 5 | - | 2 | Y | Y | - | - | - | - |
| 2B | 6X6 | 300 | 5 | - | 2 | Y | Y | - | - | - | - |
| 2C | 6X40 | 0 | 2-4-2 | Y | 2 | Y | Y | - | 3 | - | Y |
| 4A | 6X60 | 0 | 2-4-2 | - | 4 | Y | Y | - | 3 | - | - |
| 4B | 6X60 | 0 | 2-4-2 | - | 4 | Y | Y | - | 10 | - | - |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | * |
| 8A | 6X40 | 0 | * | Y | 8 | Y | Y | - | 3 | - | * |
| S3 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |
| S4 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |

* Multizone Microwave Detection


3 Phase Fully Actuated Asheville Signal System

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 1 may be lagged.
- Set all detector units to presence mode.
- In the event of loop replacement, refer to the current ITS and Signals Design Manual and submit a Plan of Record to the Signal Design Section.
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.

PHASING DIAGRAM DETECTION LEGEND

- DETECTED MOVEMENT
- UNDETECTED MOVEMENT (OVERLAP)
- ⋯ UNSIGNALIZED MOVEMENT
- ⚡ PEDESTRIAN MOVEMENT



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | | |
|-------------------------|-------|------------|-----|------------|-----|
| | 1 | 2 | 4 | 6 | 8 |
| Min Green 1 * | 7 | 12 | 7 | 12 | 7 |
| Extension 1 * | 2.0 | 6.0 | 1.0 | 6.0 | 2.0 |
| Max Green 1 * | 25 | 90 | 20 | 90 | 20 |
| Yellow Clearance | 3.0 | 4.7 | 4.9 | 4.7 | 4.9 |
| Red Clearance | 2.8 | 1.6 | 2.6 | 1.6 | 2.6 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - | - |
| Don't Walk 1 | - | - | - | - | - |
| Seconds Per Actuation * | - | 1.5 | - | 1.5 | - |
| Max Variable Initial * | - | 34 | - | 34 | - |
| Time Before Reduction * | - | 15 | - | 15 | - |
| Time To Reduce * | - | 30 | - | 30 | - |
| Minimum Gap | - | 3.0 | - | 3.0 | - |
| Recall Mode | - | MIN RECALL | - | MIN RECALL | - |
| Vehicle Call Memory | - | YELLOW | - | YELLOW | - |
| Dual Entry | - | - | ON | - | ON |
| Simultaneous Gap | ON | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

LEGEND


- | PROPOSED | EXISTING |
|--|--|
| ○ → Traffic Signal Head | ● → Traffic Signal Head |
| ○ → Modified Signal Head | N/A |
| ⊥ Sign | ⊥ Sign |
| ⊥ Pedestrian Signal Head With Push Button & Sign | ⊥ Pedestrian Signal Head With Push Button & Sign |
| ○ → Signal Pole with Guy | ● → Signal Pole with Guy |
| ○ → Signal Pole with Sidewalk Guy | ● → Signal Pole with Sidewalk Guy |
| ⊠ Inductive Loop Detector | ⊠ Inductive Loop Detector |
| ⊠ Controller & Cabinet | ⊠ Controller & Cabinet |
| ⊠ Junction Box | ⊠ Junction Box |
| ⊠ 2-in Underground Conduit | ⊠ 2-in Underground Conduit |
| N/A Right of Way | — Right of Way |
| → Directional Arrow | → Directional Arrow |
| ⊠ Metal Strain Pole | ⊠ Metal Strain Pole |
| Construction Zone | N/A |
| Microwave Detection Zone | Microwave Detection Zone |

Signal Upgrade
Temporary Design 1
Construction Phases 1,2,2A,2B

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|--|--|------------------------|--|
| | US 25 Business (Asheville Highway) at SR 1534 (Naples Road)/Skyland Drive | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | REVISIONS: INITI. DATE | |


HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997



DocuSigned by:
Natasha R. Simmons 12/26/2019
SIGNATURE DATE
SIG. INVENTORY NO. 14-1050T1

EDI MODEL 2018EClip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.
- Integrate monitor with Ethernet network in cabinet.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Program phases 4 and 8 for Dual Entry.
- Enable Simultaneous Gap-Out for all Phases.
- Program phases 2 and 6 for Variable Initial and Gap Reduction.
- Program phases 2 and 6 for Startup In Green.
- Program phases 2 and 6 for Yellow Flash, and overlap 1 as Wag Overlaps.
- The cabinet and controller are part of the Asheville Signal System.

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....332 W/AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
 LOAD SWITCHES USED.....S1,S2,S5,S8,S11,AUX S1,AUX S4
 PHASES USED.....1,2,4,6,8
 OVERLAP "A".....1+2
 OVERLAP "B".....NOT USED
 OVERLAP "C".....6
 OVERLAP "D".....NOT USED


SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 | AUX S1 | AUX S2 | AUX S3 | AUX S4 | AUX S5 | AUX S6 |
|-----------------------|-----|-----|-------|----|----|-------|----|----|-------|-----|-----|-------|--------|--------|--------|--------|--------|--------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 | 9 | 10 | 17 | 11 | 12 | 18 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED | OLA | OLB | SPARE | OLC | OLD | SPARE |
| SIGNAL HEAD NO. | 11 | 82 | 22,23 | NU | NU | 41,42 | NU | NU | 61,62 | NU | NU | 81,82 | NU | 11 | NU | 21 | NU | NU |
| RED | | * | 128 | | | 101 | | | 134 | | | 107 | | | | | | |
| YELLOW | | | 129 | | | 102 | | | 135 | | | 108 | | | | | | |
| GREEN | | | 130 | | | 103 | | | 136 | | | 109 | | | | | | |
| RED ARROW | | | | | | | | | | | | | | | | A121 | | A114 |
| YELLOW ARROW | | | 126 | | | | | | | | | | | | | A122 | | A115 |
| FLASHING YELLOW ARROW | | | | | | | | | | | | | | | | A123 | | A116 |
| GREEN ARROW | 127 | 127 | | | | | | | | | | | | | | | | |

NU = Not Used
 * Denotes install load resistor. See load resistor installation detail this sheet.
 ★ See pictorial of head wiring in detail this sheet.

FYA SIGNAL WIRING DETAIL

(wire signal heads as shown)




NOTE

The sequence display for signal head 11 requires special logic programming. See sheet 2 for programming instructions.

INPUT FILE POSITION LAYOUT

(front view)




EX.: 1A, 2A, ETC. = LOOP NO.'S
 FS = FLASH SENSE
 ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| ZONE 1A | ★ | I1U | 56 | 18 | 1 | 1 | Y | Y | | | 15 |
| | | J4U | 48 | 10 | 26 | 6 | Y | Y | Y | | 3 |
| 2A | TB2-9,10 | I3U | 63 | 25 | 32 | 2 | Y | Y | | | |
| 2B | TB2-11,12 | I3L | 76 | 38 | 42 | 2 | Y | Y | | | |
| 2C | TB4-1,2 | I4U | 47 | 9 | 22 | 2 | Y | Y | Y | | 3 |
| 4A | TB4-9,10 | I6U | 41 | 3 | 4 | 4 | Y | Y | | | 3 |
| 4B | TB4-11,12 | I6L | 45 | 7 | 14 | 4 | Y | Y | | | 10 |
| * S3 | TB7-9,10 | J9U | 59 | 21 | 15 | SYS | | | | | |
| * S4 | TB7-11,12 | J9L | 61 | 23 | 17 | SYS | | | | | |

★ Multizone Microwave Detector Zone. See Special Detector Note this page.
 * System detector only. Remove the vehicle phase assigned to this detector in the default programming.
 † Add jumper from I1-W to J4-W, on rear of input file.




SPECIAL DETECTOR NOTE

For detection zones 1A, 1B, 6A, 6B, and 8A install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.
 For Detection Zone 1A, the equipment placement and slot reserved for the wired input is typical for a NCDOT installation.

LOAD RESISTOR INSTALLATION DETAIL

(install resistor as shown below)



| ACCEPTABLE VALUES | |
|-------------------|-----------|
| VALUE (ohms) | WATTAGE |
| 1.5K - 1.9K | 25W (min) |
| 2.0K - 3.0K | 10W (min) |

Electrical Detail - Sheet 1 of 2

Signal Upgrade
 Temporary Design 1
 Construction Phases 1,2,2A,2B


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|---------------------------|--|-----------------------------|----------------|
| | Prepared for: US 25 Business (Asheville Highway) at SR 1534 (Naples Road)/Skyland Drive | | SEAL |
| | Division 14 Henderson Co. Hendersonville | REVIEWED BY: A.D. Klinksiek | |
| PLAN DATE: September 2018 | PREPARED BY: A.H. Thornburg | REVIEWED BY: N.R. Simmons | SIGNATURE DATE |
| REVISIONS | INIT. | DATE | DATE |


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)


- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2, and 3.
- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).



NOTE: LOGIC FOR PHASE 1 RED CLEAR WHEN TRANSITIONING FROM PHASE 1 TO PHASE 2 (HEAD 11).



NOTE: LOGIC FOR SWITCHING FLASHING YELLOW ARROW OFF DURING PHASE 1 (HEAD 11).



NOTE: LOGIC FOR YELLOW ARROW CLEARANCE FROM PHASE 1 (HEAD 11).


LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

| OUTPUT REFERENCE SCHEDULE | |
|----------------------------------|--------------------|
| USE TO INTERPRET LOGIC PROCESSOR | |
| OUTPUT 50 | = Overlap A Red |
| OUTPUT 51 | = Overlap A Yellow |
| OUTPUT 52 | = Overlap A Green |

OVERLAP PROGRAMMING DETAIL


(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).



← NOTICE GREEN FLASH

PRESS '+' TWICE




← NOTICE GREEN FLASH

OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-1050T1
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A


Electrical Detail - Sheet 2 of 2
Signal Upgrade
Temporary Design 1
Construction Phases 1,2,2A,2B

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



| | | |
|---|--|--|
| | Prepared for: US 25 Business (Asheville Highway) at SR 1534 (Naples Road)/Skyland Drive | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| REVISIONS INIT. DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 SIGNATURE DATE | SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031464 NATASHA R. SIMMONS |
| 1750 N. Greenfield Pkwy, Corner, NC 27529 | | SIG. INVENTORY NO. 14-1050T1 |

PHASING DIAGRAM




PHASING DIAGRAM DETECTION LEGEND

- ←●→ DETECTED MOVEMENT
- ←→ UNDETECTED MOVEMENT (OVERLAP)
- ←...→ UNSIGNALIZED MOVEMENT
- ←- - -→ PEDESTRIAN MOVEMENT

TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|------|------|---|
| | 01+6 | 02+6 | 04+8 | FOOT | P |
| 11 | — | Y | R | Y | — |
| 21 | Y | Y | R | Y | — |
| 22,23,24 | R | G | R | Y | — |
| 41,42 | R | R | G | R | — |
| 61,62 | G | G | R | Y | — |
| 81 | R | R | G | R | — |
| 82 | Y | R | G | R | — |

SIGNAL FACE I.D.




OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | SYSTEM LOOP | NEW CARD | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|-------------|----------|--------------|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | | | STRETCH TIME |
| 1A | 6X40 | 0 | 2-4-2 | Y | 1 | Y | Y | - | 15 | - | Y |
| 1B | 6X40 | 0 | 2-4-2 | Y | 1 | Y | Y | - | 15 | - | Y |
| 2A | 6X6 | 300 | 5 | - | 2 | Y | Y | - | - | - | - |
| 2B | 6X6 | 300 | 5 | - | 2 | Y | Y | - | - | - | - |
| 2C | 6X40 | 0 | 2-4-2 | - | 2 | Y | Y | Y | - | 3 | - |
| 4A | 6X60 | 0 | 2-4-2 | - | 4 | Y | Y | - | - | 3 | - |
| 4B | 6X60 | 0 | 2-4-2 | - | 4 | Y | Y | - | - | 10 | - |
| 6A | 6X6 | 300 | 6 | Y | 6 | Y | Y | - | - | - | Y |
| 6B | 6X6 | 300 | 6 | Y | 6 | Y | Y | - | - | - | Y |
| 8A | 6X40 | 0 | 2-4-2 | Y | 8 | Y | Y | - | - | 3 | Y |
| S1 | 6X6 | +170 | 4 | Y | - | - | - | - | - | - | Y |
| S2 | 6X6 | +170 | 4 | Y | - | - | - | - | - | - | Y |
| S3 | 6X6 | +170 | 4 | Y | - | - | - | - | - | - | Y |
| S4 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |
| S5 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |

3 Phase Fully Actuated Asheville Signal System

NOTES


- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 1 may be lagged.
- Set all detector units to presence mode.
- In the event of loop replacement, refer to the current ITS and Signals Design Manual and submit a Plan of Record to the Signal Design Section.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | | |
|-------------------------|-------|------------|-----|------------|-----|
| | 1 | 2 | 4 | 6 | 8 |
| Min Green 1 * | 7 | 12 | 7 | 12 | 7 |
| Extension 1 * | 2.0 | 6.0 | 1.0 | 6.0 | 2.0 |
| Max Green 1 * | 25 | 90 | 20 | 90 | 20 |
| Yellow Clearance | 3.0 | 4.7 | 4.9 | 4.7 | 4.9 |
| Red Clearance | 2.8 | 1.6 | 2.6 | 1.6 | 2.6 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - | - |
| Don't Walk 1 | - | - | - | - | - |
| Seconds Per Actuation * | - | 1.5 | - | 1.5 | - |
| Max Variable Initial * | - | 34 | - | 34 | - |
| Time Before Reduction * | - | 15 | - | 15 | - |
| Time To Reduce * | - | 30 | - | 30 | - |
| Minimum Gap | - | 3.0 | - | 3.0 | - |
| Recall Mode | - | MIN RECALL | - | MIN RECALL | - |
| Vehicle Call Memory | - | YELLOW | - | YELLOW | - |
| Dual Entry | - | - | ON | - | ON |
| Simultaneous Gap | ON | ON | ON | ON | ON |

LEGEND



* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

Signal Upgrade - Final Design


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

| | | | |
|--|--|------------------------|--|
| | US 25 Business (Asheville Highway) at SR 1534 (Naples Road)/Skyland Drive | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | REVISIONS: INITI. DATE | |

DocuSigned by: Natasha R. Simmons/26/2019
DATE: _____
SIGNATURE: _____
SIG. INVENTORY NO. 14-1050

EDI MODEL 2018EClip-NC CONFLICT MONITOR
PROGRAMMING DETAIL
 (remove jumpers and set switches as shown)



- NOTES:**
- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
 - Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
 - Ensure that Red Enable is active at all times during normal operation.
 - Integrate monitor with Ethernet network in cabinet.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Program phases 4 and 8 for Dual Entry.
- Enable Simultaneous Gap-Out for all Phases.
- Program phases 2 and 6 for Variable Initial and Gap Reduction.
- Program phases 2 and 6 for Startup In Green.
- Program phases 2 and 6 for Yellow Flash, and overlap 1 as Wag Overlaps.
- The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART


| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 | AUX S1 | AUX S2 | AUX S3 | AUX S4 | AUX S5 | AUX S6 |
|-----------------------|-----|-----|----------|----|----|-------|----|----|-------|-----|-----|-------|--------|--------|--------|--------|--------|--------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 | 9 | 10 | 17 | 11 | 12 | 18 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED | OLA | OLB | SPARE | OLC | OLD | SPARE |
| SIGNAL HEAD NO. | 11★ | 82 | 22,23,24 | NU | NU | 41,42 | NU | NU | 61,62 | NU | NU | 81,82 | NU | 11★ | NU | NU | 21★ | NU |
| RED | | * | 128 | | | 101 | | | 134 | | | 107 | | | | | | |
| YELLOW | | | 129 | | | 102 | | | 135 | | | 108 | | | | | | |
| GREEN | | | 130 | | | 103 | | | 136 | | | 109 | | | | | | |
| RED ARROW | | | | | | | | | | | | | | | | | | |
| YELLOW ARROW | | | | | | | | | | | | | | | | | | |
| FLASHING YELLOW ARROW | | | | | | | | | | | | | | | | | | |
| GREEN ARROW | 127 | 127 | | | | | | | | | | | | | | | | |

NU = Not Used
 * Denotes install load resistor. See load resistor installation detail this sheet.
 ★ See pictorial of head wiring in detail this sheet.

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....332 W/AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
 LOAD SWITCHES USED.....S1,S2,S5,S8,S11,AUX S1,AUX S4
 PHASES USED.....1,2,4,6,8
 OVERLAP "A".....1+2
 OVERLAP "B".....NOT USED
 OVERLAP "C".....6
 OVERLAP "D".....NOT USED

FYA SIGNAL WIRING DETAIL
 (wire signal heads as shown)



NOTE
 The sequence display for signal head 11 requires special logic programming. See sheet 2 for programming instructions.

INPUT FILE POSITION LAYOUT
 (front view)


| FILE "I" | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 |
|----------|----------|----------|-----|----------|-----|----------|--------------|-----|--------------|-----|-----|-----|-----|-------------|
| U | ∅ 1 | ∅ 1 | ∅ 2 | ∅ 2 | S | ∅ 4 | SYS. DET. S5 | S | SYS. DET. S1 | S | S | S | S | FS |
| L | NOT USED | NOT USED | ∅ 2 | NOT USED | ∅ 4 | NOT USED | SYS. DET. S2 | ∅ 4 | NOT USED | ∅ 4 | ∅ 4 | ∅ 4 | ∅ 4 | DC ISOLATOR |
| U | S | ∅ 6 | S | S | S | ∅ 8 | S | S | SYS. DET. S3 | S | S | S | S | S |
| L | ∅ 6 | ∅ 6 | ∅ 6 | ∅ 6 | ∅ 6 | NOT USED | SYS. DET. S4 | ∅ 6 | ∅ 6 | ∅ 6 | ∅ 6 | ∅ 6 | ∅ 6 | DC ISOLATOR |

EX. : 1A, 2A, ETC. = LOOP NO.'S
 FS = FLASH SENSE
 ST = STOP TIME
 ⊗ Wired Input - Do not populate slot with detector cord


INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|-----------------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 1A ¹ | TB2-1,2 | I1U | 56 | 18 | 1 | 1 | Y | Y | | | 15 |
| | | J4U | 48 | 10 | 26 | 6 | Y | Y | Y | | 3 |
| 1B | TB2-5,6 | I2U | 39 | 1 | 2 | 1 | Y | Y | | | 15 |
| 2A | TB2-9,10 | I3U | 63 | 25 | 32 | 2 | Y | Y | | | |
| 2B | TB2-11,12 | I3L | 76 | 38 | 42 | 2 | Y | Y | | | |
| 2C | TB4-1,2 | I4U | 47 | 9 | 22 | 2 | Y | Y | Y | | 3 |
| 4A | TB4-9,10 | I6U | 41 | 3 | 4 | 4 | Y | Y | | | 3 |
| 4B | TB4-11,12 | I6L | 45 | 7 | 14 | 4 | Y | Y | | | 10 |
| * S5 | TB6-1,2 | I7U | 65 | 27 | 34 | SYS | | | | | |
| * S1 | TB6-9,10 | I9U | 60 | 22 | 11 | SYS | | | | | |
| * S2 | TB6-11,12 | I9L | 62 | 24 | 13 | SYS | | | | | |
| 6A | TB3-5,6 | J2U | 40 | 2 | 6 | 6 | Y | Y | | | |
| 6B | TB3-7,8 | J2L | 44 | 6 | 16 | 6 | Y | Y | | | |
| 8A | TB5-9,10 | J6U | 42 | 4 | 8 | 8 | Y | Y | | | 3 |
| * S3 | TB7-9,10 | J9U | 59 | 21 | 15 | SYS | | | | | |
| * S4 | TB7-11,12 | J9L | 61 | 23 | 17 | SYS | | | | | |

¹Add jumper from I1-W to J4-W. on rear of input file.
 * System detector only. Remove the vehicle phase assigned to this detector in the default programming.



LOAD RESISTOR INSTALLATION DETAIL
 (install resistor as shown below)



Electrical Detail - Final Design
 Signal Upgrade - Sheet 1 of 2

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared for: **US 25 Business (Asheville Highway) at SR 1534 (Naples Road)/Skyland Drive**

Division 14 Henderson Co. Hendersonville

PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek
 PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

REVISIONS: _____ INITI. _____ DATE _____


DocuSigned by: **Natasha R. Simmons** 14-1050

SIG. INVENTORY NO. 14-1050


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)


- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2, and 3.
- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).



NOTE: LOGIC FOR PHASE 1 RED CLEAR WHEN TRANSITIONING FROM PHASE 1 TO PHASE 2 (HEAD 11).



NOTE: LOGIC FOR SWITCHING FLASHING YELLOW ARROW OFF DURING PHASE 1 (HEAD 11).



NOTE: LOGIC FOR YELLOW ARROW CLEARANCE FROM PHASE 1 (HEAD 11).

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

| OUTPUT REFERENCE SCHEDULE | |
|----------------------------------|--------------------|
| USE TO INTERPRET LOGIC PROCESSOR | |
| OUTPUT 50 | = Overlap A Red |
| OUTPUT 51 | = Overlap A Yellow |
| OUTPUT 52 | = Overlap A Green |

OVERLAP PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).

```

    PAGE 1: VEHICLE OVERLAP 'A' SETTINGS
    PHASE:           12345678910111213141516
    VEH OVL PARENTS: XX
    VEH OVL NOT VEH:
    VEH OVL NOT PED:
    VEH OVL GRN EXT:
    STARTUP COLOR:  - RED - YELLOW - GREEN
    FLASH COLORS:   - RED - YELLOW X GREEN
    SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
    FLASH YELLOW IN CONTROLLER FLASH?...Y
    GREEN EXTENSION (0-255 SEC)...0
    YELLOW CLEAR (0=PARENT,3-25.5 SEC)...0.0
    RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0
    OUTPUT AS PHASE # (0=NONE, 1-16)...0
  
```

← NOTICE GREEN FLASH

PRESS '+' TWICE

```

    PAGE 1: VEHICLE OVERLAP 'C' SETTINGS
    PHASE:           12345678910111213141516
    VEH OVL PARENTS: X
    VEH OVL NOT VEH:
    VEH OVL NOT PED:
    VEH OVL GRN EXT:
    STARTUP COLOR:  - RED - YELLOW - GREEN
    FLASH COLORS:   - RED - YELLOW X GREEN
    SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
    FLASH YELLOW IN CONTROLLER FLASH?...Y
    GREEN EXTENSION (0-255 SEC)...0
    YELLOW CLEAR (0=PARENT,3-25.5 SEC)...0.0
    RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0
    OUTPUT AS PHASE # (0=NONE, 1-16)...0
  
```


← NOTICE GREEN FLASH

OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-1050
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A


Electrical Detail - Final Design
Signal Upgrade - Sheet 2 of 2

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED



| | | | |
|--|---|--|---|
| ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared for: | US 25 Business (Asheville Highway) at SR 1534 (Naples Road)/Skyland Drive | | SEAL |
| | Division 14 Henderson Co. Hendersonville | PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| REVISIONS _____ _____ _____ | INIT. _____ _____ _____ | DATE _____ _____ _____ | DocuSigned by: NATASHA R. SIMMONS DATE: 4/26/2019 SIG. INVENTORY NO. 14-1050 |

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND

- DETECTED MOVEMENT
- UNDETECTED MOVEMENT (OVERLAP)
- ⋯ UNSIGNALIZED MOVEMENT
- ⋯ PEDESTRIAN MOVEMENT

QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|----|------|-------|
| | 01+6 | 02+6 | 04 | PRE3 | FLUSH |
| 11 | — | R | R | R | R |
| 21,22 | R | G | R | R | Y |
| 41,42 | R | R | G | G | R |
| 61,62 | G | G | R | R | Y |

SIGNAL FACE I.D.

All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|--------------------------|----------------------|-------------------------|-------------|----------|---|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY TIME | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | SYSTEM LOOP | NEW CARD | |
| 1A | 6X40 | 0 | * | Y | 1 | Y | Y | - | - | 3 | - | - | - | - | - | * |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4A | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4B | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | 15 | - | - | - | - | - | * |
| **01 | 6X6 | 625 | * | Y | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |

* Multizone Microwave Detection
** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 1 may be lagged.
- Set all detector units to presence mode.
- Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
- When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.

OASIS 2070 TIMING CHART


| FEATURE | PHASE | | | |
|-------------------------|-------|------------|-----|------------|
| | 1 | 2 | 4 | 6 |
| Min Green 1 * | 7 | 12 | 7 | 12 |
| Extension 1 * | 2.0 | 6.0 | 2.0 | 6.0 |
| Max Green 1 * | 25 | 90 | 30 | 90 |
| Yellow Clearance | 3.0 | 4.1 | 3.7 | 4.4 |
| Red Clearance | 3.3 | 1.5 | 2.4 | 1.0 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | - | 1.5 | - | 1.5 |
| Max Variable Initial * | - | 34 | - | 34 |
| Time Before Reduction * | - | 15 | - | 15 |
| Time To Reduce * | - | 30 | - | 30 |
| Minimum Gap | - | 3.0 | - | 3.0 |
| Recall Mode | - | MIN RECALL | - | MIN RECALL |
| Vehicle Call Memory | - | YELLOW | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

* Time defaults to time used for phase during normal operation
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997



PROPOSED LEGEND EXISTING

| | | | |
|-----|--|-----|-----|
| ○ | Traffic Signal Head | ● | N/A |
| ○ | Modified Signal Head | — | N/A |
| — | Sign | — | N/A |
| □ | Pedestrian Signal Head With Push Button & Sign | — | N/A |
| — | Signal Pole with Guy | — | N/A |
| — | Signal Pole with Sidewalk Guy | — | N/A |
| □ | Inductive Loop Detector | — | N/A |
| □ | Controller & Cabinet | — | N/A |
| □ | Junction Box | — | N/A |
| — | 2-in Underground Conduit | — | N/A |
| N/A | Right of Way | — | N/A |
| → | Directional Arrow | → | N/A |
| — | Construction Zone | — | N/A |
| — | Microwave Detection Zone | — | N/A |
| (A) | No Left Turn Sign (R3-2) | (A) | N/A |
| (B) | No Right Turn Sign (R3-1) | (B) | N/A |
| (C) | "YIELD" Sign (R1-2) | (C) | N/A |

Signal Upgrade
Temporary Design 1
Construction Phases 1,2,2A


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|----------------|--|--|------|
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031464 NATASHA R. SIMMONS | |
| REVISIONS | | DATE | DATE |
| 0 40 1"=40' | | DocuSigned by: Natasha R. Simmons 1/26/2019 SIGNATURE DATE SIG. INVENTORY NO. 14-0901T1 | |



EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|-----|-------|-------|----|-------|-------|----|-------|-------|-----|-----|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | 11 | 21,22 | NU | NU | 41,42 | NU | NU | 61,62 | NU | NU | NU | NU |
| RED | | 128 | | | 101 | | | 134 | | | | |
| YELLOW | | 129 | | | 102 | | | 135 | | | | |
| GREEN | | 130 | | | 103 | | | 136 | | | | |
| RED ARROW | 125 | | | | | | | | | | | |
| YELLOW ARROW | 126 | | | | | | | | | | | |
| GREEN ARROW | 127 | | | | | | | | | | | |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S1,S2,S5,S8
 PHASES USED.....1,2,4,6
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT

(front view)




INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | I4U | 41 | 3 | * 4 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 **Multizone Microwave Detector Zone. See Special Detector Note.

INPUT FILE POSITION LEGEND: J2L



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0901T1
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 1
 Construction Phases 1,2,2A

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | | | |
|-----------------------------|---|-----------------------------|--|--|--|
| | Prepared for: | | Division 14 Henderson Co. Hendersonville | | |
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | SEAL 031464 NATASHA R. SIMMONS | | |
| PLAN DATE: September 2018 | | REVIEWED BY: A.D. Klinksiek | | DocuSigned by: Natasha R. Simmons 4/26/2019 | |
| PREPARED BY: A.H. Thornburg | | REVIEWED BY: N.R. Simmons | | SIGNATURE DATE | |
| REVISIONS | | INIT. DATE | | SIG. INVENTORY NO. 14-0901T1 | |


HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL WHEN LEAVING PREEMPTOR SEQUENCE

(program controller as shown below)

- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.



VEHICLE DETECTOR #4 SETTINGS FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS). PRESS '+' UNTIL DETECTOR #4 IS REACHED.

| | |
|--|-------------------------|
| VEHICLE DETECTOR #4 SETTINGS (+/-1-64) | |
| SETTING: | (Y/N) |
| ENABLE DETECTOR..... | Y |
| ENABLE LOGGING..... | N |
| ENABLE DIAGNOSTICS..... | N |
| SPEED TRAP..... | N |
| CALL DETECTOR..... | N |
| EXTENSION DETECTOR..... | N |
| MODE 2 STOP BAR..... | N |
| SWITCHING DETECTOR..... | N |
| DUPLICATING DETECTOR..... | N |
| ENABLE FULL TIME DELAY..... | N |
| IF FAILED, SET MIN RECALL?..... | N |
| IF FAILED, SET MAX1 RECALL?..... | N |
| IF FAILED, SET MAX2 RECALL?..... | N |
| PHASE# | 12345678910111213141516 |
| PHASES ASSIGNED : | |
| SWITCH/DUPLICATE: | |
| LOOP SIZE (0-255 FT)..... | 6 |
| SPEED TRAP DISTANCE (0-255 FT)..... | 0 |
| STOP BAR TIME (0-255 SEC)..... | 0 |
| STRETCH (0-25.5 SEC)..... | 0.0 |
| DELAY (0-255 SEC)..... | 0 |
| MAX CALLS/MIN (0-255)..... | 255 |
| MIN CALLS/DIAGNOSTIC PERIOD (0-255)..... | 0 |
| MAX OCCUPANCY (0-100%)..... | 100 |
| EXTENSION DISABLE TIME (0-255 SEC)..... | 0 |
| QUEUE MAX OCCUPANCY TIME (0-255)..... | 5 |
| QUEUE GAP RESET TIME (0-25.5)..... | 0.1 |
| PREEMPTION INDEX FOR QUEUE (0-10)..... | 3 |

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

| | |
|---|-------------------------|
| PREEMPTION #3 SETTINGS (NEXT:1-10) | |
| INTERVAL/TIMING | CLEAR/DWELL PHASES |
| GRN YEL RED | 12345678910111213141516 |
| 1 255 0.0 0.0 | X |
| 2 0 0.0 0.0 | |
| 3 0 0.0 0.0 | |
| 4 0 0.0 0.0 | |
| 5 1 0.0 0.0 | X X |
| EXIT CALLS | |
| OPTIONS | |
| PRIORITY (Y/N TO SELECT) | MED |
| DELAY TIMER (0-255 SEC) | 0.0 |
| MIN GREEN BEFORE PRE (0= DEFAULT)..... | 12 |
| PED CLEAR BEFORE PRE (0= DEFAULT)..... | 0 |
| YELLOW CLEAR BEFORE PRE (0= DEFAULT)..... | 4.4 |
| RED CLEAR BEFORE PRE (0= DEFAULT)..... | 1.5 |
| DWELL MIN TIMER (0-255 SEC) | 30 |
| DWELL MAX TIMER (0=OFF,1-255MIN) | 0 |
| DWELL HOLD-OVER TIMER (0-255) | 0 |
| LATCH CALL? | N |
| LINK TO NEXT PREEMPT? | N |
| ENABLE BACKUP PROTECTION? | N |
| HOLD CLEAR 1 PHASES DURING DELAY? | N |
| FAST GREEN FLASH DWELL PHASES? | N |
| PED CLEARANCE THROUGH YELLOW? | N |
| INHIBIT OVERLAP GREEN EXTENSION? | N |
| SERVICE DURING SOFTWARE FLASH? | N |
| REST IN RED DURING DWELL INTERVAL? | N |
| FLASH DWELL INTERVAL? | N |
| ALLOW PEDS IN DWELL INTERVAL? | N |
| RE-TIME DWELL INTERVAL? | N |
| OVERLAPS: | ABCDEFGHIJKLMNPO |
| DWELL INT FLASH YELLOW | |
| OMIT OVERLAPS: | |


THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0901T1
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A

Electrical Detail - Sheet 2 of 2
Signal Upgrade
Temporary Design 1
Construction Phases 1,2,2A

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

| | | | | |
|--|---|--|--|--|
| | Prepared for: | | Division 14 Henderson Co. Hendersonville | |
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| REVISIONS | | | INIT. DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 SIGNATURE DATE |
| 750 N. Greenfield Pkwy, Corner, NC 27529 | | | SIG. INVENTORY NO. 14-0901T1 | |

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND

- ←● DETECTED MOVEMENT
- ← UNDETECTED MOVEMENT (OVERLAP)
- ←... UNSIGNALIZED MOVEMENT
- ←- - - PEDESTRIAN MOVEMENT

QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|----|------|-------|
| | 02+5 | 02+6 | 04 | PRE3 | FLUSH |
| 21,22 | G | G | R | R | Y |
| 41,42 | R | R | G | G | R |
| 51 | - | -R | -R | -R | -R |
| 61,62 | R | G | R | R | Y |

SIGNAL FACE I.D.

All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|--------------------------|----------------------|-------------------------|-------------|----------|---|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY TIME | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | SYSTEM LOOP | NEW CARD | |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4A | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4B | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | 15 | - | - | - | - | - | * |
| **01 | 6X6 | 625 | * | Y | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | * |
| 5A | 6X40 | 0 | * | Y | 5 | Y | Y | - | - | - | - | - | - | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |

* Multizone Microwave Detection
** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System

NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Phase 5 may be lagged.
4. Set all detector units to presence mode.
5. Reposition existing signal heads numbered 21 and 22.
6. Incorporate Microwave Detection system for vehicle detection.
7. Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
8. This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
9. When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
10. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.

OASIS 2070 TIMING CHART


| FEATURE | PHASE | | | |
|-------------------------|------------|-----|-----|------------|
| | 2 | 4 | 5 | 6 |
| Min Green 1 * | 12 | 7 | 7 | 12 |
| Extension 1 * | 6.0 | 2.0 | 2.0 | 6.0 |
| Max Green 1 * | 90 | 30 | 25 | 90 |
| Yellow Clearance | 4.1 | 6.0 | 3.0 | 4.4 |
| Red Clearance | 1.0 | 2.4 | 2.8 | 1.3 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | 1.5 | - | - | 1.5 |
| Max Variable Initial * | 34 | - | - | 34 |
| Time Before Reduction * | 15 | - | - | 15 |
| Time To Reduce * | 30 | - | - | 30 |
| Minimum Gap | 3.0 | - | - | 3.0 |
| Recall Mode | MIN RECALL | - | - | MIN RECALL |
| Vehicle Call Memory | YELLOW | - | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

* Time defaults to time used for phase during normal operation
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997



LEGEND

| PROPOSED | EXISTING |
|--|---------------------------------|
| ○ → Traffic Signal Head | ● → Traffic Signal Head |
| ○ → Modified Signal Head | N/A |
| ⊥ Sign | ⊥ Sign |
| ⊥ Pedestrian Signal Head With Push Button & Sign | ⊥ Pedestrian Signal Head |
| ○ Signal Pole with Guy | ○ Signal Pole with Guy |
| ⊥ Signal Pole with Sidewalk Guy | ⊥ Signal Pole with Sidewalk Guy |
| ⊠ Inductive Loop Detector | ⊠ Inductive Loop Detector |
| ⊠ Controller & Cabinet | ⊠ Controller & Cabinet |
| ⊠ Junction Box | ⊠ Junction Box |
| - - - 2-in Underground Conduit | - - - 2-in Underground Conduit |
| N/A Right of Way | N/A Right of Way |
| → Directional Arrow | → Directional Arrow |
| Construction Zone | N/A |
| Microwave Detection Zone | Microwave Detection Zone |
| (A) No Left Turn Sign (R3-2) | (A) No Left Turn Sign (R3-2) |
| (B) No Right Turn Sign (R3-1) | (B) No Right Turn Sign (R3-1) |
| (C) "YIELD" Sign (R1-2) | (C) "YIELD" Sign (R1-2) |


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Signal Upgrade
Temporary Design 2
Construction Phase 2B

| | | | |
|--|--|------------------------|------------------------------|
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | REVISIONS: INITI. DATE | |
| DocuSigned by: <i>Natasha R. Simmons</i> 14-0901T2 SIGNATURE DATE | | | SIG. INVENTORY NO. 14-0901T2 |

EDI MODEL 2018ECLIP-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|----|-------|-------|----|-------|-------|----|-------|-------|-----|-----|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | NU | 21,22 | NU | NU | 41,42 | NU | 51 | 61,62 | NU | NU | NU | NU |
| RED | | 128 | | | 101 | | | 134 | | | | |
| YELLOW | | 129 | | | 102 | | | 135 | | | | |
| GREEN | | 130 | | | 103 | | | 136 | | | | |
| RED ARROW | | | | | | | | 131 | | | | |
| YELLOW ARROW | | | | | | | | 132 | | | | |
| GREEN ARROW | | | | | | | | 133 | | | | |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S2,S5,S7,S8
 PHASES USED.....2,4,5,6
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | I4U | 41 | 3 | * 4 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 **Multizone Microwave Detector Zone. See Special Detector Note.



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0901T2
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 2
 Construction Phase 2B

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


| | | | |
|---|---|-----------------------------|-------------|
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | Prepared for: | |
| Prepared for: | PLAN DATE: September 2018 | REVIEWED BY: A.D. Klinksiek | SEAL 031464 |
| Prepared by: A.H. Thornburg | REVIEWED BY: N.R. Simmons | REVISIONS | DATE |
| HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | DocuSigned by: Natasha R. Simmons 4/26/2019 | SIGNATURE | DATE |

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL WHEN LEAVING PREEMPTOR SEQUENCE

(program controller as shown below)

1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.



VEHICLE DETECTOR #4 SETTINGS FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS). PRESS '+' UNTIL DETECTOR #4 IS REACHED.

| | |
|--|-------------------------|
| VEHICLE DETECTOR #4 SETTINGS (+,-,1-64) | |
| SETTING: | (Y/N) |
| ENABLE DETECTOR..... | Y |
| ENABLE LOGGING..... | N |
| ENABLE DIAGNOSTICS..... | N |
| SPEED TRAP..... | N |
| CALL DETECTOR..... | N |
| EXTENSION DETECTOR..... | N |
| MODE 2 STOP BAR..... | N |
| SWITCHING DETECTOR..... | N |
| DUPLICATING DETECTOR..... | N |
| ENABLE FULL TIME DELAY..... | N |
| IF FAILED, SET MIN RECALL?..... | N |
| IF FAILED, SET MAX1 RECALL?..... | N |
| IF FAILED, SET MAX2 RECALL?..... | N |
| PHASE# | 12345678910111213141516 |
| PHASES ASSIGNED : | |
| SWITCH/DUPLICATE : | |
| LOOP SIZE (0-255 FT)..... | 6 |
| SPEED TRAP DISTANCE (0-255 FT)..... | 0 |
| STOP BAR TIME (0-255 SEC)..... | 0 |
| STRETCH (0-25.5 SEC)..... | 0.0 |
| DELAY (0-255 SEC)..... | 0 |
| MAX CALLS/MIN (0-255)..... | 255 |
| MIN CALLS/DIAGNOSTIC PERIOD (0-255)..... | 0 |
| MAX OCCUPANCY (0-100%)..... | 100 |
| EXTENSION DISABLE TIME (0-255 SEC)..... | 0 |
| QUEUE MAX OCCUPANCY TIME (0-255)..... | 5 |
| QUEUE GAP RESET TIME (0-25.5)..... | 0.1 |
| PREEMPTION INDEX FOR QUEUE (0-10)..... | 3 |

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

| | |
|---|-------------------------|
| PREEMPTION #3 SETTINGS (NEXT:1-10) | |
| INTERVAL/TIMING | CLEAR/DWELL PHASES |
| GRN YEL RED | 12345678910111213141516 |
| 1 255 0.0 0.0 | X |
| 2 0 0.0 0.0 | |
| 3 0 0.0 0.0 | |
| 4 0 0.0 0.0 | |
| 5 1 0.0 0.0 | X X |
| EXIT CALLS | |
| OPTIONS | |
| PRIORITY (Y/N TO SELECT) | MED |
| DELAY TIMER (0-255 SEC) | 0.0 |
| MIN GREEN BEFORE PRE (0= DEFAULT)..... | 12 |
| PED CLEAR BEFORE PRE (0= DEFAULT)..... | 0 |
| YELLOW CLEAR BEFORE PRE (0= DEFAULT)..... | 4.4 |
| RED CLEAR BEFORE PRE (0= DEFAULT)..... | 1.3 |
| DWELL MIN TIMER (0-255 SEC) | 30 |
| DWELL MAX TIMER (0=OFF,1-255MIN) | 0 |
| DWELL HOLD-OVER TIMER (0-255) | 0 |
| LATCH CALL? | N |
| LINK TO NEXT PREEMPT? | N |
| ENABLE BACKUP PROTECTION? | N |
| HOLD CLEAR 1 PHASES DURING DELAY? | N |
| FAST GREEN FLASH DWELL PHASES? | N |
| PED CLEARANCE THROUGH YELLOW? | N |
| INHIBIT OVERLAP GREEN EXTENSION? | N |
| SERVICE DURING SOFTWARE FLASH? | N |
| REST IN RED DURING DWELL INTERVAL? | N |
| FLASH DWELL INTERVAL? | N |
| ALLOW PEDS IN DWELL INTERVAL? | N |
| RE-TIME DWELL INTERVAL? | N |
| OVERLAPS: | ABCDEFGHIJKLMNPO |
| DWELL INT FLASH YELLOW | |
| OMIT OVERLAPS: | |

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0901T2
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A


Electrical Detail - Sheet 2 of 2
Signal Upgrade
Temporary Design 2
Construction Phase 2B

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

| | | |
|--------------------------|--|------------------------------|
| | Prepared for: US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | SEAL |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| REVISIONS INITI. DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 SIGNATURE DATE | SIG. INVENTORY NO. 14-0901T2 |

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND
 ←● DETECTED MOVEMENT
 ← UNDETECTED MOVEMENT (OVERLAP)
 - - - UNSIGNALIZED MOVEMENT
 ←- - - PEDESTRIAN MOVEMENT

QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|----|------|-------|
| | 01+6 | 02+6 | 04 | PRE3 | FLUSH |
| 11 | - | R | R | R | R |
| 21,22 | R | G | R | R | Y |
| 41,42 | R | R | G | G | R |
| 61,62 | G | G | R | R | Y |

SIGNAL FACE I.D.

All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART


| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|--------------------------|----------------------|-------------------------|-------------|----------|---|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY TIME | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | LOOP SYSTEM | NEW CARD | |
| 1A | 6X40 | 0 | * | Y | 1 | Y | Y | - | - | 3 | - | - | - | - | - | * |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4A | 6X40 | 0 | * | - | 4 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4B | 6X40 | 0 | * | - | 4 | Y | Y | - | - | 15 | - | - | - | - | - | * |
| **01 | 6X6 | 625 | * | Y | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |

* Multizone Microwave Detection
 ** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System

NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Phase 1 may be lagged.
4. Set all detector units to presence mode.
5. Reposition existing signal heads numbered 41,42,61, and 62.
6. Incorporate Microwave Detection system for vehicle detection.
7. Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
8. This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
9. When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
10. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | |
|-------------------------|-------|------------|-----|------------|
| | 1 | 2 | 4 | 6 |
| Min Green 1 * | 7 | 12 | 7 | 12 |
| Extension 1 * | 2.0 | 6.0 | 2.0 | 6.0 |
| Max Green 1 * | 25 | 90 | 30 | 90 |
| Yellow Clearance | 3.0 | 4.1 | 3.6 | 4.4 |
| Red Clearance | 2.9 | 1.4 | 2.1 | 1.0 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | - | 1.5 | - | 1.5 |
| Max Variable Initial * | - | 34 | - | 34 |
| Time Before Reduction * | - | 15 | - | 15 |
| Time To Reduce * | - | 30 | - | 30 |
| Minimum Gap | - | 3.0 | - | 3.0 |
| Recall Mode | - | MIN RECALL | - | MIN RECALL |
| Vehicle Call Memory | - | YELLOW | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

* Time defaults to time used for phase during normal operation

LEGEND

| PROPOSED | EXISTING |
|--|-----------------------------------|
| ○ → Traffic Signal Head | ● → Traffic Signal Head |
| ○ → Modified Signal Head | N/A |
| □ → Pedestrian Signal Head With Push Button & Sign | □ → Pedestrian Signal Head |
| ○ → Signal Pole with Guy | ○ → Signal Pole with Guy |
| ○ → Signal Pole with Sidewalk Guy | ○ → Signal Pole with Sidewalk Guy |
| ⊠ → Inductive Loop Detector | ⊠ → Inductive Loop Detector |
| ⊠ → Controller & Cabinet | ⊠ → Controller & Cabinet |
| □ → Junction Box | □ → Junction Box |
| - - - → 2-in Underground Conduit | - - - → 2-in Underground Conduit |
| N/A → Right of Way | - - - → Right of Way |
| → → Directional Arrow | → → Directional Arrow |
| ▬ → Construction Zone | N/A |
| ▬ → Microwave Detection Zone | ▬ → Microwave Detection Zone |
| (A) → No Left Turn Sign (R3-2) | (A) → No Left Turn Sign (R3-2) |
| (B) → No Right Turn Sign (R3-1) | (B) → No Right Turn Sign (R3-1) |
| (C) → "YIELD" Sign (R1-2) | (C) → "YIELD" Sign (R1-2) |

Signal Upgrade
 Temporary Design 3
 Construction Phases 2C,3,3A


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|---|--|--|--|
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031464 NATASHA R. SIMMONS | |
| 750 N. Greenfield Pkwy, Garner, NC 27525 HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | | DocuSigned by: Natasha R. Simmons 1/26/2019 SIGNATURE DATE SIG. INVENTORY NO. 14-090173 | |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|-----|-------|-------|----|-------|-------|----|-------|-------|-----|-----|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | 11 | 21,22 | NU | NU | 41,42 | NU | NU | 61,62 | NU | NU | NU | NU |
| RED | | 128 | | | 101 | | | 134 | | | | |
| YELLOW | | 129 | | | 102 | | | 135 | | | | |
| GREEN | | 130 | | | 103 | | | 136 | | | | |
| RED ARROW | 125 | | | | | | | | | | | |
| YELLOW ARROW | 126 | | | | | | | | | | | |
| GREEN ARROW | 127 | | | | | | | | | | | |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S1,S2,S5,S8
 PHASES USED.....1,2,4,6
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | 14U | 41 | 3 | * 4 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 **Multizone Microwave Detector Zone. See Special Detector Note.



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0901T3
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 3
 Construction Phases 2C,3,3A

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


| | | | | | |
|---|--|--|--|------|--|
| | Prepared for: | | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | SEAL |
| | Division 14 Henderson Co. Hendersonville | | PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | | |
| REVISIONS | | | INIT. | DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 |
| HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | | | | | SIG. INVENTORY NO. 14-0901T3 |

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL WHEN LEAVING PREEMPTOR SEQUENCE

(program controller as shown below)

- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.



NOTE:
INHIBITS PREEMPT
BY DISCONNECTING
QUEUE LOOP

NOTE:
RECONNECTS QUEUE
LOOP IF ALL
PHASES WITH
CALLS HAVE BEEN
SERVED

NOTE:
TIMEOUT FOR
RECONNECTING
QUEUE LOOP

VEHICLE DETECTOR #4 SETTINGS FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS). PRESS '+' UNTIL DETECTOR #4 IS REACHED.

```

VEHICLE DETECTOR #4 SETTINGS (+,-,1-64)
SETTING: (Y/N)
ENABLE DETECTOR.....Y
ENABLE LOGGING.....N
ENABLE DIAGNOSTICS.....N
SPEED TRAP.....N
CALL DETECTOR.....N
EXTENSION DETECTOR.....N
MODE 2 STOP BAR.....N
SWITCHING DETECTOR.....N
DUPLICATING DETECTOR.....N
ENABLE FULL TIME DELAY.....N
IF FAILED, SET MIN RECALL?.....N
IF FAILED, SET MAX1 RECALL?.....N
IF FAILED, SET MAX2 RECALL?.....N
PHASE# :12345678910111213141516
PHASES ASSIGNED :
SWITCH/DUPLICATE:
LOOP SIZE (0-255 FT).....6
SPEED TRAP DISTANCE (0-255 FT).....0
STOP BAR TIME (0-255 SEC).....0
STRETCH (0-25.5 SEC).....0.0
DELAY (0-255 SEC).....0
MAX CALLS/MIN (0-255).....255
MIN CALLS/DIAGNOSTIC PERIOD (0-255).....0
MAX OCCUPANCY (0-100%).....100
EXTENSION DISABLE TIME (0-255 SEC).....0
QUEUE MAX OCCUPANCY TIME (0-255).....5
QUEUE GAP RESET TIME (0-25.5).....0.1
PREEMPTION INDEX FOR QUEUE (0-10).....3
  
```

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

| PREEMPTION #3 | INTERVAL/TIMING | SETTINGS (NEXT:1-10) | CLEAR/DWELL PHASES |
|---------------|-----------------|----------------------|--------------------|
| 1 | 255 0.0 0.0 | | X |
| 2 | 0 0.0 0.0 | | |
| 3 | 0 0.0 0.0 | | |
| 4 | 0 0.0 0.0 | | |
| 5 | 1 0.0 0.0 | X X | |

EXIT CALLS

| OPTIONS | VALUES |
|--------------------------------------|--------|
| PRIORITY (Y/N TO SELECT) | MED |
| DELAY TIMER (0-255 SEC) | 0.0 |
| MIN GREEN BEFORE PRE (0= DEFAULT) | 12 |
| PED CLEAR BEFORE PRE (0= DEFAULT) | 0 |
| YELLOW CLEAR BEFORE PRE (0= DEFAULT) | 4.4 |
| RED CLEAR BEFORE PRE (0= DEFAULT) | 1.4 |
| DWELL MIN TIMER (0-255 SEC) | 30 |
| DWELL MAX TIMER (0=OFF,1-255MIN) | 0 |
| DWELL HOLD-OVER TIMER (0-255) | 0 |
| LATCH CALL? | N |
| LINK TO NEXT PREEMPT? | N |
| ENABLE BACKUP PROTECTION? | N |
| HOLD CLEAR 1 PHASES DURING DELAY? | N |
| FAST GREEN FLASH DWELL PHASES? | N |
| PED CLEARANCE THROUGH YELLOW? | N |
| INHIBIT OVERLAP GREEN EXTENSION? | N |
| SERVICE DURING SOFTWARE FLASH? | N |
| REST IN RED DURING DWELL INTERVAL? | N |
| FLASH DWELL INTERVAL? | N |
| ALLOW PEDS IN DWELL INTERVAL? | N |
| RE-TIME DWELL INTERVAL? | N |

OVERLAPS: ABCDEFGHIJKLMNPO
 DWELL INT FLASH YELLOW
 OMIT OVERLAPS:


THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0901T3
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A

Electrical Detail - Sheet 2 of 2
Signal Upgrade
Temporary Design 3
Construction Phases 2C,3,3A

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

| | | | | |
|-----------|---|-------|---|--|
| | Prepared for: | | Division 14 Henderson Co. Hendersonville US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | |
| | HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | | | |
| REVISIONS | | INIT. | DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 SIGNATURE DATE SIG. INVENTORY NO. 14-0901T3 |

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND
 ←● DETECTED MOVEMENT
 ← UNDETECTED MOVEMENT (OVERLAP)
 ← UN SIGNALIZED MOVEMENT
 ← PEDESTRIAN MOVEMENT

QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|----|------|-------|
| | 01+6 | 02+6 | 04 | PRE3 | FLUSH |
| 11 | — | R | R | R | R |
| 21,22 | R | G | R | R | Y |
| 41,42 | R | R | G | G | R |
| 61,62 | G | G | R | R | Y |

SIGNAL FACE I.D.

All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|--------------------------|----------------------|-------------------------|-------------|----------|---|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY TIME | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | SYSTEM LOOP | NEW CARD | |
| 1A | 6X40 | 0 | * | Y | 1 | Y | Y | - | - | 3 | - | - | - | - | - | * |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4A | 6X40 | 0 | * | - | 4 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4B | 6X40 | 0 | * | - | 4 | Y | Y | - | - | 15 | - | - | - | - | - | * |
| **01 | 6X6 | 625 | * | - | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |

* Multizone Microwave Detection
 ** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 1 may be lagged.
- Set all detector units to presence mode.
- Reposition existing signal heads numbered 21,22,61,62, and signs A and B.
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
- When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.

OASIS 2070 TIMING CHART


| FEATURE | PHASE | | | |
|-------------------------|-------|------------|-----|------------|
| | 1 | 2 | 4 | 6 |
| Min Green 1 * | 7 | 12 | 7 | 12 |
| Extension 1 * | 2.0 | 6.0 | 2.0 | 6.0 |
| Max Green 1 * | 25 | 90 | 30 | 90 |
| Yellow Clearance | 3.0 | 4.1 | 3.6 | 4.4 |
| Red Clearance | 2.6 | 1.2 | 2.1 | 1.0 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | - | 1.5 | - | 1.5 |
| Max Variable Initial * | - | 34 | - | 34 |
| Time Before Reduction * | - | 15 | - | 15 |
| Time To Reduce * | - | 30 | - | 30 |
| Minimum Gap | - | 3.0 | - | 3.0 |
| Recall Mode | - | MIN RECALL | - | MIN RECALL |
| Vehicle Call Memory | - | YELLOW | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

* Time defaults to time used for phase during normal operation



PROPOSED


| | | | |
|-----|--|-----|----------|
| ○ | Traffic Signal Head | ● | EXISTING |
| ○ | Modified Signal Head | N/A | |
| ⊥ | Sign | ⊥ | |
| ⊥ | Pedestrian Signal Head With Push Button & Sign | ⊥ | |
| ⊥ | Signal Pole with Guy | ⊥ | |
| ⊥ | Signal Pole with Sidewalk Guy | ⊥ | |
| ⊥ | Inductive Loop Detector | ⊥ | |
| ⊥ | Controller & Cabinet | ⊥ | |
| ⊥ | Junction Box | ⊥ | |
| ⊥ | 2-in Underground Conduit | ⊥ | |
| N/A | Right of Way | → | |
| → | Directional Arrow | → | |
| ▬ | Construction Zone | N/A | |
| ▬ | Microwave Detection Zone | ▬ | |
| A | No Left Turn Sign (R3-2) | A | |
| B | No Right Turn Sign (R3-1) | B | |
| C | "YIELD" Sign (R1-2) | C | |

Signal Upgrade
 Temporary Design 4
 Construction Phase 3B

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|--|--|------------------------|--|
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | REVISIONS: INITI. DATE | |


HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997



DocuSigned by:
 Natasha R. Simmons 1/26/2019
 SIGNATURE DATE
 SIG. INVENTORY NO. 14-090174

EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|-----|-------|-------|----|-------|-------|----|-------|-------|-----|-----|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | 11 | 21,22 | NU | NU | 41,42 | NU | NU | 61,62 | NU | NU | NU | NU |
| RED | | 128 | | | 101 | | | 134 | | | | |
| YELLOW | | 129 | | | 102 | | | 135 | | | | |
| GREEN | | 130 | | | 103 | | | 136 | | | | |
| RED ARROW | 125 | | | | | | | | | | | |
| YELLOW ARROW | 126 | | | | | | | | | | | |
| GREEN ARROW | 127 | | | | | | | | | | | |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S1,S2,S5,S8
 PHASES USED.....1,2,4,6
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | 14U | 41 | 3 | * 4 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 **Multizone Microwave Detector Zone. See Special Detector Note.



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0901T4
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 4
 Construction Phase 3B


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | | | |
|---|--|--|--|------|--|
| | Prepared for: | | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | SEAL |
| | Division 14 Henderson Co. Hendersonville | | PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | | |
| REVISIONS | | | INIT. | DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 |
| HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | | | | | SIG. INVENTORY NO. 14-0901T4 |


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL WHEN LEAVING PREEMPTOR SEQUENCE

(program controller as shown below)

- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
 - FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).
- NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.




PRESS '+'




NOTE:
INHIBITS PREEMPT
BY DISCONNECTING
QUEUE LOOP

PRESS '+'



NOTE:
RECONNECTS QUEUE
LOOP IF ALL
PHASES WITH
CALLS HAVE BEEN
SERVED

PRESS '+'



NOTE:
TIMEOUT FOR
RECONNECTING
QUEUE LOOP

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

VEHICLE DETECTOR #4 SETTINGS FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS), PRESS '+' UNTIL DETECTOR #4 IS REACHED.

```

VEHICLE DETECTOR #4 SETTINGS (+,-,1-64)
SETTING: (Y/N)
ENABLE DETECTOR.....Y
ENABLE LOGGING.....N
ENABLE DIAGNOSTICS.....N
SPEED TRAP.....N
CALL DETECTOR.....N
EXTENSION DETECTOR.....N
MODE 2 STOP BAR.....N
SWITCHING DETECTOR.....N
DUPLICATING DETECTOR.....N
ENABLE FULL TIME DELAY.....N
IF FAILED, SET MIN RECALL?.....N
IF FAILED, SET MAX1 RECALL?.....N
IF FAILED, SET MAX2 RECALL?.....N
PHASE# :12345678910111213141516
PHASES ASSIGNED :
SWITCH/DUPLICATE:
LOOP SIZE (0-255 FT).....6
SPEED TRAP DISTANCE (0-255 FT).....0
STOP BAR TIME (0-255 SEC).....0
STRETCH (0-25.5 SEC).....0.0
DELAY (0-255 SEC).....0
MAX CALLS/MIN (0-255).....255
MIN CALLS/DIAGNOSTIC PERIOD (0-255).....0
MAX OCCUPANCY (0-100%).....100
EXTENSION DISABLE TIME (0-255 SEC).....0
QUEUE MAX OCCUPANCY TIME (0-255).....5
QUEUE GAP RESET TIME (0-25.5).....0.1
PREEMPTION INDEX FOR QUEUE (0-10).....3
    
```

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

```



PREEMPTION #3 SETTINGS (NEXT:1-10)
INTERVAL/TIMING CLEAR/DWELL PHASES
GRN YEL RED 12345678910111213141516
1 255 0.0 0.0 X
2 0 0.0 0.0
3 0 0.0 0.0
4 0 0.0 0.0
5 1 0.0 0.0 X X
EXIT CALLS
OPTIONS
PRIORITY (Y/N TO SELECT) .....MED
DELAY TIMER (0-255 SEC) .....0.0
MIN GREEN BEFORE PRE (0= DEFAULT).....12
PED CLEAR BEFORE PRE (0= DEFAULT).....0
YELLOW CLEAR BEFORE PRE (0= DEFAULT).....4.4
RED CLEAR BEFORE PRE (0= DEFAULT).....1.2
DWELL MIN TIMER (0-255 SEC) .....30
DWELL MAX TIMER (0=OFF,1-255MIN) .....0
DWELL HOLD-OVER TIMER (0-255) .....0
LATCH CALL? .....N
LINK TO NEXT PREEMPT? .....N
ENABLE BACKUP PROTECTION? .....N
HOLD CLEAR 1 PHASES DURING DELAY? .....N
FAST GREEN FLASH DWELL PHASES? .....N
PED CLEARANCE THROUGH YELLOW? .....N
INHIBIT OVERLAP GREEN EXTENSION? .....N
SERVICE DURING SOFTWARE FLASH? .....N
REST IN RED DURING DWELL INTERVAL? ..N
FLASH DWELL INTERVAL? .....N
ALLOW PEDS IN DWELL INTERVAL? .....N
RE-TIME DWELL INTERVAL? .....N
OVERLAPS: ABCDEFGHIJKLMNPO
DWELL INT FLASH YELLOW
OMIT OVERLAPS:
    
```

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0901T4
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A


Electrical Detail - Sheet 2 of 2
Signal Upgrade
Temporary Design 4
Construction Phase 3B

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1564
(919) 546-8997

| | | | |
|---|--|--|--|
|  | Prepared for: US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | |  |
| | Division 14 Henderson Co. Hendersonville | SEAL 031464 ENGINEER NATASHA R. SIMMONS | |
| PLAN DATE: September 2018 | REVIEWED BY: A.D. Klinksiek | PREPARED BY: A.H. Thornburg | REVIEWED BY: N.R. Simmons |
| REVISIONS | INIT. | DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 SIGNATURE DATE SIG. INVENTORY NO. 14-0901T4 |

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND

- ←● DETECTED MOVEMENT
- ← UNDETECTED MOVEMENT (OVERLAP)
- ← UNSIGNALIZED MOVEMENT
- ← PEDESTRIAN MOVEMENT

QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|----|-------|-------|
| | 01+6 | 02+6 | 04 | PRE3 | FLUSH |
| 11 | — | — | — | — | — |
| 21,22 | R | G | R | R | Y |
| 41,42 | R | R | G | 21,22 | 41,42 |
| 61,62 | G | G | R | 61,62 | — |

SIGNAL FACE I.D.

All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART


| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|---------------------|----------------------|-------------------------|------|----------|---|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | LOOP | NEW CARD | |
| 1A | 6X40 | 0 | * | Y | 1 | Y | Y | - | - | 3 | - | - | - | - | - | * |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4A | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | - | - | - | - | - | - | * |
| 4B | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | 15 | - | - | - | - | - | * |
| **01 | 6X6 | 625 | * | Y | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |

* Multizone Microwave Detection
** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 1 may be lagged.
- Set all detector units to presence mode.
- Reposition existing signal heads numbered 21,22,61,62, and signs A and B.
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
- When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | |
|-------------------------|-------|------------|-----|------------|
| | 1 | 2 | 4 | 6 |
| Min Green 1 * | 7 | 12 | 7 | 12 |
| Extension 1 * | 2.0 | 6.0 | 2.0 | 6.0 |
| Max Green 1 * | 25 | 90 | 30 | 90 |
| Yellow Clearance | 3.0 | 4.1 | 3.6 | 4.4 |
| Red Clearance | 2.8 | 1.3 | 2.1 | 1.0 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | - | 1.5 | - | 1.5 |
| Max Variable Initial * | - | 34 | - | 34 |
| Time Before Reduction * | - | 15 | - | 15 |
| Time To Reduce * | - | 30 | - | 30 |
| Minimum Gap | - | 3.0 | - | 3.0 |
| Recall Mode | - | MIN RECALL | - | MIN RECALL |
| Vehicle Call Memory | - | YELLOW | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

* Time defaults to time used for phase during normal operation

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

PROPOSED **EXISTING**

- Traffic Signal Head
- Modified Signal Head
- ⊥ Sign
- ⊥ Pedestrian Signal Head With Push Button & Sign
- ⊥ Signal Pole with Guy
- ⊥ Signal Pole with Sidewalk Guy
- ⊥ Inductive Loop Detector
- ⊥ Controller & Cabinet
- ⊥ Junction Box
- ⊥ 2-in Underground Conduit
- Right of Way
- Directional Arrow
- █ Construction Zone
- █ Microwave Detection Zone
- ⊙ No Left Turn Sign (R3-2)
- ⊙ No Right Turn Sign (R3-1)
- ⊙ "YIELD" Sign (R1-2)


Signal Upgrade
Temporary Design 5
Construction Phase 3C

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | |
|---|--|---|
| | <p>US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps</p> | |
| | <p>Division 14 Henderson Co. Hendersonville</p> | <p>PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek</p> |
| <p>750 N. Greenfield Pkwy, Garner, NC 27525</p> | <p>PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons</p> | <p>SEAL NORTH CAROLINA PROFESSIONAL ENGINEER NATASHA R. SIMMONS</p> |
| <p>REVISIONS</p> | <p>INITI. DATE</p> | <p>DocuSigned by: Natasha R. Simmons 1/26/2019</p> |
| <p>0 40 1"=40'</p> | <p>SIG. INVENTORY NO. 14-0901T5</p> | |

EDI MODEL 2018ECLIP-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|-----|-------|-------|----|-------|-------|----|-------|-------|-----|-----|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | 11 | 21,22 | NU | NU | 41,42 | NU | NU | 61,62 | NU | NU | NU | NU |
| RED | | 128 | | | 101 | | | 134 | | | | |
| YELLOW | | 129 | | | 102 | | | 135 | | | | |
| GREEN | | 130 | | | 103 | | | 136 | | | | |
| RED ARROW | 125 | | | | | | | | | | | |
| YELLOW ARROW | 126 | | | | | | | | | | | |
| GREEN ARROW | 127 | | | | | | | | | | | |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S1,S2,S5,S8
 PHASES USED.....1,2,4,6
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | 14U | 41 | 3 | * 4 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 ** Multizone Microwave Detector Zone. See Special Detector Note.



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0901T5
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 5
 Construction Phase 3C

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | | | |
|-----------------------------|--|-----------------------------|---|--|--|
| | Prepared for: | | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | | SEAL 031464 NATASHA R. SIMMONS | | |
| PLAN DATE: September 2018 | | REVIEWED BY: A.D. Klinksiek | | DocuSigned by: Natasha R. Simmons 4/26/2019 | |
| PREPARED BY: A.H. Thornburg | | REVIEWED BY: N.R. Simmons | | SIGNATURE DATE | |
| REVISIONS | | INIT. DATE | | SIG. INVENTORY NO. 14-0901T5 | |


HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL WHEN LEAVING PREEMPTOR SEQUENCE


(program controller as shown below)

1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS), SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.




PRESS '+'




NOTE:
INHIBITS PREEMPT
BY DISCONNECTING
QUEUE LOOP

PRESS '+'



NOTE:
RECONNECTS QUEUE
LOOP IF ALL
PHASES WITH
CALLS HAVE BEEN
SERVED

PRESS '+'



NOTE:
TIMEOUT FOR
RECONNECTING
QUEUE LOOP

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

VEHICLE DETECTOR #4 SETTINGS FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS), PRESS '+' UNTIL DETECTOR #4 IS REACHED.

```

VEHICLE DETECTOR #4 SETTINGS (+,-,1-64)
SETTING: (Y/N)
ENABLE DETECTOR.....Y
ENABLE LOGGING.....N
ENABLE DIAGNOSTICS.....N
SPEED TRAP.....N
CALL DETECTOR.....N
EXTENSION DETECTOR.....N
MODE 2 STOP BAR.....N
SWITCHING DETECTOR.....N
DUPLICATING DETECTOR.....N
ENABLE FULL TIME DELAY.....N
IF FAILED, SET MIN RECALL?.....N
IF FAILED, SET MAX1 RECALL?.....N
IF FAILED, SET MAX2 RECALL?.....N
PHASE# :12345678910111213141516
PHASES ASSIGNED :
SWITCH/DUPLICATE:
LOOP SIZE (0-255 FT).....6
SPEED TRAP DISTANCE (0-255 FT).....0
STOP BAR TIME (0-255 SEC).....0
STRETCH (0-25.5 SEC).....0.0
DELAY (0-255 SEC).....0
MAX CALLS/MIN (0-255).....255
MIN CALLS/DIAGNOSTIC PERIOD (0-255).0
MAX OCCUPANCY (0-100%).....100
EXTENSION DISABLE TIME (0-255 SEC)..0
QUEUE MAX OCCUPANCY TIME (0-255)...5
QUEUE GAP RESET TIME (0-25.5).....0.1
PREEMPTION INDEX FOR QUEUE (0-10)...3

```

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

| PREEMPTION #3 | INTERVAL/TIMING | SETTINGS (NEXT:1-10) | CLEAR/DWELL PHASES |
|---------------|-----------------|----------------------|-------------------------|
| 1 | 255 0.0 0.0 | | 12345678910111213141516 |
| 2 | 0 0.0 0.0 | | X |
| 3 | 0 0.0 0.0 | | |
| 4 | 0 0.0 0.0 | | |
| 5 | 1 0.0 0.0 | X X | |

EXIT CALLS

OPTIONS


PRIORITY (Y/N TO SELECT)MED
 DELAY TIMER (0-255 SEC)0.0
 MIN GREEN BEFORE PRE (0= DEFAULT)...12
 PED CLEAR BEFORE PRE (0= DEFAULT)...0
 YELLOW CLEAR BEFORE PRE (0= DEFAULT)...4.4
 RED CLEAR BEFORE PRE (0= DEFAULT)...1.3
 DWELL MIN TIMER (0-255 SEC)30
 DWELL MAX TIMER (0=OFF,1-255MIN) ...0
 DWELL HOLD-OVER TIMER (0-255)0
 LATCH CALL?N
 LINK TO NEXT PREEMPT?N
 ENABLE BACKUP PROTECTION?N
 HOLD CLEAR 1 PHASES DURING DELAY? ...N
 FAST GREEN FLASH DWELL PHASES?N
 PED CLEARANCE THROUGH YELLOW?N
 INHIBIT OVERLAP GREEN EXTENSION? ...N
 SERVICE DURING SOFTWARE FLASH?N
 REST IN RED DURING DWELL INTERVAL? ..N
 FLASH DWELL INTERVAL?N
 ALLOW PEDS IN DWELL INTERVAL?N
 RE-TIME DWELL INTERVAL?N
 OVERLAPS: ABCDEFGHIJKLMNPO
 DWELL INT FLASH YELLOW
 OMIT OVERLAPS:

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0901T5
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A


Electrical Detail - Sheet 2 of 2
Signal Upgrade
Temporary Design 5
Construction Phase 3C

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997



| | |
|---|-----------------------------|
| US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | |
| Division 14 Henderson Co. Hendersonville | |
| PLAN DATE: September 2018 | REVIEWED BY: A.D. Klinksiek |
| PREPARED BY: A.H. Thornburg | REVIEWED BY: N.R. Simmons |
| REVISIONS | INIT. DATE |
| | |
| | |
| | |



DocuSigned by:
Natasha R. Simmons 4/26/2019
SIG. INVENTORY NO. 14-0901T5





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | |
|-------------|-------|------|------|-------|
| | 02+6 | 03+8 | 04+8 | FLUSH |
| 21,22 | | R | R | R |
| 41,42,43 | R | R | / | R |
| 61,62 | / | R | R | R |
| 81,82,83 | R | | | R |



OASIS 2070E LOOP & DETECTOR INSTALLATION CHART



| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | SYSTEM LOOP | NEW CARD | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|-------------|----------|------------|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | | | DELAY TIME |
| 2A | 6X40 | 0 | * | Y | 2 | Y | Y | - | - | - | - | * |
| 2B | 6X40 | 0 | * | Y | 2 | Y | Y | - | - | - | - | * |
| 4A | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | - | Y | - | 2.4 | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | - | Y | - | 2.4 | - | - | * |
| 6C | 6X40 | 0 | * | Y | 6 | Y | Y | - | - | - | - | * |
| 6D | 6X40 | 0 | * | Y | 6 | Y | Y | - | - | - | - | * |
| 8A | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | - | - | * |

* Multizone Microwave Detection

3 Phase Fully Actuated Asheville Signal System

NOTES


- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Omit phase 4 during phase 2+6 on.
- Program controller to clear from phase 2+6 to phase 4 by progressing through phase 3.
- Omit phase 3 during phase 4 on.
- Phase 3 provides red clearance time for vehicles traveling Northbound on US 25 (Asheville Hwy).
- Set all detector units to presence mode.
- Program all phases for "Red Rest".
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | | |
|-------------------------|-------|-----------|-----|-----|-----|
| | 2 | 3 (DUMMY) | 4 | 6 | 8 |
| Min Green 1 * | 10 | 1 | 10 | 10 | 10 |
| Extension 1 * | 2.0 | 0.0 | 2.0 | 2.0 | 2.0 |
| Max Green 1 * | 60 | 1 | 60 | 60 | 60 |
| Yellow Clearance | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Red Clearance | 2.8 | 7.4 | 2.5 | 5.0 | 5.4 |
| Red Revert | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Walk 1 * | - | - | - | - | - |
| Don't Walk 1 | - | - | - | - | - |
| Seconds Per Actuation * | - | - | - | - | - |
| Max Variable Initial * | - | - | - | - | - |
| Time Before Reduction * | - | - | - | - | - |
| Time To Reduce * | - | - | - | - | - |
| Minimum Gap | - | - | - | - | - |
| Recall Mode | - | - | - | - | - |
| Vehicle Call Memory | - | - | - | - | - |
| Dual Entry | ON | ON | ON | ON | ON |
| Simultaneous Gap | ON | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.



Signal Upgrade
Temporary Design 6
Construction Phase 5



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|------------------|--|---|------|
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031464 NATASHA R. SIMMONS | |
| REVISIONS | | DATE | DATE |
| 0 40 1" = 40' | | DocuSigned by: Natasha R. Simmons 14/09/2019 DATE | |

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Restore controller to factory defaults before programming per this electrical detail.
3. Program phases 2, 3, 4, 6, and 8 for Dual Entry.
4. Enable Simultaneous Gap-Out for all Phases.
5. Program phases 2 and 6 for Startup In Green.
6. Program phases 2, 3, 4, 6, and 8 for Red Rest.
7. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 |
|-----------------|----|-------|-------|----|----------|-------|----|-------|-------|-----|----------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 |
| SIGNAL HEAD NO. | NU | 21,22 | NU | NC | 41,42,43 | NU | NU | 61,62 | NU | NU | 81,82,83 |
| RED | | 128 | | | | | | 134 | | | 107 |
| YELLOW | | 129 | | | | | | | | | 108 |
| GREEN | | | | | | | | | | | |
| RED ARROW | | | | | 101 | | | | | | |
| YELLOW ARROW | | | | | 102 | | | 135 | | | |
| GREEN ARROW | | 130 | | | 103 | | | 136 | | | 109 |

NU = Not Used
NC = Not Connected

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S2,S5,S8,S11
 PHASES USED.....2,*3,4,6,8
 OVERLAPS.....NONE
 * PHASE USED FOR TIMING PURPOSES ONLY

DYNAMIC OMIT CONTROL PROGRAMMING

(program controller as shown below)

1. From Main Menu press '2' (Phase Control), then '1' (Phase Control Functions). Scroll to the bottom of the menu and enable Dynamic/Backup Control Functions 1 and 2.
2. From Phase Control Functions Menu press '2' (Dynamic/Backup Control Functions).

```

DYNAMIC/BACKUP CONTROL FUNCTION #01
OVERLAPS:;ABCDEFGHIJKLMNPO
IF OVERLAPS ARE ACTIVE ;
OR PHASES:;12345678910111213141516
IF PHASES ARE ON: X
OMIT PHASES : X
CALL PHASES : X
    
```

PRESS 'NEXT'

```

DYNAMIC/BACKUP CONTROL FUNCTION #02
OVERLAPS:;ABCDEFGHIJKLMNPO
IF OVERLAPS ARE ACTIVE ;
OR PHASES:;12345678910111213141516
IF PHASES ARE ON: X
OMIT PHASES : X
CALL PHASES : X
    
```


DYNAMIC OMIT PROGRAMMING COMPLETE

NOTE: THIS PROGRAMMING ENSURES THAT PHASE 3 WILL BE SERVED PRIOR TO PHASE 4 WHEN CONTROLLER IS ADVANCING FROM 2+6.

PHASE 3 IS USED TO PROVIDE EXTENDED RED CLEARANCE BEFORE SERVING PHASE 4.

INPUT FILE POSITION LAYOUT

(front view)



EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
ST = STOP TIME

SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

PHASE SEQUENCE PROGRAMMING DETAIL

(program controller as shown below)

FROM OASIS LOCAL CONTROLLER MAIN MENU
SELECT: 4 PHASE SEQUENCE

| PHASE SEQUENCE: PAGE 1 | NEXT: PAGES | |
|------------------------|-------------|----------------------------|
| RNG:LEAD | BARRIER 1 | X-LAG:LEAD BARRIER 2 X-LAG |
| 1 0 | 2 0 | 3 0 |
| 2 0 | 6 0 | 8 0 |
| 3 0 | 0 0 | 0 0 |
| 4 0 | 0 0 | 0 0 |

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0901T6
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail
Signal Upgrade
Temporary Design 6
Construction Phase 5

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|--|--|-----------------------------------|--|
| | Prepared for: US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | SEAL 031464 NATASHA R. SIMMONS | |
| PLAN DATE: September 2018 PREPARED BY: A.H. Thornburg | REVIEWED BY: A.D. Klinksiek REVIEWED BY: N.R. Simmons | REVISIONS INIT. DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 DATE SIG. INVENTORY NO. 14-0901T6 |

HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997






TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | |
|-------------|-------|------|------|-------|
| | 02+6 | 03+8 | 04+8 | FLASH |
| 21,22,23 | | R | R | R |
| 24,25 | / | R | R | R |
| 41,42,43,44 | / | R | R | R |
| 61,62,63,64 | / | R | R | R |
| 81,82 | R | | | R |
| 83,84 | / | / | / | / |

SIGNAL FACE I.D.




OASIS 2070E LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | SYSTEM LOOP | NEW CARD | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|--------------|-------------|----------|------------|
| | | | | | PHASE | CALLING | EXTENSION | STRETCH TIME | | | DELAY TIME |
| 2A | 6X40 | 0 | 2-4-2 | Y | 2 | Y | Y | - | - | - | Y |
| 2B | 6X40 | 0 | 2-4-2 | Y | 2 | Y | Y | - | - | - | Y |
| 2C | 6X40 | 0 | 2-4-2 | Y | 2 | Y | Y | - | - | - | Y |
| 4A | 6X40 | 0 | 2-4-2 | Y | 3/4 | Y | Y | - | - | - | Y |
| 4B | 6X40 | 0 | 2-4-2 | Y | 3/4 | Y | Y | - | - | - | Y |
| 6A | 6X6 | 300 | 5 | Y | 6 | - | Y | - | 2.4 | - | Y |
| 6B | 6X6 | 300 | 5 | Y | 6 | - | Y | - | 2.4 | - | Y |
| 6C | 6X40 | 0 | 2-4-2 | Y | 6 | Y | Y | - | - | - | Y |
| 6D | 6X40 | 0 | 2-4-2 | Y | 6 | Y | Y | - | - | - | Y |
| 8A | 6X40 | 0 | 2-4-2 | Y | 8 | Y | Y | - | - | - | Y |
| 8B | 6X40 | 0 | 2-4-2 | Y | 8 | Y | Y | - | - | - | Y |
| S1 | 6X6 | +25 | 4 | Y | - | - | - | - | - | - | Y |
| S2 | 6X6 | +25 | 4 | Y | - | - | - | - | - | - | Y |
| S3 | 6X6 | +115 | 3 | Y | - | - | - | - | - | - | Y |
| S4 | 6X6 | +90 | 3 | Y | - | - | - | - | - | - | Y |
| S5 | 6X6 | +95 | 3 | Y | - | - | - | - | - | - | Y |
| S6 | 6X6 | +95 | 3 | Y | - | - | - | - | - | - | Y |
| S7 | 6X6 | +95 | 3 | Y | - | - | - | - | - | - | Y |
| S8 | 6X6 | +10 | 3 | Y | - | - | - | - | - | - | Y |
| S9 | 6X6 | +10 | 3 | Y | - | - | - | - | - | - | Y |

3 Phase Fully Actuated Asheville Signal System

NOTES


- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Omit phase 4 during phase 2+6 on.
- Program controller to clear from phase 2+6 to phase 4 by progressing through phase 3.
- Omit phase 3 during phase 4 on.
- Phase 3 provides red clearance time for vehicles traveling Northbound on US 25 (Asheville Hwy).
- Set all detector units to presence mode.
- Program all phases for "Red Rest".
- Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- The cabinet should be designed to include Auxiliary Output file for future use.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | | |
|------------------------|-------|-----------|-----|-----|-----|
| | 2 | 3 (DUMMY) | 4 | 6 | 8 |
| Min Green 1* | 10 | 1 | 10 | 10 | 10 |
| Extension 1* | 2.0 | 0.0 | 2.0 | 2.0 | 2.0 |
| Max Green 1* | 60 | 1 | 60 | 60 | 60 |
| Yellow Clearance | 3.0 | 3.0 | 3.0 | 4.1 | 3.0 |
| Red Clearance | 3.6 | 6.5 | 3.4 | 2.2 | 5.4 |
| Red Revert | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Walk 1* | - | - | - | - | - |
| Don't Walk 1 | - | - | - | - | - |
| Seconds Per Actuation* | - | - | - | - | - |
| Max Variable Initial* | - | - | - | - | - |
| Time Before Reduction* | - | - | - | - | - |
| Time To Reduce* | - | - | - | - | - |
| Minimum Gap | - | - | - | - | - |
| Recall Mode | - | - | - | - | - |
| Vehicle Call Memory | - | - | - | - | - |
| Dual Entry | ON | ON | ON | ON | ON |
| Simultaneous Gap | ON | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.



Signal Upgrade - Final Design

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps

Division 14 Henderson Co. Hendersonville

PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek

PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

SEAL

N. R. Simmons
Professional Engineer
No. 031464

REVISIONS: _____

DATE: _____

Signature: _____




DATE: _____

DocuSigned by: *Natasha R. Simmons* 14-0901



EDI MODEL 2018ECLIP-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Program phases 2, 3, 4, 6, and 8 for Dual Entry.
3. Enable Simultaneous Gap-Out for all Phases.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2, 3, 4, 6, and 8 for Red Rest.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 | AUX S1 | AUX S2 | AUX S3 | AUX S4 | AUX S5 | AUX S6 |
|-----------------|----|----------|-------|-----|----|-------------|----|----|-------------|-----|-----|-------|--------|--------|--------|--------|--------|--------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 | 9 | 10 | 17 | 11 | 12 | 18 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED | OLA | OLB | SPARE | OLC | OLD | SPARE |
| SIGNAL HEAD NO. | NU | 21,22,23 | 24,25 | NU | NC | 41,42,43,44 | NU | NU | 61,62,63,64 | NU | NU | 81,82 | 83,84 | NU | NU | NU | NU | NU |
| RED | | 128 | | | | | | | 134 | | | 107 | | | | | | |
| YELLOW | | 129 | | | | | | | | | | 108 | | | | | | |
| GREEN | | | | | | | | | | | | | | | | | | |
| RED ARROW | | | 128 | | | 101 | | | | | | | 107 | | | | | |
| YELLOW ARROW | | | 129 | | | 102 | | | 135 | | | | 108 | | | | | |
| GREEN ARROW | | | 130 | 130 | | 103 | | | 136 | | | | 109 | 109 | | | | |

NU = Not Used
NC = Not Connected

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....332 W/ AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
 LOAD SWITCHES USED.....S2,S5,S8,S11
 PHASES USED.....2,*3,4,6,8
 OVERLAPS.....NONE
 * PHASE USED FOR TIMING PURPOSES ONLY

DYNAMIC OMIT CONTROL PROGRAMMING

(program controller as shown below)

1. From Main Menu press '2' (Phase Control), then '1' (Phase Control Functions). Scroll to the bottom of the menu and enable Dynamic/Backup Control Functions 1 and 2.
2. From Phase Control Functions Menu press '2' (Dynamic/Backup Control Functions).

DYNAMIC/BACKUP CONTROL FUNCTION #01
 OVERLAPS: ABCDEFGHIJKLMNPO
 IF OVERLAPS ARE ACTIVE :
 OR PHASES: 12345678910111213141516
 IF PHASES ARE ON: X X
 OMIT PHASES : X
 CALL PHASES : X

PRESS 'NEXT'

DYNAMIC/BACKUP CONTROL FUNCTION #02
 OVERLAPS: ABCDEFGHIJKLMNPO
 IF OVERLAPS ARE ACTIVE :
 OR PHASES: 12345678910111213141516
 IF PHASES ARE ON: X
 OMIT PHASES : X
 CALL PHASES : X


DYNAMIC OMIT PROGRAMMING COMPLETE

NOTE: THIS PROGRAMMING ENSURES THAT PHASE 3 WILL BE SERVED PRIOR TO PHASE 4 WHEN CONTROLLER IS ADVANCING FROM 2+6.

PHASE 3 IS USED TO PROVIDE EXTENDED RED CLEARANCE BEFORE SERVING PHASE 4.

INPUT FILE POSITION LAYOUT

(front view)



EX.: 1A, 2A, ETC. = LOOP NO.'S


FS = FLASH SENSE
ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 2A | TB2-5,6 | I2U | 39 | 1 | 2 | 2 | Y | Y | | | |
| 2B | TB2-7,8 | I2L | 43 | 5 | 12 | 2 | Y | Y | | | |
| 2C | TB2-9,10 | I3U | 63 | 25 | 32 | 2 | Y | Y | | | |
| 4A | TB4-9,10 | I6U | 41 | 3 | 4 | 3/4 | Y | Y | | | |
| 4B | TB4-11,12 | I6L | 45 | 7 | 14 | 3/4 | Y | Y | | | |
| * S1 | TB6-1,2 | I7U | 65 | 27 | 34 | SYS | | | | | |
| * S2 | TB6-3,4 | I7L | 78 | 40 | 44 | SYS | | | | | |
| * S3 | TB6-9,10 | I9U | 60 | 22 | 11 | SYS | | | | | |
| * S4 | TB6-11,12 | I9L | 62 | 24 | 13 | SYS | | | | | |
| 6A | TB3-5,6 | J2U | 40 | 2 | 6 | 6 | | Y | | 2,4 | |
| 6B | TB3-7,8 | J2L | 44 | 6 | 16 | 6 | | Y | | 2,4 | |
| 6C | TB3-9,10 | J3U | 64 | 26 | 36 | 6 | Y | Y | | | |
| 6D | TB3-11,12 | J3L | 77 | 39 | 46 | 6 | Y | Y | | | |
| * S9 | TB5-5,6 | J5U | 57 | 19 | 7 | SYS | | | | | |
| 8A | TB5-9,10 | J6U | 42 | 4 | 8 | 8 | Y | Y | | | |
| 8B | TB5-11,12 | J6L | 46 | 8 | 18 | 8 | Y | Y | | | |
| * S5 | TB7-1,2 | J7U | 66 | 28 | 38 | SYS | | | | | |
| * S6 | TB7-3,4 | J7L | 79 | 41 | 48 | SYS | | | | | |
| * S7 | TB7-9,10 | J9U | 59 | 21 | 15 | SYS | | | | | |
| * S8 | TB7-11,12 | J9L | 61 | 23 | 17 | SYS | | | | | |

* SYSTEM DETECTOR ONLY. REMOVE THE VEHICLE PHASE ASSIGNED TO THIS DETECTOR IN THE DEFAULT PROGRAMMING.

INPUT FILE POSITION LEGEND: J2L



PHASE SEQUENCE PROGRAMMING DETAIL

(program controller as shown below)


FROM OASIS LOCAL CONTROLLER MAIN MENU
SELECT: 4 PHASE SEQUENCE

| PHASE SEQUENCE: PAGE 1 | NEXT: PAGES) | | | | | | |
|------------------------|--------------|-------------|-----------|-------|---|---|---|
| RNG: LEAD | BARRIER 1 | X-LAG: LEAD | BARRIER 2 | X-LAG | | | |
| 1 | 0 | 2 | 0 | 3 | 4 | 0 | 0 |
| 2 | 0 | 6 | 0 | 0 | 8 | 0 | 0 |
| 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

THIS ELECTRICAL DETAIL IS FOR
 THE SIGNAL DESIGN: 14-0901
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Final Design
Signal Upgrade

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED





US 25 / US 25 Business
 (Asheville Highway) at
 I-26 EB Ramps

Division 14 Henderson Co. Hendersonville


PLAN DATE: September 2018 REVIEWED BY: A.D. Klinskiak
 PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

| REVISIONS | INIT. | DATE |
|-----------|-------|------|
| | | |




DocuSigned by:
 Natasha R. Simmons 4/26/2019
 DATE
 SIG. INVENTORY NO. 14-0901

Design Loading for METAL POLE NO. 1



Elevation View

Design Loading for METAL POLE NO. 2




Elevation View

SPECIAL NOTE


The contractor is responsible for verifying that the mast arm attachment height (H1) will provide the "Design Height" clearance from the roadway before submitting final shop drawings for approval. Verify elevation data below which was obtained by field measurement or from available project survey data.

Elevation Data for Mast Arm Attachment (H1)


| Elevation Differences for: | Pole 1 | Pole 2 |
|---|-----------|-----------|
| Baseline reference point at CL Foundation @ ground level | 0.0 ft. | 0.0 ft. |
| Elevation difference at High point of roadway surface | +0.24 ft. | +1.16 ft. |
| Elevation difference at Edge of travelway or face of curb | -0.27 ft. | -0.64 ft. |



POLE RADIAL ORIENTATION



8 BOLT BASE PLATE DETAIL



BASE PLATE TEMPLATE & ANCHOR BOLT LOCK PLATE DETAIL For 8 Bolt Base Plate

METAL POLE No. 1,2

| PROJECT REFERENCE NO. | SHEET NO. |
|-----------------------|-----------|
| I-4400C | Sig. 10.2 |

MAST ARM LOADING SCHEDULE

| LOADING SYMBOL | DESCRIPTION | AREA | SIZE | WEIGHT |
|---------------------------|--|-----------|-------------------|--------|
| [Signal Head Symbol] | RIGID MOUNTED SIGNAL HEAD 12"-3 SECTION-WITH BACKPLATE | 9.3 S.F. | 25.5" W X 52.5" L | 60 LBS |
| [Sign Symbol] | SIGN RIGID MOUNTED | 7.5 S.F. | 30.0" W X 36.0" L | 14 LBS |
| [Street Name Sign Symbol] | STREET NAME SIGN RIGID MOUNTED | 16.0 S.F. | 24.0" W X 96.0" L | 36 LBS |

NOTES

DESIGN REFERENCE MATERIAL

- Design the traffic signal structure and foundation in accordance with:
 - The 6th Edition 2013 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions.
 - The 2018 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signal project special provisions.
 - The 2018 NCDOT Roadway Standard Drawings.
 - The traffic signal project plans and special provisions.
 - The NCDOT "Metal Pole Standards" located at the following NCDOT website: <https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

DESIGN REQUIREMENTS

- Design the traffic signal structure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signal plans for the actual loads that will be applied at the time of the installation.
- Design all signal supports using stress ratios that do not exceed 0.9.
- The camber design for the mast arm deflection should provide an appearance of a low pitched arch where the tip or the free end of the mast arm does not deflect below horizontal when fully loaded.
- A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design requirements.
- Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts.
- The mast arm attachment height (H1) shown is based on the following design assumptions:
 - Mast arm slope and deflection are not considered in determining the arm attachment height as they are assumed to offset each other.
 - Signal heads are rigidly mounted and vertically centered on the mast arm.
 - The roadway clearance height for design is as shown in the elevation views.
 - The top of the pole base plate is 0.75 feet above the ground elevation.
 - Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground level and the high point of the roadway.
- The pole manufacturer will determine the total height (H2) of each pole using the greater of the following:
 - Mast arm attachment height (H1) plus 2 feet, or
 - H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot.
- If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919) 814-5000.
- The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signal heads over the roadway.
- The contractor is responsible for providing soil penetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed.


All metal poles and arms should be BLACK in color as specified in the project special provisions.

NCDOT Wind Zone 4 (90 mph)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|--|---|--|--|
| | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinskyk PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | SCALE: 0 N/A REVISIONS: _____ INITI. DATE _____ SIGNATURE: _____ DATE: _____ SIG. INVENTORY NO. 14-0901 | |

Design Loading for METAL POLE NO. 3




Elevation View

SPECIAL NOTE


The contractor is responsible for verifying that the mast arm attachment height (H1) will provide the "Design Height" clearance from the roadway before submitting final shop drawings for approval. Verify elevation data below which was obtained by field measurement or from available project survey data.

Elevation Data for Mast Arm Attachment (H1)

| Elevation Differences for: | Pole 3 |
|--|-----------|
| Baseline reference point at ϕ Foundation @ ground level | 0.0 ft. |
| Elevation difference at High point of roadway surface | +2.02 ft. |
| Elevation difference at Edge of travelway or face of curb | +2.02 ft. |




POLE RADIAL ORIENTATION



8 BOLT BASE PLATE DETAIL

See Note 6



BASE PLATE TEMPLATE & ANCHOR BOLT LOCK PLATE DETAIL
For 8 Bolt Base Plate



HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

METAL POLE No. 3

| PROJECT REFERENCE NO. | SHEET NO. |
|-----------------------|-----------|
| I-4400C | Sig. 10.3 |

MAST ARM LOADING SCHEDULE

| LOADING SYMBOL | DESCRIPTION | AREA | SIZE | WEIGHT |
|----------------|---|-----------|-------------------------|--------|
| | RIGID MOUNTED SIGNAL HEAD 12"-3 SECTION-WITH BACKPLATE | 9.3 S.F. | 25.5" W X 52.5" L | 60 LBS |
| | SIGN RIGID MOUNTED | 7.5 S.F. | 30.0" W X 36.0" L | 14 LBS |
| | STREET NAME SIGN RIGID MOUNTED | 16.0 S.F. | 24.0" W X 96.0" L | 36 LBS |

NOTES

DESIGN REFERENCE MATERIAL

- Design the traffic signal structure and foundation in accordance with:
 - The 6th Edition 2013 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions.
 - The 2018 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signal project special provisions.
 - The 2018 NCDOT Roadway Standard Drawings.
 - The traffic signal project plans and special provisions.
 - The NCDOT "Metal Pole Standards" located at the following NCDOT website: <https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

DESIGN REQUIREMENTS

- Design the traffic signal structure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signal plans for the actual loads that will be applied at the time of the installation.
- Design all signal supports using stress ratios that do not exceed 0.9.
- The camber design for the mast arm deflection should provide an appearance of a low pitched arch where the tip or the free end of the mast arm does not deflect below horizontal when fully loaded.
- A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design requirements.
- Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts.
- The mast arm attachment height (H1) shown is based on the following design assumptions:
 - Mast arm slope and deflection are not considered in determining the arm attachment height as they are assumed to offset each other.
 - Signal heads are rigidly mounted and vertically centered on the mast arm.
 - The roadway clearance height for design is as shown in the elevation views.
 - The top of the pole base plate is 0.75 feet above the ground elevation.
 - Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground level and the high point of the roadway.
- The pole manufacturer will determine the total height (H2) of each pole using the greater of the following:
 - Mast arm attachment height (H1) plus 2 feet, or
 - H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot.
- If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919) 814-5000.
- The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signal heads over the roadway.
- The contractor is responsible for providing soil penetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed.



All metal poles and arms should be BLACK in color as specified in the project special provisions.

NCDOT Wind Zone 4 (90 mph)

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

| | | |
|---|--|---|
| Prepared For: TRANSPORTATION MOBILITY AND SAFETY DIVISION DIVISION OF TRANSPORTATION SIGNAL DESIGN SECTION 750 N. Greenfield Pkwy, Garner, NC 27529 | US 25 / US 25 Business (Asheville Highway) at I-26 EB Ramps | SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 03464 N. R. SIMMONS |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinsky PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |

PHASING DIAGRAM



QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|----|-------|-------|
| | 02+5 | 02+6 | 08 | PRE 3 | FLUSH |
| 21,22,23 | G | G | R | R | Y |
| 51 | — | — | — | — | — |
| 61,62 | R | G | R | R | Y |
| 81,82 | R | R | G | G | R |

SIGNAL FACE I.D.

All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART


| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|--------------------------|----------------------|-------------------------|-------------|----------|---|---|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY TIME | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | SYSTEM LOOP | NEW CARD | | |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 5A | 6X40 | 0 | * | Y | 5 | Y | Y | - | - | 3 | - | - | - | - | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 8A | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 8B | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | 5 | - | - | - | - | - | - | * |
| 8C | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | 15 | - | - | - | - | - | - | * |
| **01 | 6X6 | 625 | * | Y | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | - | * |

* Multizone Microwave Detection
** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 5 may be lagged.
- Set all detector units to presence mode.
- Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
- When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | |
|-------------------------|------------|-----|------------|-----|
| | 2 | 5 | 6 | 8 |
| Min Green 1 * | 12 | 7 | 12 | 7 |
| Extension 1 * | 6.0 | 2.0 | 6.0 | 2.0 |
| Max Green 1 * | 90 | 35 | 90 | 30 |
| Yellow Clearance | 4.6 | 3.0 | 4.3 | 3.7 |
| Red Clearance | 1.3 | 3.3 | 1.6 | 2.3 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | 1.5 | - | 1.5 | - |
| Max Variable Initial * | 34 | - | 34 | - |
| Time Before Reduction * | 15 | - | 15 | - |
| Time To Reduce * | 30 | - | 30 | - |
| Minimum Gap | 3.0 | - | 3.0 | - |
| Recall Mode | MIN RECALL | - | MIN RECALL | - |
| Vehicle Call Memory | YELLOW | - | YELLOW | - |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

PROPOSED SIGNS

| PROPOSED | EXISTING |
|--|----------|
| (A) No Left Turn Sign (R3-2) | (A) |
| (B) No Right Turn Sign (R3-1) | (B) |
| (C) "YIELD" Sign (R1-2) | (C) |
| (D) Combined Through and Left Arrow Sign (R3-6L) | (D) |
| (E) Right Arrow "ONLY" Sign (R3-5R) | (E) |

LEGEND

| PROPOSED | EXISTING |
|--|--|
| ○ Traffic Signal Head | ● Traffic Signal Head |
| ○ Modified Signal Head | ○ Modified Signal Head |
| ○ Pedestrian Signal Head With Push Button & Sign | ○ Pedestrian Signal Head With Push Button & Sign |
| ○ Signal Pole with Guy | ○ Signal Pole with Guy |
| ○ Signal Pole with Sidewalk Guy | ○ Signal Pole with Sidewalk Guy |
| ⊠ Inductive Loop Detector | ⊠ Inductive Loop Detector |
| ⊠ Controller & Cabinet | ⊠ Controller & Cabinet |
| ⊠ Junction Box | ⊠ Junction Box |
| — 2-in Underground Conduit | — 2-in Underground Conduit |
| — Right of Way | — Right of Way |
| → Directional Arrow | → Directional Arrow |
| Construction Zone | N/A |
| Microwave Detection Zone | ○ Microwave Detection Zone |

Signal Upgrade
Temporary Design 1
Construction Phases 3,3A

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


| | | | |
|--|--|---|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031664 NATASHA R. SIMMONS | |

HNTB
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|----|----------|-------|----|----|-------|----|-------|-------|-----|-------|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | NU | 21,22,23 | NU | NU | NU | NU | 51 | 61,62 | NU | NU | 81,82 | NU |
| RED | | 128 | | | | | | 134 | | | 107 | |
| YELLOW | | 129 | | | | | | 135 | | | 108 | |
| GREEN | | 130 | | | | | | 136 | | | 109 | |
| RED ARROW | | | | | | | | 131 | | | | |
| YELLOW ARROW | | | | | | | | 132 | | | | |
| GREEN ARROW | | | | | | | | 133 | | | | |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S2,S7,S8,S11
 PHASES USED.....2,5,6,8
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | 18U | 42 | 4 | * 8 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 **Multizone Microwave Detector Zone. See Special Detector Note.



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR
 THE SIGNAL DESIGN: 14-0902T1
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 1
 Construction Phases 3,3A

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

| | | | |
|-----------------------------|--|---------------------------|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | Prepared for: | |
| Prepared by: A.H. Thornburg | Reviewed by: A.D. Klinksiek | Prepared by: N.R. Simmons | Reviewed by: N.R. Simmons |
| REVISIONS | INIT. | DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 SIGNATURE DATE |

HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

750 N. Greenfield Pkwy, Corner, NC 27529


SIG. INVENTORY NO. 14-0902T1

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL
WHEN LEAVING PREEMPTOR SEQUENCE

(program controller as shown below)

1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.



VEHICLE DETECTOR #8 SETTINGS
FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS). PRESS '+' UNTIL DETECTOR #8 IS REACHED.

| | |
|--|-------------------------|
| VEHICLE DETECTOR #8 SETTINGS (+,-,1-64) | |
| SETTING: | (Y/N) |
| ENABLE DETECTOR..... | Y |
| ENABLE LOGGING..... | N |
| ENABLE DIAGNOSTICS..... | N |
| SPEED TRAP..... | N |
| CALL DETECTOR..... | N |
| EXTENSION DETECTOR..... | N |
| MODE 2 STOP BAR..... | N |
| SWITCHING DETECTOR..... | N |
| DUPLICATING DETECTOR..... | N |
| ENABLE FULL TIME DELAY..... | N |
| IF FAILED, SET MIN RECALL?..... | N |
| IF FAILED, SET MAX1 RECALL?..... | N |
| IF FAILED, SET MAX2 RECALL?..... | N |
| PHASE# | 12345678910111213141516 |
| PHASES ASSIGNED : | |
| SWITCH/DUPLICATE: | |
| LOOP SIZE (0-255 FT)..... | 6 |
| SPEED TRAP DISTANCE (0-255 FT)..... | 0 |
| STOP BAR TIME (0-255 SEC)..... | 0 |
| STRETCH (0-25.5 SEC)..... | 0.0 |
| DELAY (0-255 SEC)..... | 0 |
| MAX CALLS/MIN (0-255)..... | 255 |
| MIN CALLS/DIAGNOSTIC PERIOD (0-255)..... | 0 |
| MAX OCCUPANCY (0-100%)..... | 100 |
| EXTENSION DISABLE TIME (0-255 SEC)..... | 0 |
| QUEUE MAX OCCUPANCY TIME (0-255)..... | 5 |
| QUEUE GAP RESET TIME (0-25.5)..... | 0.1 |
| PREEMPTION INDEX FOR QUEUE (0-10)..... | 3 |

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

| | |
|---|-------------------------|
| PREEMPTION #3 SETTINGS (NEXT:1-10) | |
| INTERVAL/TIMING | CLEAR/DWELL PHASES |
| GRN YEL RED | 12345678910111213141516 |
| 1 255 0.0 0.0 | X |
| 2 0 0.0 0.0 | |
| 3 0 0.0 0.0 | |
| 4 0 0.0 0.0 | |
| 5 1 0.0 0.0 | X X |
| EXIT CALLS | |
| OPTIONS | |
| PRIORITY (Y/N TO SELECT) | MED |
| DELAY TIMER (0-255 SEC) | 0.0 |
| MIN GREEN BEFORE PRE (0= DEFAULT)..... | 12 |
| PED CLEAR BEFORE PRE (0= DEFAULT)..... | 0 |
| YELLOW CLEAR BEFORE PRE (0= DEFAULT)..... | 4.6 |
| RED CLEAR BEFORE PRE (0= DEFAULT)..... | 1.6 |
| DWELL MIN TIMER (0-255 SEC) | 30 |
| DWELL MAX TIMER (0=OFF,1-255MIN) | 0 |
| DWELL HOLD-OVER TIMER (0-255) | 0 |
| LATCH CALL? | N |
| LINK TO NEXT PREEMPT? | N |
| ENABLE BACKUP PROTECTION? | N |
| HOLD CLEAR 1 PHASES DURING DELAY? .. | N |
| FAST GREEN FLASH DWELL PHASES? | N |
| PED CLEARANCE THROUGH YELLOW? | N |
| INHIBIT OVERLAP GREEN EXTENSION? .. | N |
| SERVICE DURING SOFTWARE FLASH? | N |
| REST IN RED DURING DWELL INTERVAL? .. | N |
| FLASH DWELL INTERVAL? | N |
| ALLOW PEDS IN DWELL INTERVAL? | N |
| RE-TIME DWELL INTERVAL? | N |
| OVERLAPS: | ABCDEFGHIJKLMNPO |
| DWELL INT FLASH YELLOW | |
| OMIT OVERLAPS: | |

THIS ELECTRICAL DETAIL IS FOR
 THE SIGNAL DESIGN: 14-0902T1
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A


Electrical Detail - Sheet 2 of 2
 Signal Upgrade
 Temporary Design 1
 Construction Phases 3,3A

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

| | | | | | |
|--|--|--|--|------|--|
| | Prepared for: | | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | | PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | | |
| REVISIONS | | | INIT. | DATE | DocuSigned by: Natasha R. Simmons 4/26/2019 |
| 750 N. Greenfield Pkwy, Corner, NC 27529 | | | SIG. INVENTORY NO. 14-0902T1 | | |

HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND

- ←● DETECTED MOVEMENT
- ← UNDETECTED MOVEMENT (OVERLAP)
- ← UNSIGNALIZED MOVEMENT
- ← PEDESTRIAN MOVEMENT

QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|-----|------|-------|
| | 02+5 | 02+6 | 08 | PRE3 | FLUSH |
| 21,22 | G | G | R | R | Y |
| 51 | --- | --- | --- | --- | --- |
| 61,62 | R | G | R | R | Y |
| 81,82 | R | R | G | G | R |
| 83,84 | R | R | / | / | R |

SIGNAL FACE I.D.

All Heads L.E.D.




OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | DETECTOR PROGRAMMING | | | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------------------|-------|---------|-----------|-----------------|--------------|------------|--------------------------|----------------------|-------------------------|-------------|----------|---|---|
| | | | | NEW LOOP | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY TIME | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | LOOP SYSTEM | NEW CARD | | |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 5A | 6X40 | 0 | * | Y | 5 | Y | Y | - | - | 3 | - | - | - | - | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 8A | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 8B | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| 8C | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | - | - | - | - | - | - | - | * |
| **Q1 | 6X6 | 725 | * | Y | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | - | * |

* Multizone Microwave Detection
** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 5 may be lagged.
- Set all detector units to presence mode.
- Reposition existing signal heads numbered 81 and 82 and sign (D).
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
- When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | |
|-------------------------|------------|-----|------------|-----|
| | 2 | 5 | 6 | 8 |
| Min Green 1 * | 12 | 7 | 12 | 7 |
| Extension 1 * | 6.0 | 2.0 | 6.0 | 2.0 |
| Max Green 1 * | 90 | 35 | 90 | 30 |
| Yellow Clearance | 4.6 | 3.0 | 4.3 | 4.3 |
| Red Clearance | 2.6 | 3.3 | 1.4 | 1.6 |
| Red Revert | 2.0 | 2.0 | 1.0 | 1.6 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | 1.5 | - | 1.5 | - |
| Max Variable Initial * | 34 | - | 34 | - |
| Time Before Reduction * | 15 | - | 15 | - |
| Time To Reduce * | 30 | - | 30 | - |
| Minimum Gap | 3.0 | - | 3.0 | - |
| Recall Mode | MIN RECALL | - | MIN RECALL | - |
| Vehicle Call Memory | YELLOW | - | YELLOW | - |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

* Time defaults to time used for phase during normal operation
HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997


PROPOSED LEGEND EXISTING

| | | |
|---|--|----------------------------------|
| ○→ Traffic Signal Head | ●→ Modified Signal Head | ●→ N/A |
| ○→ Pedestrian Signal Head With Push Button & Sign | ○→ Signal Pole with Guy | ○→ Signal Pole with Sidewalk Guy |
| □→ Inductive Loop Detector | □→ Controller & Cabinet | □→ Junction Box |
| --- 2-in Underground Conduit | → Directional Arrow | → N/A |
| █ Construction Zone | ○ Microwave Detection Zone | ○ No Left Turn Sign (R3-2) |
| ○ No Left Turn Sign (R3-2) | ○ No Right Turn Sign (R3-1) | ○ "YIELD" Sign (R1-2) |
| ○ "YIELD" Sign (R1-2) | ○ Combined Through and Left Arrow Sign (R3-6L) | ○ |

Signal Upgrade
Temporary Design 2
Construction Phase 3B

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


| | | | |
|--|--|-------------------------|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | REVISIONS INIT. DATE | |



* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|----|-------|-------|----|----|-------|----|-------|-------|-----|-------|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | NU | 21,22 | NU | NU | NU | NU | 51 | 61,62 | NU | NU | 81,82 | 83,84 |
| RED | | 128 | | | | | | 134 | | | 107 | 107 |
| YELLOW | | 129 | | | | | | 135 | | | 108 | |
| GREEN | | 130 | | | | | | 136 | | | 109 | |
| RED ARROW | | | | | | | | 131 | | | | |
| YELLOW ARROW | | | | | | | | 132 | | | | 108 |
| GREEN ARROW | | | | | | | | 133 | | | | 109 |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S2,S7,S8,S11
 PHASES USED.....2,5,6,8
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT

(front view)



EX.: 1A, 2A, ETC. = LOOP NO.'S


FS = FLASH SENSE
 ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | 18U | 42 | 4 | * 8 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 **Multizone Microwave Detector Zone. See Special Detector Note.

INPUT FILE POSITION LEGEND: J2L



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR
 THE SIGNAL DESIGN: 14-0902T2
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 2
 Construction Phase 3B

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

ELECTRICAL AND PROGRAMMING DETAILS FOR:

US 25 (Asheville Highway)
 at
 I-26 WB Ramps

Division 14 Henderson Co. Hendersonville

PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek
 PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

| REVISIONS | INIT. | DATE |
|-----------|-------|------|
| | | |

SEAL

DocuSigned by:
 Natasha R. Simmons 4/26/2019

SIGNATURE DATE

SIG. INVENTORY NO. 14-0902T2

HNTB


HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL WHEN LEAVING PREEMPTOR SEQUENCE

(program controller as shown below)

- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.



VEHICLE DETECTOR #8 SETTINGS FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS). PRESS '+' UNTIL DETECTOR #8 IS REACHED.

| VEHICLE DETECTOR #8 SETTINGS (+/-1-64) | |
|--|--------------------------|
| SETTING: | (Y/N) |
| ENABLE DETECTOR..... | Y |
| ENABLE LOGGING..... | N |
| ENABLE DIAGNOSTICS..... | N |
| SPEED TRAP..... | N |
| CALL DETECTOR..... | N |
| EXTENSION DETECTOR..... | N |
| MODE 2 STOP BAR..... | N |
| SWITCHING DETECTOR..... | N |
| DUPLICATING DETECTOR..... | N |
| ENABLE FULL TIME DELAY..... | N |
| IF FAILED, SET MIN RECALL?..... | N |
| IF FAILED, SET MAX1 RECALL?..... | N |
| IF FAILED, SET MAX2 RECALL?..... | N |
| PHASE# | :12345678910111213141516 |
| PHASES ASSIGNED : | |
| SWITCH/DUPLICATE: | |
| LOOP SIZE (0-255 FT)..... | 6 |
| SPEED TRAP DISTANCE (0-255 FT)..... | 0 |
| STOP BAR TIME (0-255 SEC)..... | 0 |
| STRETCH (0-25.5 SEC)..... | 0.0 |
| DELAY (0-255 SEC)..... | 0 |
| MAX CALLS/MIN (0-255)..... | 255 |
| MIN CALLS/DIAGNOSTIC PERIOD (0-255)..... | 0 |
| MAX OCCUPANCY (0-100%)..... | 100 |
| EXTENSION DISABLE TIME (0-255 SEC)..... | 0 |
| QUEUE MAX OCCUPANCY TIME (0-255)..... | 0.5 |
| QUEUE GAP RESET TIME (0-25.5)..... | 0.1 |
| PREEMPTION INDEX FOR QUEUE (0-10)..... | 3 |

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

| PREEMPTION #3 SETTINGS (NEXT:1-10) | |
|---|-------------------------|
| INTERVAL/TIMING | CLEAR/DWELL PHASES |
| GRN YEL RED | 12345678910111213141516 |
| 1 255 0.0 0.0 | X |
| 2 0 0.0 0.0 | |
| 3 0 0.0 0.0 | |
| 4 0 0.0 0.0 | |
| 5 1 0.0 0.0 | X X |
| EXIT CALLS | |
| OPTIONS | |
| PRIORITY (Y/N TO SELECT) | MED |
| DELAY TIMER (0-255 SEC) | 0.0 |
| MIN GREEN BEFORE PRE (0= DEFAULT)..... | 12 |
| PED CLEAR BEFORE PRE (0= DEFAULT)..... | 0 |
| YELLOW CLEAR BEFORE PRE (0= DEFAULT)..... | 4.6 |
| RED CLEAR BEFORE PRE (0= DEFAULT)..... | 2.6 |
| DWELL MIN TIMER (0-255 SEC) | 30 |
| DWELL MAX TIMER (0=OFF,1-255MIN) | 0 |
| DWELL HOLD-OVER TIMER (0-255) | 0 |
| LATCH CALL? | N |
| LINK TO NEXT PREEMPT? | N |
| ENABLE BACKUP PROTECTION? | N |
| HOLD CLEAR 1 PHASES DURING DELAY? | N |
| FAST GREEN FLASH DWELL PHASES? | N |
| PED CLEARANCE THROUGH YELLOW? | N |
| INHIBIT OVERLAP GREEN EXTENSION? | N |
| SERVICE DURING SOFTWARE FLASH? | N |
| REST IN RED DURING DWELL INTERVAL? | N |
| FLASH DWELL INTERVAL? | N |
| ALLOW PEDS IN DWELL INTERVAL? | N |
| RE-TIME DWELL INTERVAL? | N |
| OVERLAPS: | ABCDEFGHIJKLMNPO |
| DWELL INT FLASH YELLOW | |
| OMIT OVERLAPS: | |


THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0902T2
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A

Electrical Detail - Sheet 2 of 2
Signal Upgrade
Temporary Design 2
Construction Phase 3B

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

| | | | |
|--|--|--|------|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Prepared for: | Division 14 Henderson Co. Hendersonville | |
| PLAN DATE: September 2018 | | REVIEWED BY: A.D. Klinksiek | |
| PREPARED BY: A.H. Thornburg | | REVIEWED BY: N.R. Simmons | |
| REVISIONS | | INIT. | DATE |
| DocuSigned by: Natasha R. Simmons 4/26/2019 | | DATE | |
| SIG. INVENTORY NO. 14-0902T2 | | | |

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND

- ←● DETECTED MOVEMENT
- ← UNDETECTED MOVEMENT (OVERLAP)
- ←..... UNSIGNALIZED MOVEMENT
- ←- - - PEDESTRIAN MOVEMENT

QUEUE PREEMPT PHASES
(Medium Priority)





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | |
|-------------|-------|------|----|------|-------|
| | 02+5 | 02+6 | 08 | PRE3 | FLUSH |
| 21,22 | G | G | R | R | Y |
| 51 | - | - | - | - | - |
| 61,62 | R | G | R | R | Y |
| 81,82 | R | R | G | G | R |
| 83,84 | R | R | / | / | R |

SIGNAL FACE I.D.

All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | | | | | | | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|---------------------|----------------------|-------------------------|-------------|----------|---|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | DELAY TIME | QUEUE MAX OCCUPANCY | QUEUE GAP RESET TIME | PREEMPT INDEX FOR QUEUE | SYSTEM LOOP | NEW CARD | |
| 2A | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | Y | Y | - | - | - | - | - | - | - | - | * |
| 5A | 6X40 | 0 | * | Y | 5 | Y | Y | - | - | 3 | - | - | - | - | - | * |
| 6A | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |
| 6B | 6X6 | 300 | * | Y | 6 | Y | Y | - | - | - | - | - | - | - | - | * |
| 8A | 6X40 | 0 | * | - | 8 | Y | Y | - | - | - | - | - | - | - | - | * |
| 8B | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | - | - | - | - | - | - | * |
| 8C | 6X40 | 0 | * | Y | 8 | Y | Y | - | - | - | - | - | - | - | - | * |
| **01 | 6X6 | 725 | * | - | PRE3 | - | - | - | - | - | 5 | 0.1 | 3 | - | - | * |

* Multizone Microwave Detection
** See Note 8

3 Phase Fully Actuated w/ Queue Preemption Asheville Signal System NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 5 may be lagged.
- Set all detector units to presence mode.
- Reposition existing signal heads numbered 21,22,51,61,62, and signs A and B.
- Incorporate Microwave Detection system for vehicle detection.
- Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
- This loop serves as a queue backup detector. After 5 seconds of constant actuation, the detector unit places a call to the controller to preempt normal operation to clear out the storage lanes.
- When leaving preemption, all phases with a call must be serviced before preemptor can be serviced again.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.

LEGEND

| PROPOSED | EXISTING |
|--|--|
| ○→ Traffic Signal Head | ○→ Traffic Signal Head |
| ●→ Modified Signal Head | ●→ Modified Signal Head |
| ⊥ Sign | ⊥ Sign |
| ⊥ Pedestrian Signal Head With Push Button & Sign | ⊥ Pedestrian Signal Head With Push Button & Sign |
| ○ Signal Pole with Guy | ○ Signal Pole with Guy |
| ○ Signal Pole with Sidewalk Guy | ○ Signal Pole with Sidewalk Guy |
| ⊠ Inductive Loop Detector | ⊠ Inductive Loop Detector |
| ⊠ Controller & Cabinet | ⊠ Controller & Cabinet |
| ⊠ Junction Box | ⊠ Junction Box |
| 2-in Underground Conduit | 2-in Underground Conduit |
| Right of Way | Right of Way |
| → Directional Arrow | → Directional Arrow |
| Construction Zone | Construction Zone |
| Microwave Detection Zone | Microwave Detection Zone |
| A No Left Turn Sign (R3-2) | A No Left Turn Sign (R3-2) |
| B No Right Turn Sign (R3-1) | B No Right Turn Sign (R3-1) |
| C "YIELD" Sign (R1-2) | C "YIELD" Sign (R1-2) |
| D Combined Through and Left Arrow Sign (R3-6L) | D Combined Through and Left Arrow Sign (R3-6L) |

OASIS 2070 TIMING CHART


| FEATURE | PHASE | | | |
|-------------------------|------------|-----|------------|-----|
| | 2 | 5 | 6 | 8 |
| Min Green 1 * | 12 | 7 | 12 | 7 |
| Extension 1 * | 6.0 | 2.0 | 6.0 | 2.0 |
| Max Green 1 * | 90 | 35 | 90 | 30 |
| Yellow Clearance | 4.6 | 3.0 | 4.3 | 4.3 |
| Red Clearance | 3.2 | 3.5 | 1.5 | 1.9 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | 1.5 | - | 1.5 | - |
| Max Variable Initial * | 34 | - | 34 | - |
| Time Before Reduction * | 15 | - | 15 | - |
| Time To Reduce * | 30 | - | 30 | - |
| Minimum Gap | 3.0 | - | 3.0 | - |
| Recall Mode | MIN RECALL | - | MIN RECALL | - |
| Vehicle Call Memory | YELLOW | - | YELLOW | - |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

2070 QUEUE PREEMPTION

| FUNCTION | PRE 3 |
|---------------------------|--------|
| Interval 1 - Dwell Green | 255 |
| Interval 1 - Dwell Yellow | 0.0* |
| Interval 1 - Dwell Red | 0.0* |
| Interval 5 - Exit Green | 1 |
| Interval 5 - Yellow | 0.0 |
| Interval 5 - Red | 0.0 |
| Exist Phase(s) | 2+6 |
| Priority | Medium |
| Delay Time | 0 |
| Min Green Before Pre | 12 |
| Ped Clear Before Pre | 0 |
| Yellow Clear Before Pre | 0.0* |
| Red Clear Before Pre | 0.0* |
| Dwell Min Time | 30 |
| Enable Backup Protection | N |
| Ped Clear Through Yellow | N |
| Omit Overlaps | - |

* Time defaults to time used for phase during normal operation
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997




Signal Upgrade
Temporary Design 3
Construction Phase 3C

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|---|---|---|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinskyk PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031664 NATASHA R. SIMMONS | |
| REVISIONS: _____ INITI: _____ DATE: _____ DocuSigned by: | | | |
| SIG. INVENTORY NO. 14-090273 | | | |

EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 |
|-----------------|----|-------|-------|----|----|-------|----|-------|-------|-----|-------|-------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | NU | 21,22 | NU | NU | NU | NU | 51 | 61,62 | NU | NU | 81,82 | 83,84 |
| RED | | 128 | | | | | | 134 | | | 107 | 107 |
| YELLOW | | 129 | | | | | | 135 | | | 108 | |
| GREEN | | 130 | | | | | | 136 | | | 109 | |
| RED ARROW | | | | | | | | 131 | | | | |
| YELLOW ARROW | | | | | | | | 132 | | | | 108 |
| GREEN ARROW | | | | | | | | 133 | | | | 109 |


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S2,S7,S8,S11
 PHASES USED.....2,5,6,8
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 01 | ** | 18U | 42 | 4 | * 8 | PRE3 | | | | | |

* See vehicle detector programming detail on Sheet 2.
 **Multizone Microwave Detector Zone. See Special Detector Note.



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 01, detector card placement and associated inputs reserved for compatibility with the queue preemption detector setting instructions located on sheet 2 of this electrical detail.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0902T3
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 1 of 2
 Signal Upgrade
 Temporary Design 3
 Construction Phase 3C

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


| | | | |
|---|--|---------------------------|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | Prepared for: | |
| Prepared by: A.H. Thornburg | REVIEWED BY: A.D. Klinksiek | REVIEWED BY: N.R. Simmons | DocuSigned by: Natasha R. Simmons 4/26/2019 |
| REVISIONS | INIT. | DATE | DATE |
| HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | | | SIG. INVENTORY NO. 14-0902T3 |

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL WHEN LEAVING PREEMPTOR SEQUENCE

(program controller as shown below)

- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1,2,3, AND 4.
- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

NOTE: WHEN LEAVING PREEMPTOR SEQUENCE, THE FOLLOWING LOGIC STATEMENTS ENSURE ALL PHASES WITH A CALL WILL BE SERVED BEFORE PREEMPTOR CAN BE SERVICED AGAIN.



VEHICLE DETECTOR #8 SETTINGS FOR QUEUE PREEMPT

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS), THEN '1' (VEHICLE DETECTOR ASSIGNMENTS). PRESS '+' UNTIL DETECTOR #8 IS REACHED.

```

VEHICLE DETECTOR #8 SETTINGS (+,-,1-64)
SETTING: (Y/N)
ENABLE DETECTOR.....Y
ENABLE LOGGING.....N
ENABLE DIAGNOSTICS.....N
SPEED TRAP.....N
CALL DETECTOR.....N
EXTENSION DETECTOR.....N
MODE 2 STOP BAR.....N
SWITCHING DETECTOR.....N
DUPLICATING DETECTOR.....N
ENABLE FULL TIME DELAY.....N
IF FAILED, SET MIN RECALL?.....N
IF FAILED, SET MAX1 RECALL?.....N
IF FAILED, SET MAX2 RECALL?.....N
PHASE# :12345678910111213141516
PHASES ASSIGNED :
SWITCH/DUPLICATE:
LOOP SIZE (0-255 FT).....6
SPEED TRAP DISTANCE (0-255 FT).....0
STOP BAR TIME (0-255 SEC).....0
STRETCH (0-25.5 SEC).....0.0
DELAY (0-255 SEC).....0
MAX CALLS/MIN (0-255).....255
MIN CALLS/DIAGNOSTIC PERIOD (0-255).....0
MAX OCCUPANCY (0-100%).....100
EXTENSION DISABLE TIME (0-255 SEC).....0
QUEUE MAX OCCUPANCY TIME (0-255).....5
QUEUE GAP RESET TIME (0-25.5).....0.1
PREEMPTION INDEX FOR QUEUE (0-10).....3
  
```

QUEUE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' until Preemption #3 is reached.

| PREEMPTION #3 | INTERVAL/TIMING | SETTINGS (NEXT:1-10) | CLEAR/DWELL PHASES |
|---------------|-----------------|----------------------|-------------------------|
| 1 | 255 0.0 0.0 | | 12345678910111213141516 |
| 2 | 0 0.0 0.0 | | X |
| 3 | 0 0.0 0.0 | | |
| 4 | 0 0.0 0.0 | | |
| 5 | 1 0.0 0.0 | | X X |

EXIT CALLS

| OPTIONS | VALUES |
|--------------------------------------|--------|
| PRIORITY (Y/N TO SELECT) | MED |
| DELAY TIMER (0-255 SEC) | 0.0 |
| MIN GREEN BEFORE PRE (0= DEFAULT) | 12 |
| PED CLEAR BEFORE PRE (0= DEFAULT) | 0 |
| YELLOW CLEAR BEFORE PRE (0= DEFAULT) | 4.6 |
| RED CLEAR BEFORE PRE (0= DEFAULT) | 3.2 |
| DWELL MIN TIMER (0-255 SEC) | 30 |
| DWELL MAX TIMER (0=OFF,1-255MIN) | 0 |
| DWELL HOLD-OVER TIMER (0-255) | 0 |
| LATCH CALL? | N |
| LINK TO NEXT PREEMPT? | N |
| ENABLE BACKUP PROTECTION? | N |
| HOLD CLEAR 1 PHASES DURING DELAY? | N |
| FAST GREEN FLASH DWELL PHASES? | N |
| PED CLEARANCE THROUGH YELLOW? | N |
| INHIBIT OVERLAP GREEN EXTENSION? | N |
| SERVICE DURING SOFTWARE FLASH? | N |
| REST IN RED DURING DWELL INTERVAL? | N |
| FLASH DWELL INTERVAL? | N |
| ALLOW PEDS IN DWELL INTERVAL? | N |
| RE-TIME DWELL INTERVAL? | N |

OVERLAPS: ABCDEFGHIJKLMNPO
 OMIT OVERLAPS:

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0902T3
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A

Electrical Detail - Sheet 2 of 2
 Signal Upgrade
 Temporary Design 3
 Construction Phase 3C

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

| | | | |
|--|---|--|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | Prepared for: | |
| Prepared for: | PLAN DATE: September 2018 PREPARED BY: A.H. Thornburg | REVIEWED BY: A.D. Klinksiek REVIEWED BY: N.R. Simmons | DocuSigned by: Natasha R. Simmons 4/26/2019 |
| 750 N. Greenfield Pkwy, Corner, NC 27529 | HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | REVISIONS INIT. DATE | SIG. INVENTORY NO. 14-0902T3 |





TABLE OF OPERATION


| SIGNAL FACE | PHASE | | | |
|-------------|-------|------|------|-------|
| | 02+6 | 04+7 | 04+8 | FLASH |
| 21,22 | / | R | R | R |
| 41,42 | R | ↑ | ↑ | R |
| 61,62 | ↑ | R | R | R |
| 81,82,83 | R | R | R | R |




OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | STRETCH TIME | DELAY TIME | SYSTEM LOOP | NEW CARD |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|------------|-------------|----------|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | | | | |
| 2A | 6X6 | 300 | * | Y | 2 | - | Y | - | 2.4 | - | - | * |
| 2B | 6X6 | 300 | * | Y | 2 | - | Y | - | 2.4 | - | - | * |
| 2C | 6X40 | 0 | * | Y | 2 | Y | Y | - | - | - | - | * |
| 2D | 6X40 | 0 | * | Y | 2 | Y | Y | - | - | - | - | * |
| 4A | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | - | - | * |
| 6A | 6X40 | 0 | * | Y | 6 | Y | Y | - | - | - | - | * |
| 8A | 6X40 | 0 | * | Y | 7/8 | Y | Y | - | - | - | - | * |

* Multizone Microwave Detection




- ### 3 Phase Fully Actuated Asheville Signal System
- #### NOTES
- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
 - Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
 - Omit phase 8 during phase 2+6 on.
 - Program controller to clear from phase 2+6 to phase 8 by progressing through phase 7.
 - Omit phase 7 during phase 8 on.
 - Phase 7 provides red clearance time for vehicles traveling Southbound on US 25 (Asheville Hwy)
 - Set all detector units to presence mode.
 - Program all phases for "Red Rest".
 - Incorporate Microwave Detection system for vehicle detection.
 - Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
 - Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | | |
|-------------------------|-------|-----|-----|-----------|-----|
| | 2 | 4 | 6 | 7 (DUMMY) | 8 |
| Min Green 1 * | 10 | 10 | 10 | 1 | 10 |
| Extension 1 * | 2.0 | 2.0 | 2.0 | 0.0 | 2.0 |
| Max Green 1 * | 60 | 60 | 60 | 1 | 60 |
| Yellow Clearance | 4.3 | 3.0 | 3.0 | 3.0 | 3.0 |
| Red Clearance | 2.2 | 4.8 | 2.5 | 8.5 | 3.4 |
| Red Revert | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Walk 1 * | - | - | - | - | - |
| Don't Walk 1 | - | - | - | - | - |
| Seconds Per Actuation * | - | - | - | - | - |
| Max Variable Initial * | - | - | - | - | - |
| Time Before Reduction * | - | - | - | - | - |
| Time To Reduce * | - | - | - | - | - |
| Minimum Gap | - | - | - | - | - |
| Recall Mode | - | - | - | - | - |
| Vehicle Call Memory | - | - | - | - | - |
| Dual Entry | ON | ON | ON | ON | ON |
| Simultaneous Gap | ON | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.




Signal Upgrade
Temporary Design 4
Construction Phase 5

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|--|--|---|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | REVISIONS INIT. DATE _____ _____ | |


HNTB
 HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997



DocuSigned by:
 Natasha R. Simmons 12/6/2019
 SIGNATURE DATE
 SIG. INVENTORY NO. 14-090274

EDI MODEL 2018ECLIP-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Restore controller to factory defaults before programming per this electrical detail.
3. Program phases 2, 4, 6, 7, and 8 for Dual Entry.
4. Enable Simultaneous Gap-Out for all Phases.
5. Program phases 2 and 6 for Startup In Green.
6. Program phases 2, 4, 6, 7, and 8 for Red Rest.
7. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 |
|-----------------|----|-------|-------|----|-------|-------|----|-------|-------|-----|----------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 |
| SIGNAL HEAD NO. | NU | 21,22 | NU | NU | 41,42 | NU | NU | 61,62 | NU | NC | 81,82,83 |
| RED | | 128 | | | 101 | | | 134 | | | |
| YELLOW | | | | | 102 | | | 135 | | | |
| GREEN | | | | | | | | | | | |
| RED ARROW | | | | | | | | | | | 107 |
| YELLOW ARROW | | 129 | | | | | | | | | 108 |
| GREEN ARROW | | 130 | | | 103 | | | 136 | | | 109 |

NU = Not Used
NC = Not Connected

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S2,S5,S8,S11
 PHASES USED.....2,4,6,*7,8
 OVERLAPS.....NONE
 * PHASE USED FOR TIMING PURPOSES ONLY

DYNAMIC OMIT CONTROL PROGRAMMING

(program controller as shown below)

1. From Main Menu press '2' (Phase Control), then '1' (Phase Control Functions). Scroll to the bottom of the menu and enable Dynamic/Backup Control Functions 1 and 2.
2. From Phase Control Functions Menu press '2' (Dynamic/Backup Control Functions).

```

DYNAMIC/BACKUP CONTROL FUNCTION #01
OVERLAPS:;ABCDEFHIJKLMNPO
IF OVERLAPS ARE ACTIVE ;
OR PHASES:;12345678910111213141516
IF PHASES ARE ON; X X
OMIT PHASES ; X
CALL PHASES ; X
    
```

PRESS 'NEXT'

```

DYNAMIC/BACKUP CONTROL FUNCTION #02
OVERLAPS:;ABCDEFHIJKLMNPO
IF OVERLAPS ARE ACTIVE ;
OR PHASES:;12345678910111213141516
IF PHASES ARE ON; X
OMIT PHASES ; X
CALL PHASES ;
    
```


DYNAMIC OMIT PROGRAMMING COMPLETE

NOTE: THIS PROGRAMMING ENSURES THAT PHASE 7 WILL BE SERVED PRIOR TO PHASE 8 WHEN CONTROLLER IS ADVANCING FROM 2+6.

PHASE 7 IS USED TO PROVIDE EXTENDED RED CLEARANCE BEFORE SERVING PHASE 8.

INPUT FILE POSITION LAYOUT

(front view)



SPECIAL DETECTOR NOTE

Install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

PHASE SEQUENCE PROGRAMMING DETAIL

(program controller as shown below)

FROM OASIS LOCAL CONTROLLER MAIN MENU
SELECT: 4 PHASE SEQUENCE

| PHASE SEQUENCE: PAGE 1 | NEXT: PAGES) | |
|------------------------|--------------|----------------------------|
| RNG:LEAD | BARRIER 1 | X-LAG:LEAD BARRIER 2 X-LAG |
| 1 0 | 2 0 | 0 4 0 0 |
| 2 0 | 6 0 | 0 7 0 0 |
| 3 0 | 0 0 | 0 0 0 0 |
| 4 0 | 0 0 | 0 0 0 0 |

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0902T4
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A



Electrical Detail
Signal Upgrade
Temporary Design 4
Construction Phase 5

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|---|---|--|--|
| | US 25 (Asheville Highway) at I-26 WB Off Ramp | | |
| | Prepared for: | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinskiak PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | | Revisions table with columns: REVISIONS, INITI, DATE. Includes signature of Natasha R. Simmons dated 4/26/2019. | |

EDI MODEL 2018ECLIP-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.
- Integrate monitor with Ethernet network in cabinet.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Program phases 2, 4, 6, 7, and 8 for Dual Entry.
- Enable Simultaneous Gap-Out for all Phases.
- Program phases 2 and 6 for Startup In Green.
- Program phases 2, 4, 6, 7, and 8 for Red Rest.
- The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 | AUX S1 | AUX S2 | AUX S3 | AUX S4 | AUX S5 | AUX S6 |
|-----------------|----|-------------|-------|----|-------|-------|----|----|-------|-------|-----|-------|-------------|--------|--------|--------|--------|--------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 | 9 | 10 | 17 | 11 | 12 | 18 |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED | OLA | OLB | SPARE | OLC | OLD | SPARE |
| SIGNAL HEAD NO. | NU | 21,22,23,24 | NU | NU | 41,42 | 43,44 | NU | NU | 61,62 | 63,64 | NU | NC | 81,82,83,84 | NU | NU | NU | NU | NU |
| RED | | 128 | | | 101 | | | | 134 | | | | | | | | | |
| YELLOW | | | | | 102 | | | | 135 | | | | | | | | | |
| GREEN | | | | | | | | | | | | | | | | | | |
| RED ARROW | | | | | | 101 | | | 134 | | | 107 | | | | | | |
| YELLOW ARROW | | 129 | | | 102 | | | | 135 | | | 108 | | | | | | |
| GREEN ARROW | | 130 | | | 103 | 103 | | | 136 | 136 | | 109 | | | | | | |

NU = Not Used
NC = Not Connected

EQUIPMENT INFORMATION

CONTROLLER.....2070E
CABINET.....332 W/ AUX
SOFTWARE.....ECONOLITE OASIS
CABINET MOUNT.....BASE
OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
LOAD SWITCHES USED.....S2,S5,S8,S11
PHASES USED.....2,4,6,*7,8
OVERLAPS.....NONE
* PHASE USED FOR TIMING PURPOSES ONLY

DYNAMIC OMIT CONTROL PROGRAMMING

(program controller as shown below)

- From Main Menu press '2' (Phase Control), then '1' (Phase Control Functions). Scroll to the bottom of the menu and enable Dynamic/Backup Control Functions 1 and 2.
- From Phase Control Functions Menu press '2' (Dynamic/Backup Control Functions).

DYNAMIC/BACKUP CONTROL FUNCTION #01
OVERLAPS: ABCDEFGHIJKLMNPO
IF OVERLAPS ARE ACTIVE :
OR PHASES: 12345678910111213141516
IF PHASES ARE ON: X X
OMIT PHASES : X
CALL PHASES : X

PRESS 'NEXT'

DYNAMIC/BACKUP CONTROL FUNCTION #02
OVERLAPS: ABCDEFGHIJKLMNPO
IF OVERLAPS ARE ACTIVE :
OR PHASES: 12345678910111213141516
IF PHASES ARE ON: X
OMIT PHASES : X
CALL PHASES : X

DYNAMIC OMIT PROGRAMMING COMPLETE

NOTE: THIS PROGRAMMING ENSURES THAT PHASE 7 WILL BE SERVED PRIOR TO PHASE 8 WHEN CONTROLLER IS ADVANCING FROM 2+6.

PHASE 7 IS USED TO PROVIDE EXTENDED RED CLEARANCE BEFORE SERVING PHASE 8.

INPUT FILE POSITION LAYOUT

(front view)

| FILE "I" | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 |
|----------|-----|-----|-----|-----|-------|--------------|---|--------------|---|----|----|----|----|-------------|
| S | ∅ 2 | ∅ 2 | S | S | ∅ 4 | SYS. DET. S1 | S | SYS. DET. S3 | S | S | S | S | S | FS |
| U | 2A | 2C | ∅ 2 | ∅ 2 | ∅ 4 | SYS. DET. S2 | S | SYS. DET. S4 | S | S | S | S | S | DC ISOLATOR |
| L | 2B | 2D | ∅ 2 | ∅ 2 | ∅ 4 | SYS. DET. S2 | S | SYS. DET. S4 | S | S | S | S | S | DC ISOLATOR |
| FILE "J" | ∅ 6 | ∅ 6 | S | S | ∅ 7/8 | SYS. DET. S5 | S | SYS. DET. S7 | S | S | S | S | S | S |
| U | 6A | ∅ 6 | ∅ 6 | ∅ 6 | ∅ 7/8 | SYS. DET. S5 | S | SYS. DET. S7 | S | S | S | S | S | S |
| L | 6B | ∅ 6 | ∅ 6 | ∅ 6 | ∅ 7/8 | SYS. DET. S6 | S | SYS. DET. S8 | S | S | S | S | S | S |

EX.: 1A, 2A, ETC. = LOOP NO.'S


FS = FLASH SENSE
ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 2A | TB2-5,6 | I2U | 39 | 1 | 2 | 2 | | Y | | 2,4 | |
| 2B | TB2-7,8 | I2L | 43 | 5 | 12 | 2 | | Y | | 2,4 | |
| 2C | TB2-9,10 | I3U | 63 | 25 | 32 | 2 | Y | Y | | | |
| 2D | TB2-11,12 | I3L | 76 | 38 | 42 | 2 | Y | Y | | | |
| 4A | TB4-9,10 | I6U | 41 | 3 | 4 | 4 | Y | Y | | | |
| 4B | TB4-11,12 | I6L | 45 | 7 | 14 | 4 | Y | Y | | | |
| * S1 | TB6-1,2 | I7U | 65 | 27 | 34 | SYS | | | | | |
| * S2 | TB6-3,4 | I7L | 78 | 40 | 44 | SYS | | | | | |
| * S3 | TB6-9,10 | I9U | 60 | 22 | 11 | SYS | | | | | |
| * S4 | TB6-11,12 | I9L | 62 | 24 | 13 | SYS | | | | | |
| 6A | TB3-5,6 | J2U | 40 | 2 | 6 | 6 | Y | Y | | | |
| 6B | TB3-7,8 | J2L | 44 | 6 | 16 | 6 | Y | Y | | | |
| 8A | TB5-9,10 | J6U | 42 | 4 | 8 | 7/8 | Y | Y | | | |
| 8B | TB5-11,12 | J6L | 46 | 8 | 18 | 7/8 | Y | Y | | | |
| * S5 | TB7-1,2 | J7U | 66 | 28 | 38 | SYS | | | | | |
| * S6 | TB7-3,4 | J7L | 79 | 41 | 48 | SYS | | | | | |
| * S7 | TB7-9,10 | J9U | 59 | 21 | 15 | SYS | | | | | |
| * S8 | TB7-11,12 | J9L | 61 | 23 | 17 | SYS | | | | | |

* SYSTEM DETECTOR ONLY. REMOVE THE VEHICLE PHASE ASSIGNED TO THIS DETECTOR IN THE DEFAULT PROGRAMMING.

INPUT FILE POSITION LEGEND: J2L



PHASE SEQUENCE PROGRAMMING DETAIL

(program controller as shown below)

FROM OASIS LOCAL CONTROLLER MAIN MENU
SELECT: 4 PHASE SEQUENCE


PHASE SEQUENCE: PAGE 1 NEXT: PAGES)

| RNG | LEAD | BARRIER 1 | X-LAG | LEAD | BARRIER 2 | X-LAG |
|-----|------|-----------|-------|------|-----------|-------|
| 1 | 0 | 2 | 0 | 4 | 0 | 0 |
| 2 | 0 | 6 | 0 | 7 | 0 | 0 |
| 3 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4 | 0 | 0 | 0 | 0 | 0 | 0 |


THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0902
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A

Electrical Detail - Final Design
Signal Upgrade

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED




US 25 (Asheville Highway)
at
I-26 WB Ramps
Division 14 Henderson Co. Hendersonville
PLAN DATE: September 2018 REVIEWED BY: A.D. Klinskiak
PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons



HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997


DocuSigned by:
Natasha R. Simmons 4/26/2019
SIGNATURE DATE
SIG. INVENTORY NO. 14-0902

Design Loading for METAL POLE NO. 1



Elevation View

Design Loading for METAL POLE NO. 2




Elevation View

SPECIAL NOTE


The contractor is responsible for verifying that the mast arm attachment height (H1) will provide the "Design Height" clearance from the roadway before submitting final shop drawings for approval. Verify elevation data below which was obtained by field measurement or from available project survey data.

Elevation Data for Mast Arm Attachment (H1)


| Elevation Differences for: | Pole 1 | Pole 2 |
|--|-----------|-----------|
| Baseline reference point at ϕ Foundation @ ground level | 0.0 ft. | 0.0 ft. |
| Elevation difference at High point of roadway surface | +1.28 ft. | -0.73 ft. |
| Elevation difference at Edge of travelway or face of curb | +0.61 ft. | -0.78 ft. |



POLE RADIAL ORIENTATION



8 BOLT BASE PLATE DETAIL



BASE PLATE TEMPLATE & ANCHOR BOLT LOCK PLATE DETAIL For 8 Bolt Base Plate

METAL POLE No. 1,2

| | |
|-----------------------|-----------|
| PROJECT REFERENCE NO. | SHEET NO. |
| I-4400C | Fig. 15.2 |

MAST ARM LOADING SCHEDULE

| LOADING SYMBOL | DESCRIPTION | AREA | SIZE | WEIGHT |
|----------------|--|-----------|-------------------|--------|
| | RIGID MOUNTED SIGNAL HEAD 12"-3 SECTION-WITH BACKPLATE | 9.3 S.F. | 25.5" W X 52.5" L | 60 LBS |
| | SIGN RIGID MOUNTED | 7.5 S.F. | 30.0" W X 36.0" L | 14 LBS |
| | STREET NAME SIGN RIGID MOUNTED | 12.0 S.F. | 18.0" W X 96.0" L | 27 LBS |

NOTES

DESIGN REFERENCE MATERIAL

- Design the traffic signal structure and foundation in accordance with:
 - The 6th Edition 2013 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions.
 - The 2018 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signal project special provisions.
 - The 2018 NCDOT Roadway Standard Drawings.
 - The traffic signal project plans and special provisions.
 - The NCDOT "Metal Pole Standards" located at the following NCDOT website: <https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

DESIGN REQUIREMENTS

- Design the traffic signal structure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signal plans for the actual loads that will be applied at the time of the installation.
- Design all signal supports using stress ratios that do not exceed 0.9.
- The camber design for the mast arm deflection should provide an appearance of a low pitched arch where the tip or the free end of the mast arm does not deflect below horizontal when fully loaded.
- A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design requirements.
- Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts.
- The mast arm attachment height (H1) shown is based on the following design assumptions:
 - Mast arm slope and deflection are not considered in determining the arm attachment height as they are assumed to offset each other.
 - Signal heads are rigidly mounted and vertically centered on the mast arm.
 - The roadway clearance height for design is as shown in the elevation views.
 - The top of the pole base plate is 0.75 feet above the ground elevation.
 - Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground level and the high point of the roadway.
- The pole manufacturer will determine the total height (H2) of each pole using the greater of the following:
 - Mast arm attachment height (H1) plus 2 feet, or
 - H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot.
- If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919) 814-5000.
- The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signal heads over the roadway.
- The contractor is responsible for providing soil penetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed.


All metal poles and arms should be BLACK in color as specified in the project special provisions.

NCDOT Wind Zone 4 (90 mph)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|---|--|---|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | | |
| | Division 14 Henderson Co. Hendersonville | PLAN DATE: September 2018 REVIEWED BY: A.D. Klinsky | |
| PREPARED BY: A.H. Thornburg | SCALE: 0 N/A N/A | REVISIONS: | DATE: |
| HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | | | DocuSigned by: SIGNATURE DATE SIG. INVENTORY NO. 14-0902 |


Design Loading for METAL POLE NO. 3




Elevation View

SPECIAL NOTE
 The contractor is responsible for verifying that the mast arm attachment height (H1) will provide the "Design Height" clearance from the roadway before submitting final shop drawings for approval. Verify elevation data below which was obtained by field measurement or from available project survey data.


| Elevation Data for Mast Arm Attachment (H1) | |
|--|-----------|
| Elevation Differences for: | Pole 3 |
| Baseline reference point at ϕ Foundation @ ground level | 0.0 ft. |
| Elevation difference at High point of roadway surface | +0.05 ft. |
| Elevation difference at Edge of travelway or face of curb | -0.66 ft. |



POLE RADIAL ORIENTATION



8 BOLT BASE PLATE DETAIL



BASE PLATE TEMPLATE & ANCHOR BOLT LOCK PLATE DETAIL For 8 Bolt Base Plate

HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

METAL POLE No. 3

| PROJECT REFERENCE NO. | SHEET NO. |
|-----------------------|-----------|
| I-4400C | Sig. 15.3 |

| MAST ARM LOADING SCHEDULE | | | | |
|---------------------------|--|-----------|-------------------|--------|
| LOADING SYMBOL | DESCRIPTION | AREA | SIZE | WEIGHT |
| | RIGID MOUNTED SIGNAL HEAD 12"-3 SECTION-WITH BACKPLATE | 9.3 S.F. | 25.5" W X 52.5" L | 60 LBS |
| | SIGN RIGID MOUNTED | 7.5 S.F. | 30.0" W X 36.0" L | 14 LBS |
| | STREET NAME SIGN RIGID MOUNTED | 16.0 S.F. | 24.0" W X 96.0" L | 36 LBS |

NOTES

DESIGN REFERENCE MATERIAL

- Design the traffic signal structure and foundation in accordance with:
 - The 6th Edition 2013 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions.
 - The 2018 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signal project special provisions.
 - The 2018 NCDOT Roadway Standard Drawings.
 - The traffic signal project plans and special provisions.
 - The NCDOT "Metal Pole Standards" located at the following NCDOT website: <https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

DESIGN REQUIREMENTS

- Design the traffic signal structure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signal plans for the actual loads that will be applied at the time of the installation.
- Design all signal supports using stress ratios that do not exceed 0.9.
- The camber design for the mast arm deflection should provide an appearance of a low pitched arch where the tip or the free end of the mast arm does not deflect below horizontal when fully loaded.
- A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design requirements.
- Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts.
- The mast arm attachment height (H1) shown is based on the following design assumptions:
 - Mast arm slope and deflection are not considered in determining the arm attachment height as they are assumed to offset each other.
 - Signal heads are rigidly mounted and vertically centered on the mast arm.
 - The roadway clearance height for design is as shown in the elevation views.
 - The top of the pole base plate is 0.75 feet above the ground elevation.
 - Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground level and the high point of the roadway.
- The pole manufacturer will determine the total height (H2) of each pole using the greater of the following:
 - Mast arm attachment height (H1) plus 2 feet, or
 - H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot.
- If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919) 814-5000.
- The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signal heads over the roadway.
- The contractor is responsible for providing soil penetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed.

All metal poles and arms should be BLACK in color as specified in the project special provisions.

NCDOT Wind Zone 4 (90 mph)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | |
|---------------------|--|--|
| | US 25 (Asheville Highway) at I-26 WB Ramps | |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinsky PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| SCALE: 0 N/A N/A | REVISIONS: _____ INITI. DATE | DocuSigned by: Melissa R. Simmons 1/26/2019 SIGNATURE DATE SIG. INVENTORY NO. 14-0902 |

PHASING DIAGRAM





TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | | FLASH |
|-------------|-------|-------|-----|-----|-------|
| | Ø 2+5 | Ø 2+6 | Ø 4 | Ø 4 | |
| 21,22 | G | G | R | Y | |
| 41 | R | R | G | R | |
| 42 | R | R | G | R | |
| 51 | - | - | - | - | - |
| 61,62 | R | G | R | Y | |

SIGNAL FACE I.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | SYSTEM LOOP | NEW CARD | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|--------------|-------------|----------|------------|
| | | | | | PHASE | CALLING | EXTENSION | STRETCH TIME | | | DELAY TIME |
| 2A | 6X6 | 300 | 4 | - | 2 | Y | Y | - | - | - | Y |
| 2B | 6X6 | 300 | 4 | - | 2 | Y | Y | - | - | - | Y |
| 4A | 6X40 | 0 | * | Y | 4 | Y | Y | - | - | 3 | - |
| 5A | 6X40 | 0 | 2-4-2 | Y | 5 | Y | Y | - | - | 15 | - |
| 5B | 6X40 | 0 | * | Y | 5 | Y | Y | - | - | 15 | - |
| 6A | 6X6 | 300 | 5 | - | 6 | Y | Y | - | - | - | Y |
| 6B | 6X6 | 300 | 5 | - | 6 | Y | Y | - | - | - | Y |
| S1 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |
| S2 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |
| S3 | 6X6 | +150 | 4 | Y | - | - | - | - | - | - | Y |
| S4 | 6X6 | +150 | 4 | Y | - | - | - | - | - | - | Y |



* Multizone Microwave Detection

3 Phase Fully Actuated Asheville Signal System

NOTES


1. Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Phase 5 may be lagged.
4. Set all detector units to presence mode.
5. In the event of loop replacement, refer to the current ITS and Signals Design Manual and submit a Plan of Record to the Signal Design Section.
6. Locate new cabinet so not to obstruct sight distance of vehicles turning right on red.
7. Incorporate Microwave Detection system for vehicle detection.
8. Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
9. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.

PHASING DIAGRAM DETECTION LEGEND




OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | |
|-------------------------|------------|-----|-----|------------|
| | 2 | 4 | 5 | 6 |
| Min Green 1 * | 12 | 7 | 7 | 12 |
| Extension 1 * | 6.0 | 2.0 | 2.0 | 6.0 |
| Max Green 1 * | 90 | 20 | 20 | 90 |
| Yellow Clearance | 4.7 | 3.0 | 3.0 | 4.7 |
| Red Clearance | 1.3 | 2.3 | 2.6 | 1.3 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | 1.5 | - | - | 1.5 |
| Max Variable Initial * | 34 | - | - | 34 |
| Time Before Reduction * | 15 | - | - | 15 |
| Time To Reduce * | 30 | - | - | 30 |
| Minimum Gap | 3.0 | - | - | 3.0 |
| Recall Mode | MIN RECALL | - | - | MIN RECALL |
| Vehicle Call Memory | YELLOW | - | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |



LEGEND




Signal Upgrade
Temporary Design 1
Construction Phase 1

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | | |
|--|--|--|---|
| | Prepared for: TRANSPORTATION MOBILITY AND SAFETY DIVISION NORTH CAROLINA DEPARTMENT OF TRANSPORTATION SIGNAL DESIGN SECTION 750 N. Greenfield Pkwy, Garner, NC 27525 | US 25 (Asheville Highway)/ US 25 (Hendersonville Road) at SR 1345 (Butler Bridge Road) Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | SEAL |
| | HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | REVISIONS 0 30 1"=30' | DocuSigned by: Natasha R. Simmons 10/26/2019 SIGNATURE DATE SIG. INVENTORY NO. 14-074211 |

EDI MODEL 2018EClip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.
- Integrate monitor with Ethernet network in cabinet.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Enable Simultaneous Gap-Out for all Phases.
- Program phases 2 and 6 for Variable Initial and Gap Reduction.
- Program phases 2 and 6 for Startup In Green.
- Program phases 2 and 6 for Yellow Flash.
- The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 | AUX S1 | AUX S2 | AUX S3 | AUX S4 | AUX S5 | AUX S6 | |
|-----------------------|----|-------|-------|----|-------|-------|-----|-----|-------|-----|-----|-------|--------|--------|--------|--------|--------|--------|------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 | 9 | 10 | 17 | 11 | 12 | 18 | |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED | OLA | OLB | SPARE | OLC | OLD | SPARE | |
| SIGNAL HEAD NO. | NU | 21,22 | NU | NU | 41,42 | NU | 42 | 51* | 61,62 | NU | NU | NU | NU | NU | NU | 51* | NU | NU | |
| RED | | 128 | | | 101 | | * | | 134 | | | | | | | | | | |
| YELLOW | | 129 | | | 102 | | | | 135 | | | | | | | | | | |
| GREEN | | 130 | | | 103 | | | | 136 | | | | | | | | | | |
| RED ARROW | | | | | | | | | | | | | | | | | | A114 | |
| YELLOW ARROW | | | | | | | | 132 | | | | | | | | | | | A115 |
| FLASHING YELLOW ARROW | | | | | | | | | | | | | | | | | | | A116 |
| GREEN ARROW | | | | | | | 133 | 133 | | | | | | | | | | | |


NU = Not Used
 * Denotes install load resistor. See load resistor installation detail this sheet.
 ★ See pictorial of head wiring in detail this sheet.

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....332 W/AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
 LOAD SWITCHES USED.....S2,S5,S7,S8,AUX S4
 PHASES USED.....2,4,5,6
 OVERLAP "A".....NOT USED
 OVERLAP "B".....NOT USED
 OVERLAP "C".....5+6
 OVERLAP "D".....NOT USED

FYA SIGNAL WIRING DETAIL

(wire signal head as shown)




NOTE

The sequence display for signal head 51 requires special logic programming. See sheet 2 for programming instructions.

INPUT FILE POSITION LAYOUT

(front view)



EX. : 1A, 2A, ETC. = LOOP NO.'S

⊗ Wired Input - Do not populate slot with detector cord


FS = FLASH SENSE
 ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|-----------------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 2A | TB2-5,6 | I2U | 39 | 1 | 2 | 2 | Y | Y | | | |
| 2B | TB2-7,8 | I2L | 43 | 5 | 12 | 2 | Y | Y | | | |
| * S1 | TB6-9,10 | I9U | 60 | 22 | 11 | SYS | | | | | |
| * S2 | TB6-11,12 | I9L | 62 | 24 | 13 | SYS | | | | | |
| 5A ¹ | TB3-1,2 | J1U | 55 | 17 | 5 | 5 | Y | Y | | | 15 |
| | - | I4U | 47 | 9 | 22 | 2 | Y | Y | Y | | 3 |
| 6A | TB3-9,10 | J3U | 64 | 26 | 36 | 6 | Y | Y | | | |
| 6B | TB3-11,12 | J3L | 77 | 39 | 46 | 6 | Y | Y | | | |
| * S3 | TB7-9,10 | J9U | 59 | 21 | 15 | SYS | | | | | |
| * S4 | TB7-11,12 | J9L | 61 | 23 | 17 | SYS | | | | | |

¹Add jumper from J1-W to I4-W. on rear of input file.
 * System detector only. Remove the vehicle phase assigned to this detector in the default programming.

INPUT FILE POSITION LEGEND: J2L




SPECIAL DETECTOR NOTE

For detection zones 4A and 5B install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.


LOAD RESISTOR INSTALLATION DETAIL

(install resistor as shown below)

| ACCEPTABLE VALUES | |
|-------------------|-----------|
| VALUE (ohms) | WATTAGE |
| 1.5K - 1.9K | 25W (min) |
| 2.0K - 3.0K | 10W (min) |



ELECTRICAL AND PROGRAMMING DETAILS FOR:




US 25 (Asheville Highway)/
 US 25 (Hendersonville Road) at
 SR 1345 (Butler Bridge Road)

Division 14 Henderson Co. Hendersonville
 PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek
 PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

| REVISIONS | INIT. | DATE |
|-----------|-------|------|
| | | |

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED




DocuSigned by:
 Natasha R. Simmons 4/26/2019
 SIGNATURE DATE
 Sig. INVENTORY NO. 14-0742T1


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)


1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2, and 3.
2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).



NOTE: LOGIC FOR PHASE 5 RED CLEAR WHEN TRANSITIONING FROM PHASE 5 TO PHASE 6 (HEAD 51).



NOTE: LOGIC FOR SWITCHING FLASHING YELLOW ARROW OFF DURING PHASE 5 (HEAD 51).



NOTE: LOGIC FOR YELLOW ARROW CLEARANCE FROM PHASE 5 (HEAD 51).

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

| <u>OUTPUT REFERENCE SCHEDULE</u> |
|----------------------------------|
| USE TO INTERPRET LOGIC PROCESSOR |
| OUTPUT 42 = Overlap C Red |
| OUTPUT 43 = Overlap C Yellow |
| OUTPUT 44 = Overlap C Green |

OVERLAP PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).

PRESS '+' TWICE

```

PAGE 1: VEHICLE OVERLAP 'C' SETTINGS
PHASE:      12345678910111213141516
VEH OVL PARENTS:  XX
VEH OVL NOT VEH:
VEH OVL NOT PED:
VEH OVL GRN EXT:
STARTUP COLOR:  - RED  - YELLOW  - GREEN
FLASH COLORS:  - RED  - YELLOW  X GREEN
SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC)...0.0
YELLOW CLEAR (0=PARENT.3-25.5 SEC)...0.0
RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)...0
    
```

← NOTICE GREEN FLASH

OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0742T1
 DESIGNED: September 2018
 SEALED: 4/26/2019
 REVISED: N/A


Electrical Detail - Sheet 2 of 2
 Signal Upgrade
 Temporary Design 1
 Construction Phase 1

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

| <p style="font-size: small;">ELECTRICAL AND PROGRAMMING DETAILS FOR:</p> <p style="font-size: x-small;">Prepared for:</p> <p style="font-size: x-small;">1750 N. Greenfield Pkwy, Corner, NC 27529</p> | <p style="text-align: center;">US 25 (Asheville Highway)/ US 25 (Hendersonville Road) at SR 1345 (Butler Bridge Road)</p> <p style="font-size: x-small;">Division 14 Henderson Co. Hendersonville</p> <p style="font-size: x-small;">PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek</p> <p style="font-size: x-small;">PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons</p> <table border="1" style="width: 100%; border-collapse: collapse; font-size: x-small;"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table> | REVISIONS | INIT. | DATE | | | | | | | | | | <p style="font-size: x-small;">SEAL</p> <p style="font-size: x-small;">NATASHA R. SIMMONS</p> |
|--|--|----------------------|-------|------|--|--|--|--|--|--|--|--|--|---|
| REVISIONS | INIT. | DATE | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| DocuSigned by: Natasha R. Simmons 4/26/2019 | | DATE DATE DATE | | | | | | | | | | | | |
| SIG. INVENTORY NO. 14-0742T1 | | | | | | | | | | | | | | |

PHASING DIAGRAM




PHASING DIAGRAM DETECTION LEGEND

- ←●→ DETECTED MOVEMENT
- ←○→ UNDETECTED MOVEMENT (OVERLAP)
- ←...→ UNSIGNALIZED MOVEMENT
- ←- - -→ PEDESTRIAN MOVEMENT

TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | |
|-------------|-------|------|----|-------|
| | 02+5 | 02+6 | 04 | FLASH |
| 21,22 | G | G | R | Y |
| 41 | R | R | G | R |
| 42 | R | R | G | R |
| 51 | - | - | - | - |
| 61,62 | R | G | R | Y |

SIGNAL FACE I.D.




OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | SYSTEM LOOP | NEW CARD |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|-------------|----------|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | | |
| 2A | 6X6 | 300 | 4 | - | 2 | Y | Y | - | - | - | - |
| 2B | 6X6 | 300 | 4 | - | 2 | Y | Y | - | - | - | - |
| 4A | 6X40 | 0 | 2-4-2 | Y | 4 | Y | Y | - | - | 3 | - |
| 5A | 6X40 | 0 | 2-4-2 | - | 5 | Y | Y | - | - | 15 | - |
| 5B | 6X40 | 0 | 2-4-2 | Y | 5 | Y | Y | - | - | 15 | - |
| 6A | 6X6 | 300 | 5 | - | 6 | Y | Y | - | - | - | - |
| 6B | 6X6 | 300 | 5 | - | 6 | Y | Y | - | - | - | - |
| S1 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |
| S2 | 6X6 | +120 | 4 | - | - | - | - | - | - | - | Y |
| S3 | 6X6 | +150 | 4 | - | - | - | - | - | - | - | Y |
| S4 | 6X6 | +150 | 4 | - | - | - | - | - | - | - | Y |

3 Phase Fully Actuated Asheville Signal System

NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Phase 5 may be lagged.
4. Set all detector units to presence mode.
5. Reposition existing signal heads numbered 41 and 42.
6. In the event of loop replacement, refer to the current ITS and Signals Design Manual and submit a Plan of Record to the Signal Design Section.
7. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | |
|-------------------------|------------|-----|-----|------------|
| | 2 | 4 | 5 | 6 |
| Min Green 1 * | 12 | 7 | 7 | 12 |
| Extension 1 * | 6.0 | 2.0 | 2.0 | 6.0 |
| Max Green 1 * | 90 | 20 | 20 | 90 |
| Yellow Clearance | 4.7 | 3.0 | 3.0 | 4.7 |
| Red Clearance | 1.6 | 2.4 | 2.4 | 1.6 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | 1.5 | - | - | 1.5 |
| Max Variable Initial * | 34 | - | - | 34 |
| Time Before Reduction * | 15 | - | - | 15 |
| Time To Reduce * | 30 | - | - | 30 |
| Minimum Gap | 3.0 | - | - | 3.0 |
| Recall Mode | MIN RECALL | - | - | MIN RECALL |
| Vehicle Call Memory | YELLOW | - | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

LEGEND

| PROPOSED | EXISTING |
|---------------------------------|---------------------------------|
| ○→ Traffic Signal Head | ●→ Traffic Signal Head |
| ○→ Modified Signal Head | N/A |
| — Sign | — Sign |
| □ Pedestrian Signal Head | □ Pedestrian Signal Head |
| □ With Push Button & Sign | □ With Push Button & Sign |
| □ Signal Pole with Guy | □ Signal Pole with Guy |
| □ Signal Pole with Sidewalk Guy | □ Signal Pole with Sidewalk Guy |
| □ Inductive Loop Detector | □ Inductive Loop Detector |
| □ Controller & Cabinet | □ Controller & Cabinet |
| □ Junction Box | □ Junction Box |
| □ Over-sized Junction Box | □ Over-sized Junction Box |
| — 2-in Underground Conduit | — 2-in Underground Conduit |
| N/A Right of Way | — Right of Way |
| → Directional Arrow | → Directional Arrow |
| — DD Directional Drill | N/A |
| ○ Metal Pole with Mastarm | ○ Metal Pole with Mastarm |

Signal Upgrade - Final Design

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

US 25 (Asheville Highway)/
US 25 (Hendersonville Road) at
SR 1345 (Butler Bridge Road)

Division 14 Henderson Co. Hendersonville
PLAN DATE: September 2018 REVIEWED BY: A.D. Klinsky
PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

SEAL


DocuSigned by:
Natasha R. Simmons 1/26/2019

| REVISIONS | INIT. | DATE |
|-----------|-------|------|
| | | |
| | | |

SIG. INVENTORY NO. 14-0742

EDI MODEL 2018EClip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all Phases.
3. Program phases 2 and 6 for Variable Initial and Gap Reduction.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 6 for Yellow Flash.
6. The cabinet and controller are part of the Asheville Signal System.

SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 | AUX S1 | AUX S2 | AUX S3 | AUX S4 | AUX S5 | AUX S6 | |
|-----------------------|----|-------|-------|----|-------|-------|-----|-----|-------|-----|-----|-------|--------|--------|--------|--------|--------|--------|------|
| CMU CHANNEL NO. | 1 | 2 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 | 9 | 10 | 17 | 11 | 12 | 18 | |
| PHASE | 1 | 2 | 2 PED | 3 | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED | OLA | OLB | SPARE | OLC | OLD | SPARE | |
| SIGNAL HEAD NO. | NU | 21,22 | NU | NU | 41,42 | NU | 42 | 51* | 61,62 | NU | NU | NU | NU | NU | NU | 51* | NU | NU | |
| RED | | 128 | | | 101 | | * | | 134 | | | | | | | | | | |
| YELLOW | | 129 | | | 102 | | | | 135 | | | | | | | | | | |
| GREEN | | 130 | | | 103 | | | | 136 | | | | | | | | | | |
| RED ARROW | | | | | | | | | | | | | | | | | | A114 | |
| YELLOW ARROW | | | | | | | | 132 | | | | | | | | | | | A115 |
| FLASHING YELLOW ARROW | | | | | | | | | | | | | | | | | | | A116 |
| GREEN ARROW | | | | | | | 133 | 133 | | | | | | | | | | | |


NU = Not Used
 * Denotes install load resistor. See load resistor installation detail this sheet.
 * See pictorial of head wiring in detail this sheet.

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....332 W/AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
 LOAD SWITCHES USED.....S2,S5,S7,S8,AUX S4
 PHASES USED.....2,4,5,6
 OVERLAP "A".....NOT USED
 OVERLAP "B".....NOT USED
 OVERLAP "C".....5+6
 OVERLAP "D".....NOT USED

FYA SIGNAL WIRING DETAIL

(wire signal head as shown)




NOTE

The sequence display for signal head 51 requires special logic programming. See sheet 2 for programming instructions.

INPUT FILE POSITION LAYOUT

(front view)




EX.: 1A, 2A, ETC. = LOOP NO.'S
 FS = FLASH SENSE
 ST = STOP TIME
 * Wired Input - Do not populate slot with detector card

INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|-----------------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| 2A | TB2-5,6 | I2U | 39 | 1 | 2 | 2 | Y | Y | | | |
| 2B | TB2-7,8 | I2L | 43 | 5 | 12 | 2 | Y | Y | | | |
| 4A | TB4-9,10 | I6U | 41 | 3 | 4 | 4 | Y | Y | | | 3 |
| * S1 | TB6-9,10 | I9U | 60 | 22 | 11 | SYS | | | | | |
| * S2 | TB6-11,12 | I9L | 62 | 24 | 13 | SYS | | | | | |
| 5A ¹ | TB3-1,2 | J1U | 55 | 17 | 5 | 5 | Y | Y | | | 15 |
| | - | I4U | 47 | 9 | 22 | 2 | Y | Y | Y | | 3 |
| 5B | TB3-5,6 | J2U | 40 | 2 | 6 | 5 | Y | Y | | | 15 |
| 6A | TB3-9,10 | J3U | 64 | 26 | 36 | 6 | Y | Y | | | |
| 6B | TB3-11,12 | J3L | 77 | 39 | 46 | 6 | Y | Y | | | |
| * S3 | TB7-9,10 | J9U | 59 | 21 | 15 | SYS | | | | | |
| * S4 | TB7-11,12 | J9L | 61 | 23 | 17 | SYS | | | | | |

¹Add jumper from J1-W to I4-W, on rear of input file.
 * System detector only. Remove the vehicle phase assigned to this detector in the default programming.


INPUT FILE POSITION LEGEND: J2L



LOAD RESISTOR INSTALLATION DETAIL

(install resistor as shown below)

| ACCEPTABLE VALUES | |
|-------------------|-----------|
| VALUE (ohms) | WATTAGE |
| 1.5K - 1.9K | 25W (min) |
| 2.0K - 3.0K | 10W (min) |



Electrical Detail - Final Design Signal Upgrade - Sheet 1 of 2

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared for:

US 25 (Asheville Highway)/
 US 25 (Hendersonville Road) at
 SR 1345 (Butler Bridge Road)
 Division 14 Henderson Co. Hendersonville
 PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek
 PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

SEAL


HNTB
 HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

REVISIONS: _____ INITI: _____ DATE: _____
 Signed by: Natasha R. Simmons 14-0742
 DATE: _____
 SIG. INVENTORY NO. 14-0742


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)


1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2, and 3.
2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).



NOTE: LOGIC FOR PHASE 5 RED CLEAR WHEN TRANSITIONING FROM PHASE 5 TO PHASE 6 (HEAD 51).



NOTE: LOGIC FOR SWITCHING FLASHING YELLOW ARROW OFF DURING PHASE 5 (HEAD 51).



NOTE: LOGIC FOR YELLOW ARROW CLEARANCE FROM PHASE 5 (HEAD 51).

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

| <u>OUTPUT REFERENCE SCHEDULE</u> | |
|----------------------------------|--|
| USE TO INTERPRET LOGIC PROCESSOR | |
| OUTPUT 42 = Overlap C Red | |
| OUTPUT 43 = Overlap C Yellow | |
| OUTPUT 44 = Overlap C Green | |

OVERLAP PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).

PRESS '+' TWICE

```

PAGE 1: VEHICLE OVERLAP 'C' SETTINGS
PHASE:      12345678910111213141516
VEH OVL PARENTS:  XX
VEH OVL NOT VEH:
VEH OVL NOT PED:
VEH OVL GRN EXT:
STARTUP COLOR:  - RED  - YELLOW  - GREEN
FLASH COLORS:  - RED  - YELLOW  X GREEN
SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC)...0.0
YELLOW CLEAR (0=PARENT.3-25.5 SEC)...0.0
RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)...0
    
```

← NOTICE GREEN FLASH

OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0742
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A


Electrical Detail - Final Design
Signal Upgrade - Sheet 2 of 2

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

| <p style="font-size: small;">ELECTRICAL AND PROGRAMMING DETAILS FOR:</p> <p style="font-size: x-small;">Prepared for: 750 N. Greenfield Pkwy, Corner, NC 27529</p> | <p style="text-align: center;">US 25 (Asheville Highway)/ US 25 (Hendersonville Road) at SR 1345 (Butler Bridge Road)</p> <p style="font-size: x-small;">Division 14 Henderson Co. Hendersonville</p> <p style="font-size: x-small;">PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons</p> <table border="1" style="width: 100%; border-collapse: collapse; font-size: x-small;"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table> | REVISIONS | INIT. | DATE | | | | | | | | | | <p style="font-size: x-small;">SEAL</p> <p style="font-size: x-small;">DocuSigned by: <i>Natasha R. Simmons</i> 4/26/2019</p> <p style="font-size: x-small;">SIGNATURE DATE</p> <p style="font-size: x-small;">SIG. INVENTORY NO. 14-0742</p> |
|---|---|-----------|-------|------|--|--|--|--|--|--|--|--|--|---|
| REVISIONS | INIT. | DATE | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |




Design Loading for METAL POLE NO. 1



SPECIAL NOTE
 The contractor is responsible for verifying that the mast arm attachment height (H1) will provide the "Design Height" clearance from the roadway before submitting final shop drawings for approval. Verify elevation data below which was obtained by field measurement or from available project survey data.

Elevation Data for Mast Arm Attachment (H1)

| | | |
|--|-----------|--|
| Elevation Differences for: | Pole 1 | |
| Baseline reference point at ϕ Foundation @ ground level | 0.0 ft. | |
| Elevation difference at High point of roadway surface | +0.37 ft. | |
| Elevation difference at Edge of travelway or face of curb | +0.21 ft. | |



HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997

METAL POLE No. 1

| | |
|-----------------------|-----------|
| PROJECT REFERENCE NO. | SHEET NO. |
| I-4400C | Sig. 17.3 |

MAST ARM LOADING SCHEDULE

| LOADING SYMBOL | DESCRIPTION | AREA | SIZE | WEIGHT |
|----------------|---|-----------|-------------------------|--------|
| | RIGID MOUNTED SIGNAL HEAD 12"-3 SECTION-WITH BACKPLATE | 9.3 S.F. | 25.5" W X 52.5" L | 60 LBS |
| | RIGID MOUNTED SIGNAL HEAD 12"-4 SECTION-WITH BACKPLATE | 11.5 S.F. | 25.5" W X 66.0" L | 74 LBS |
| | SIGN RIGID MOUNTED | 7.5 S.F. | 30.0" W X 36.0" L | 14 LBS |
| | STREET NAME SIGN RIGID MOUNTED | 16.0 S.F. | 24.0" W X 96.0" L | 36 LBS |

NOTES

DESIGN REFERENCE MATERIAL

- Design the traffic signal structure and foundation in accordance with:
 - The 6th Edition 2013 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions.
 - The 2018 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signal project special provisions.
 - The 2018 NCDOT Roadway Standard Drawings.
 - The traffic signal project plans and special provisions.
 - The NCDOT "Metal Pole Standards" located at the following NCDOT website: <https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

DESIGN REQUIREMENTS

- Design the traffic signal structure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signal plans for the actual loads that will be applied at the time of the installation.
- Design all signal supports using stress ratios that do not exceed 0.9.
- The camber design for the mast arm deflection should provide an appearance of a low pitched arch where the tip or the free end of the mast arm does not deflect below horizontal when fully loaded.
- A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design requirements.
- Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts.
- The mast arm attachment height (H1) shown is based on the following design assumptions:
 - Mast arm slope and deflection are not considered in determining the arm attachment height as they are assumed to offset each other.
 - Signal heads are rigidly mounted and vertically centered on the mast arm.
 - The roadway clearance height for design is as shown in the elevation views.
 - The top of the pole base plate is 0.75 feet above the ground elevation.
 - Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground level and the high point of the roadway.
- The pole manufacturer will determine the total height (H2) of each pole using the greater of the following:
 - Mast arm attachment height (H1) plus 2 feet, or
 - H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot.
- If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919) 814-5000.
- The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signal heads over the roadway.
- The contractor is responsible for providing soil penetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed.

NCDOT Wind Zone 4 (90 mph)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | |
|-----------------------|--|--|
| | Prepared For: US 25 (Asheville Highway)/ US 25 (Hendersonville Road) at SR 1345 (Butler Bridge Road) | SEAL |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| SCALE 0 N/A N/A | REVISIONS INIT. DATE | DocuSigned by: SIGNATURE DATE SIG. INVENTORY NO. 14-0742 |

PHASING DIAGRAM






TABLE OF OPERATION

| SIGNAL FACE | PHASE | | | FLASH |
|-------------|-------|------|----|-------|
| | 01+6 | 02+6 | 08 | |
| 11 | — | Y | R | Y |
| 21,22 | R | G | R | Y |
| 61,62 | G | G | R | Y |
| 81 | R | R | G | R |
| 82 | R | R | G | R |

SIGNAL FACE I.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART


| LOOP | SIZE (FT) | DISTANCE FROM STOPBAR (FT) | TURNS | NEW LOOP | DETECTOR PROGRAMMING | | | | | SYSTEM LOOP | NEW CARD | |
|------|-----------|----------------------------|-------|----------|----------------------|---------|-----------|-----------------|--------------|-------------|----------|------------|
| | | | | | PHASE | CALLING | EXTENSION | FULL TIME DELAY | STRETCH TIME | | | DELAY TIME |
| 1A | 6X40 | 0 | * | Y | 1 | Y | Y | - | - | 15 | - | * |
| 1B | 6X40 | 0 | 2-4-2 | Y | 1 | Y | Y | - | - | 15 | - | Y |
| 2A | 6X6 | 70 | 4 | Y | 2 | Y | Y | - | - | - | - | Y |
| 6A | 6X6 | 70 | * | Y | 6 | Y | Y | - | - | - | - | * |
| 8A | 6X40 | 0 | 2-4-2 | Y | 8 | Y | Y | - | - | - | - | Y |

* Multizone Microwave Detection

3 Phase Fully Actuated Asheville Signal System

NOTES


1. Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Phase 1 may be lagged.
4. Set all detector units to presence mode.
5. Locate new cabinet so not to obstruct sight distance of vehicles turning right on red.
6. Incorporate Microwave Detection system for vehicle detection.
7. Provide the Engineer with the Manufacturer's approved Microwave Detection locations and mounting heights to obtain detection zones as shown.
8. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 TIMING CHART

| FEATURE | PHASE | | | |
|-------------------------|------------|-----|-----|------------|
| | 1 | 2 | 6 | 8 |
| Min Green 1 * | 7 | 12 | 12 | 7 |
| Extension 1 * | 2.0 | 3.0 | 3.0 | 2.0 |
| Max Green 1 * | 20 | 90 | 90 | 30 |
| Yellow Clearance | 3.0 | 3.9 | 3.9 | 3.0 |
| Red Clearance | 2.3 | 2.1 | 2.1 | 2.6 |
| Red Revert | 2.0 | 2.0 | 2.0 | 2.0 |
| Walk 1 * | - | - | - | - |
| Don't Walk 1 | - | - | - | - |
| Seconds Per Actuation * | - | - | - | - |
| Max Variable Initial * | - | - | - | - |
| Time Before Reduction * | - | - | - | - |
| Time To Reduce * | - | - | - | - |
| Minimum Gap | - | - | - | - |
| Recall Mode | MIN RECALL | - | - | MIN RECALL |
| Vehicle Call Memory | YELLOW | - | - | YELLOW |
| Dual Entry | - | - | - | - |
| Simultaneous Gap | ON | ON | ON | ON |

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.




New Installation

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | |
|---|--|---|
| | SR 1345 (Butler Bridge Road) at SR 1365 (N. Rugby Road) | SEAL |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |
| HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554 (919) 546-8997 | REVISIONS INIT. DATE | DocuSigned by: Natasha R. Simmons 12/26/2019 SIGNATURE DATE SIG. INVENTORY NO. 14-1307 |

EDI MODEL 2018EClip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.
- Integrate monitor with Ethernet network in cabinet.
- Special cabinet wiring is required to utilize FYA COMPACT mode. See Ped Yellow Conflict Monitor Wiring Detail on this sheet.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Enable Simultaneous Gap-Out for all Phases.
- Program phases 2 and 6 for Startup In Green.
- Program phases 2 and 6 for Yellow Flash, and overlap 1 as Wag Overlaps.
- The cabinet and controller are part of the Asheville Signal System.

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S1,S2,S3,S4,S8,S11
 PHASES USED.....1,2,6,8
 OVERLAP "A".....1+2
 OVERLAP "B".....NOT USED
 OVERLAP "C".....NOT USED
 OVERLAP "D".....NOT USED
 OVERLAP "G".....1


SIGNAL HEAD HOOK-UP CHART

| LOAD SWITCH NO. | S1 | S2 | S3 | S4 | S5 | S6 | S7 | S8 | S9 | S10 | S11 | S12 | |
|-----------------------|-----|-------|-------|-------|-----|----|-------|----|-------|-------|-----|-------|-------|
| CMU CHANNEL NO. | 1 | 2 | 9 | 13 | 3 | 4 | 14 | 5 | 6 | 15 | 7 | 8 | 16 |
| PHASE | OLA | 2 | 1 GRN | 2 PED | OLG | 4 | 4 PED | 5 | 6 | 6 PED | 7 | 8 | 8 PED |
| SIGNAL HEAD NO. | 11 | 21,22 | 11 | NU | 82 | NU | NU | NU | 61,62 | NU | NU | 81,82 | NU |
| RED | | 128 | | * | | | | | 134 | | | 107 | |
| YELLOW | | 129 | | | | | | | 135 | | | 108 | |
| GREEN | | 130 | | | | | | | 136 | | | 109 | |
| RED ARROW | 125 | | | | | | | | | | | | |
| YELLOW ARROW | 126 | | | 117 | | | | | | | | | |
| FLASHING YELLOW ARROW | 127 | | | | | | | | | | | | |
| GREEN ARROW | | | 114 | 118 | | | | | | | | | |
| Hand icon | | | | * | | | | | | | | | |

NU = Not Used
 * Denotes install load resistor. See load resistor installation detail this sheet.
 ★ See pictorial of head wiring in detail this sheet.
 NOTE: Load switches S1 and S3 require output remapping. See Sheet 3 of this electrical detail for instructions.

FYA SIGNAL WIRING DETAIL

(wire signal head as shown)



11

NOTE
 The sequence display for signal head 11 requires special logic and output remapping. See sheets 2-3 for programming instructions.

INPUT FILE POSITION LAYOUT

(front view)

| FILE POSITION | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 |
|---------------|----------|----------|---|---|---|---|----------|---|---|----|----|----|----|-------------|
| Ø 1 | Ø 1 | Ø 2 | S | S | S | S | Ø 8 | S | S | S | S | S | S | FS |
| ZONE 1A | ZONE 1B | ZONE 2A | W | W | W | W | NOT USED | W | W | W | W | W | W | DC ISOLATOR |
| WIRED INPUT | NOT USED | NOT USED | W | W | W | W | NOT USED | W | W | W | W | W | W | ST |

EX.: 1A, 2A, ETC. = LOOP NO.'S


FS = FLASH SENSE
 ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

| LOOP NO. | LOOP TERMINAL | INPUT FILE POS. | PIN NO. | INPUT ASSIGNMENT NO. | DETECTOR NO. | NEMA PHASE | CALL | EXTEND | FULL TIME DELAY | STRETCH TIME | DELAY TIME |
|----------------------|---------------|-----------------|---------|----------------------|--------------|------------|------|--------|-----------------|--------------|------------|
| ZONE 1A ¹ | ** | 11U | 56 | 18 | 1 | 1 | Y | Y | | | 15 |
| 1B | TB21-3,4 | 12U | 39 | 1 | 15 | 6 | Y | Y | Y | | 3 |
| 2A | TB21-5,6 | 13U | 58 | 20 | 2 | 1 | Y | Y | | | 15 |
| 8A | TB22-1,2 | 18U | 42 | 4 | 3 | 2 | Y | Y | | | |

¹Add jumper from 11-F to 11-SP, on rear of input file.
 * System detector only. Remove the vehicle phase assigned to this detector in the default programming.
 **Multizone Microwave Detector Zone. See Special Detector Note.

INPUT FILE POSITION LEGEND: J2L



SPECIAL DETECTOR NOTE


For loops 1A and 6A, install a microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

For loop 1A, detector card placement and slots reserved for wired inputs are typical for a NCDOT installation.

LOAD RESISTOR INSTALLATION DETAIL

(install resistors as shown below)

| ACCEPTABLE VALUES | |
|-------------------|-----------|
| VALUE (ohms) | WATTAGE |
| 1.5K - 1.9K | 25W (min) |
| 2.0K - 3.0K | 10W (min) |



Electrical Detail
 New Installation - Sheet 1 of 3
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


| | | | |
|--|--|--|--|
| | Prepared for: | SR 1345 (Butler Bridge Road) at SR 1365 (N. Rugby Road) | SEAL |
| | 750 N. Greenfield Pkwy, Corner, NC 27529 | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | REVISIONS INIT. DATE _____ _____ _____ |

HNTB HNTB NORTH CAROLINA, P.C.
 343 E. Six Forks Road, Suite 200
 Raleigh, North Carolina 27609
 NC License No: C-1554
 (919) 546-8997


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)


- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2, and 3.
- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).



NOTE: LOGIC FOR PHASE 1 RED CLEAR WHEN TRANSITIONING FROM PHASE 1 TO PHASE 2 (HEAD 11).



NOTE: LOGIC FOR SWITCHING FLASHING YELLOW ARROW OFF DURING PHASE 1 (HEAD 11).



NOTE: LOGIC FOR YELLOW ARROW CLEARANCE FROM PHASE 1 (HEAD 11).

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

| OUTPUT REFERENCE SCHEDULE | |
|---------------------------|--------------------|
| OUTPUT 14 | = Overlap A Red |
| OUTPUT 15 | = Overlap A Yellow |
| OUTPUT 16 | = Overlap A Green |

Note: All outputs shown above have been remapped. See sheet 3 of this electrical detail.

OVERLAP PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).

```

PAGE 1: VEHICLE OVERLAP 'A' SETTINGS
PHASE: :12345678910111213141516
VEH OVL PARENTS: :XX
VEH OVL NOT VEH: :
VEH OVL NOT PED: :
VEH OVL GRN EXT: :
STARTUP COLOR: - RED - YELLOW - GREEN
FLASH COLORS: - RED - YELLOW X GREEN
SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC)...0
YELLOW CLEAR (0=PARENT,3-25.5 SEC)...0.0
RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)...0
    
```

← NOTICE GREEN FLASH

PRESS '+' UNTIL OVERLAP G IS REACHED

```

PAGE 1: VEHICLE OVERLAP 'G' SETTINGS
PHASE: :12345678910111213141516
VEH OVL PARENTS: :X
VEH OVL NOT VEH: :
VEH OVL NOT PED: :
VEH OVL GRN EXT: :
STARTUP COLOR: - RED - YELLOW - GREEN
FLASH COLORS: - RED - YELLOW - GREEN
SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...N
GREEN EXTENSION (0-255 SEC)...0
YELLOW CLEAR (0=PARENT,3-25.5 SEC)...3.0
RED CLEAR (0=PARENT,0.1-25.5 SEC)...2.3
OUTPUT AS PHASE # (0=NONE, 1-16)...0
    
```

OVERLAP PROGRAMMING COMPLETE

PED YELLOW CONFLICT MONITOR WIRING DETAIL

(make cabinet wiring changes as shown below)

In order to use FYA COMPACT mode with the 2018ECLip-NC Monitor, the cabinet must be wired such that the (unused) Ped Yellow load switch outputs are wired to the conflict monitor as follows: From 2 PY (field term, 114) to chan. 9 green (monitor pin 13).

Follow the instructions below to make the appropriate connections:

- STEP 1: Fold down rear panel of output file.
- STEP 2: Find unused wiring harness from conflict monitor card edge connector (which should be tied and bundled together).
- STEP 3: Find the conductors that correspond to the following conflict monitor card edge pins and solder wire to the appropriate terminal on the rear of the output file as shown below:

CMU-13 _____ 2PY (term. 114)

NOTE: Some cabinet manufacturers use keyed connectors to accomplish this wiring configuration. If connectors are used, fold down the rear panel of the output file and find the set of 3 keyed connectors and connect them as shown below:



| | | |
|-------|-------|----------|
| 1-2PY | | 1-CMU-13 |
| 2-4PY | | 2-CMU-16 |
| 3-6PY | | 3-CMU-R |
| 4-8PY | | 4-CMU-U |

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-1307
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

Electrical Detail
New Installation - Sheet 2 of 3

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| | | |
|---|--|---|
| ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared for:  150 N. Greenfield Pkwy, Corner, NC 27529 | SR 1345 (Butler Bridge Road) at SR 1365 (N. Rugby Road) | SEAL  SEAL 031464 NATASHA R. SIMMONDS |
| | Division 14 Henderson Co. Hendersonville PLAN DATE: September 2018 REVIEWED BY: A.D. Klinksiek PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons | |

DocuSigned by:
Natasha R. Simmonds/26/2019
SIG. INVENTORY NO. 14-1307

FYA SIGNAL OUTPUT REMAPPING ASSIGNMENT PROGRAMMING DETAIL FOR LOADSWITCHES S1 & S3 (SIGNAL HEAD 11)

(program controller as shown below)

FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS), WITH CURSOR IN "OUTPUT ASSIGNMENT#" POSITION, ENTER "14"

DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'VEHICLE OVERLAP' AS SHOWN BELOW.

```

PAGE:1 C1 PIN:16 VEHICLE PHASE
OUTPUT ASSIGNMENT #.....14
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```

Overlap A Red

THE OUTPUT IS SET AS A VEHICLE PHASE BY DEFAULT. THIS "Y" WILL REMAIN UNTIL THE OUTPUT IS CHANGED. ENTER A "Y" FOR VEHICLE OVERLAP.

```

PAGE:1 C1 PIN:16 VEHICLE PHASE
SELECT VEHICLE OVERLAP (A=1,P=16)...1
SELECT COLOR(0=RED,1=YEL,2=GRN)...0

```

WHEN A 'Y' IS ENTERED FOR 'VEHICLE OVERLAP' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN. PRESS THE 'ENT' KEY AFTER ENTERING DATA, THEN 'ESC'.

```

PAGE:1 C1 PIN:16 VEHICLE OVERLAP
OUTPUT ASSIGNMENT #.....14
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```

PRESS "+" KEY FOR OUTPUT 15

```

PAGE:1 C1 PIN:17 VEHICLE PHASE
OUTPUT ASSIGNMENT #.....15
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```

Overlap A Yellow

THE OUTPUT IS SET AS A VEHICLE PHASE BY DEFAULT. THIS "Y" WILL REMAIN UNTIL THE OUTPUT IS CHANGED. ENTER A "Y" FOR VEHICLE OVERLAP.

```

PAGE:1 C1 PIN:17 VEHICLE PHASE
SELECT VEHICLE OVERLAP (A=1,P=16)...1
SELECT COLOR(0=RED,1=YEL,2=GRN)...1

```

WHEN A 'Y' IS ENTERED FOR 'VEHICLE OVERLAP' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN. PRESS THE 'ENT' KEY AFTER ENTERING DATA, THEN 'ESC'.

DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'VEHICLE OVERLAP' AS SHOWN BELOW.

```

PAGE:1 C1 PIN:17 VEHICLE OVERLAP
OUTPUT ASSIGNMENT #.....15
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```

PRESS "+" KEY FOR OUTPUT 16

```

PAGE:1 C1 PIN:18 VEHICLE PHASE
OUTPUT ASSIGNMENT #.....16
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```

Overlap A Green

THE OUTPUT IS SET AS A VEHICLE PHASE BY DEFAULT. THIS "Y" WILL REMAIN UNTIL THE OUTPUT IS CHANGED. ENTER A "Y" FOR VEHICLE OVERLAP.

```

PAGE:1 C1 PIN:18 VEHICLE PHASE
SELECT VEHICLE OVERLAP (A=1,P=16)...1
SELECT COLOR(0=RED,1=YEL,2=GRN)...2

```

WHEN A 'Y' IS ENTERED FOR 'VEHICLE OVERLAP' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN. PRESS THE 'ENT' KEY AFTER ENTERING DATA, THEN 'ESC'.

DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'VEHICLE OVERLAP' AS SHOWN BELOW.

```

PAGE:1 C1 PIN:18 VEHICLE OVERLAP
OUTPUT ASSIGNMENT #.....16
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```

PRESS "+" UNTIL OUTPUT 33 IS REACHED.

```

PAGE:1 C1 PIN:35 NOT ENABLED
OUTPUT ASSIGNMENT #.....33
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```

Phase 1 Green

THE OUTPUT IS SET AS "NOT ENABLED" BY DEFAULT. THIS "Y" WILL REMAIN UNTIL THE OUTPUT IS CHANGED. ENTER A "Y" FOR VEHICLE PHASE.

```

PAGE:1 C1 PIN:35 NOT ENABLED
SELECT VEHICLE PHASE (1-16)...1
SELECT COLOR(0=RED,1=YEL,2=GRN)...2

```

WHEN A 'Y' IS ENTERED FOR 'VEHICLE PHASE' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN. PRESS THE 'ENT' KEY AFTER ENTERING DATA, THEN 'ESC'.

DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'VEHICLE PHASE' AS SHOWN BELOW.

```

PAGE:1 C1 PIN:35 VEHICLE PHASE
OUTPUT ASSIGNMENT #.....33
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH)...0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....Y
PEDESTRIAN PHASE.....Y
VEHICLE OVERLAP.....Y
PEDESTRIAN OVERLAP.....Y
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....

```


OUTPUT PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-1307
DESIGNED: September 2018
SEALED: 4/26/2019
REVISED: N/A

Electrical Detail
New Installation - Sheet 3 of 3

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

ELECTRICAL AND PROGRAMMING DETAILS FOR:




Prepared for:

HNTB
750 N. Greenfield Pkwy, Corner, NC 27529

| SR 1345 (Butler Bridge Road) | | at | | SR 1365 (N. Rugby Road) | |
|------------------------------|-----------------------------|-----------------------------|---------------------------|-------------------------|--|
| Division 14 | | Henderson Co. | | Hendersonville | |
| PLAN DATE: September 2018 | REVIEWED BY: A.D. Klinksiek | PREPARED BY: A.H. Thornburg | REVIEWED BY: N.R. Simmons | | |
| REVISIONS | INIT. | DATE | | | |
| | | | | | |



SEAL



DocuSigned by:
Natasha R. Simmons 4/26/2019

SIG. INVENTORY NO. 14-1307

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997



DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

See Plate for Title

Prepared in the Offices of:

750 N. Greenfield Parkway
Garner, NC 27529

SEAL

DocuSigned by:
Mohd Aslami
10/11/2017
DATE

11-2017-2017_08-56
11-2018 314 Drawings/Plate Sheets/2018_Plate Sheet -dgn
r.wrough