```
Input  File: R:\Roadway\Xsc\XS Earthwork Files\EW_Y4.inp
Output File: EW_Y4.log
 1     1     1
 1     2     2    earthwork
 1     3     3 /*   TOLERANCE = 0.01    */
 1     4     4
 1     5     5    xs dgn = R:\ROADWAY\XSC\R3421B_RDY_xsc_Y4.DGN
 1     6     6
 1     7     7       proposed finish grade
 1     8     8       soil type = unclassified
 1     9     9       type = line
 1    10    10       fill mult factor = 1.00
 1    11    11       lvname = Old_Level_2, Old_Level_3, Prop XS Finish Grade
Earthwork, Prop XS Finish Grade Pavement
 1    12    12
 1    13    13       existing ground line
 1    14    14       soil type = unclassified
 1    15    15       type = line, line_string
 1    16    16       lvname = Old_Level_60
 1    17    17       lvname = Exist XS Ground Line
 1    18    18
 1    19    19       write earthwork shapes
 1    20    20         plot parameters
 1    21    21            lvname = prop xs earthwork shape
 1    22    22            co = 1
 1    23    23            stratify shape color

 1    35    35       process earthwork for baseline = Y4
 1    36    36       job number = RDY
 1    37    37       beg station = 23+50 R 1
 1    38    38       end station = 23+50 R 1
 0     0    39 END_OF_FILE

COMPUTING EARTHWORKS FOR BASELINE = Y4
COMPUTING EARTHWORKS FOR JOB = RDY
FORMING LIST OF XSCELLS
BEGINNING EARTHWORKS COMPUTATION
```


Station	Material Name	End Areas (sq. ft.)	Unadjusted Volumes (cu. yd.)	Adjusted Volumes (cu. yd.)	Mult Factor	Mass Ordinate
23+13.60	UNCLASSIFIED					
	Common Exc	244.03	0	0	1.00	
	Subgrade Exc	0.00	0	0	1.00	
	Subsoil Exc	0.00	0	0	1.00	
	Fill	0.00	0	0	1.00	0

ear_Y4_23+13.60-23+89.98

23+50.00 UNCLASSIFIED					
Common Exc	244.03	329	329	1.00	
Subgrade Exc	0.00	0	0	1.00	
Subsoil Exc	0.00	0	0	1.00	
Fill	0.00	0	0	1.00	0
23+89.98 UNCLASSIFIED					
Common Exc	244.03	352	352	1.00	
Subgrade Exc	0.00	0	0	1.00	
Subsoil Exc	0.00	0	0	1.00	
Fill	0.00	0	0	1.00	0

G R A N D S U M M A R Y T O T A L S

Material Name	Unadjusted Volumes (cu. yd.)	Adjusted Volumes (cu. yd.)	Mult Factor
UNCLASSIFIED			
Common Exc	681	681	1.00
Subgrade Exc	0	0	1.00
Subsoil Exc	0	0	1.00
Fill	0	0	1.00