

PROJECT SPECIAL PROVISIONS

Utilities by Others

**General:**

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Blue Ridge Mountain EMC – Distribution Power
- B) Frontier – Telephone
- C) Windstream– CATV
- D) Balsam West –Communications

The utility conflicts will be adjusted by the date noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be performed by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the 2018 Standard Specifications for Roads and Structures.

Utilities Requiring Adjustments:

- A) Blue Ridge Mountain EMC – Distribution Power
 Mr. Josh Swanson
 706.379.3121
josh.swanson@brmemc.com

1. See "Utilities By Others Plans" for utility conflicts
2. Blue Ridge Energy EMC will perform the tree clearing needed for the relocation work but will require any dwellings to be removed by NCDOT or the contractor.
3. Blue Ridge Energy EMC will complete their relocation from L line station 177+00 to L line station 190+00 by December 1st 2019. Blue Ridge Energy
4. Blue Ridge Energy EMC will require the contractor to clear the right of way and PUE areas from L line station 38+00 to end of the project.
5. Blue Ridge Energy EMC will complete their relocation work from L line station 140+00 to 152+00 Left after contractor has completed slope cut.
6. Blue Ridge Energy EMC will complete their relocation work from L line station 127+00 to 132+50 Right after contractor has completed fill slope.
7. Blue Ridge Energy will require NCDOT to relocate the existing roadside billboards at the following locations before Blue Ridge Energy can complete their relocation:

- 88+00 Left
- 82+00 Right
- 78+95 Right
- 73+10 Right
- 70+00 Right
- 66+25 Right
- 63+40 Right

8. Blue Ridge Energy will complete relocation efforts by January 1st 2021

B) Balsam West FiberNET – Communications

Danny Haines

828.399.9760

dhaines@balsamwest.net

1. See “Utilities By Others Plans” for utility conflict
2. Balsam West FiberNET will complete their relocation from L line station 177+00 to L line station 190+00 by January 15th, 2020.
3. Balsam West FiberNET will be attaching to Blue Ridge Energy poles and complete their relocation from beginning of project to L line station # 190+00 by March 1st, 2021.
4. Balsam West FiberNET will leave existing line in place and relocate vertically as needed on L line from station 190+00 to end of project.
5. Contractor should contact and Coordinate with Balsam West FiberNET before excavating begins.
6. Balsam West FiberNET will require any dwellings to be removed by NCDOT or the contractor prior to relocation being started.
7. Balsam West FiberNET will complete relocation efforts by May 1st, 2021

C) Windstream– CATV

Allen Davenport

706.970.9417

william.a.davenport@windstream.com

1. See “Utilities By Others Plans” for utility conflict
2. Windstream will complete their relocation from L line station 177+00 to L line station 190+00 by February 15th, 2020.
3. Windstream will be attaching to the Blue Ridge Energy poles and complete their relocation from beginning of project to L line station 220+00 by July 1st, 2021.
4. Windstream will require any dwellings to be removed by NCDOT or the contractor prior to relocation being started.
5. Contractor should contact and Coordinate with Balsam West FiberNET before excavating begins.
6. Windstream will complete relocation efforts by August 1st, 2021

D) Frontier– Phone

Jerry Fisher

Jerry.d.fisher@ftr.com

1. See “Utilities By Others Plans” for utility conflict

2. Frontier will complete their relocation from L line station 177+00 to L line station 190+00 by March 15th, 2020.
3. Frontier will be attaching to the Blue Ridge Energy poles and complete their relocation from beginning of project to L line station 220+00 by October 1st, 2021.
4. Frontier will require any dwellings to be removed by NCDOT or the contractor prior to relocation being started.
5. Contractor should contact and Coordinate with Frontier before excavating begins.
6. Windstream will complete relocation efforts by November 1st, 2021