

### ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT. PHASING DURING FREE RUN - PROGRAM CHANGES (SHOWN BELOW) IN A TIME BASED ACTION PLAN. SCHEDULE A DAY PLAN THAT INCLUDES THE ACTION PLAN PROGRAMMED TO SELECT VEH DET PLAN 2 AND ENABLE SF BITS 1 and 5.

TO RUN ALT. PHASING DURING COORDINATION - SELECT THE TIME BASED ACTION PLAN THAT IS PROGRAMMED TO SELECT VEH DET PLAN 2 AND ENABLE SF BITS 1 and 5.

<u>PHASING</u>	<u>VEH DET PLAN</u>	<u>SF BITS ENABLED</u>
ACTIONS REQUIRED TO RUN <u>DEFAULT PHASING</u>	1	NONE
ACTIONS REQUIRED TO RUN <u>ALTERNATE PHASING</u>	2	1, 5

**IMPORTANT:** IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX. FREE RUN EVENT SHOULD END BEFORE COORDINATION PLAN EVENT STARTS AND VICE-VERSA).

ALTERNATE PHASING CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN SF BITS 1 AND 5 AND VEH DET PLAN 2 ACTIVATE TO CALL THE "ALTERNATE PHASING":

**SF BITS 1,5:** Modifies overlap parent phases for heads 11 and 51 to run protected turns only.

**VEH DET PLAN 2:** Disables phase 6 call on loop 1A and reduces delay time for phase 1 call on loop 1A to 0 seconds.

Disables phase 2 call on loop 5A and reduces delay time for phase 5 call on loop 5A to 0 seconds.

### ECONOLITE ASC/3-2070 ACTION PLAN PROGRAMMING DETAIL

1. From Main Menu select 5. TIME BASE
2. From TIME BASE Submenu select 2. ACTION PLAN

```

ACTION PLAN...[ 1]
PATTERN.....AUTO  SYS OVERRIDE.... NO
TIMING PLAN..... 0  SEQUENCE..... 0
VEH DETECTOR PLAN.. 2  DET LOG.....NONE
FLASH..... --  RED REST..... NO
VEH DET DIAG PLN... 0  PED DET DIAG PLN..0
DIMMING ENABLE.. NO  PRIORITY RETURN. NO
PED PR RETURN.. NO  QUEUE DELAY..... NO
PMT COND DELAY  NO

  PHASE  1  2  3  4  5  6  7  8  9  0  1  2  3  4  5  6
PED RCL  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
WALK 2   .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
VEX 2    .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
VEH RCL  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
MAX RCL  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
MAX 2    .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
  PHASE  1  2  3  4  5  6  7  8  9  0  1  2  3  4  5  6
MAX 3    .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
CS INH   .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
OMIT     .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
SPC FCT  X  .  .  .  X  .  .  .  (1-8)
AUX FCT  .  .  .  (1-3)

  1  2  3  4  5  6  7  8  9  0  1  2  3  4  5
LP 1-15  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 16-30 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 31-45 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 46-60 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 61-75 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 76-90 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
LP 91-100 .  .  .  .  .  .  .  .  .  .  .  .  .  .  .  .
    
```

NOTICE  
SPC FCT →  
BITS

THIS ELECTRICAL DETAIL IS FOR  
THE SIGNAL DESIGN: 05-1726  
DESIGNED: March 2019  
SEALED: 7/24/2019  
REVISED: N/A

Electrical Detail - Final Design - Sheet 5 of 5		<b>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</b>								
<p style="font-size: small;">ELECTRICAL AND PROGRAMMING DETAILS FOR:</p> <p style="font-size: x-small;">Prepared In the Offices of:</p> <p style="font-size: x-small;">750 N. Greenfield Pkwy, Garner, NC 27529</p>	<p><b>SR 3015 (Airport Blvd.)</b> at <b>Factory Shops Road/ Aerial Center Parkway</b></p> <p style="font-size: x-small;">Division 5    Wake County    Morrisville</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: x-small;">PLAN DATE:</td> <td style="font-size: x-small;">May 2019</td> <td style="font-size: x-small;">REVIEWED BY:</td> <td style="font-size: x-small;">S. Armstrong</td> </tr> <tr> <td style="font-size: x-small;">PREPARED BY:</td> <td style="font-size: x-small;">S. Armstrong</td> <td style="font-size: x-small;">REVIEWED BY:</td> <td style="font-size: x-small;">Ryan W. Hough</td> </tr> </table>	PLAN DATE:	May 2019	REVIEWED BY:	S. Armstrong	PREPARED BY:	S. Armstrong	REVIEWED BY:	Ryan W. Hough	<p style="font-size: x-small;">SEAL</p> <p style="font-size: x-small;">SEAL 036833 ENGINEER RYAN W. HOUGH</p>
PLAN DATE:	May 2019	REVIEWED BY:	S. Armstrong							
PREPARED BY:	S. Armstrong	REVIEWED BY:	Ryan W. Hough							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="font-size: x-small;">REVISIONS</th> <th style="font-size: x-small;">INIT.</th> <th style="font-size: x-small;">DATE</th> </tr> <tr> <td style="height: 20px;"> </td> <td> </td> <td> </td> </tr> </table>		REVISIONS	INIT.	DATE				<p style="font-size: x-small;">DocuSigned by:</p> <p style="font-size: x-small;"><i>Ryan W. Hough</i>    8/1/2019</p> <p style="font-size: x-small;">(403320EFAA2685C3)    DATE</p> <p style="font-size: x-small;">SIG. INVENTORY NO. 05-1726</p>		
REVISIONS	INIT.	DATE								

25-JUL-2019 10:30  
051726.ssm.elec.wake.dgn  
sarmstr00g