

OASIS 2070 LOOP & DETECTOR INSTALLATION CHART												
INDUCTIVE LOOPS				DETECTOR PROGRAMMING								
LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	PHASE	CALLING	EXTENSION	FULL TIME DELAY	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD
2A	6X6	70	3	Y	2	Y	Y	-	-	_	I	Y
2B	6X6	70	3	Y	2	Y	Y	I	-	-	-	Y
2C	6X6	70	3	Y	2	Y	Y	-	-	-	-	Y
7A	6X40	0	2-4-2	Y	7	Y	Y	-	-	* 15	-	Y
7B	6X40	0	2-4-2	Y	7	Y	Y	-	-	10	-	Y

PROJECT REFERENCE NO.	SHEET NO.
R - 2303E	Sig. 4.0

2 Phase Fully Actuated NC 24 (Sunset Avenue) CLS

<u>NOTES</u>

	NOTES					
1.	Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.					
2.	Do not program signal for late night flashing operation unless otherwise directed by					
3.	the Engineer. Set all detector units to					
4.	presence mode. Locate new cabinet so as not to obstruct sight distance of					
5.	vehicles turning right on red. Heads C1, C2, C3 are continuously					
	green.					
6.	Omit "WALK" and flashing "DON'T WALK" with no pedestrian calls.					
7.	Program pedestrian heads to countdown the flashing "Don't					
8.	Walk" time only. 8. The Division Traffic Engineer will determine the hours of use for each phasing					
9.	plan. 9. Maximum times shown in timing chart are for free-run operation only. Coordinated					
10.	signal system timing values supersede these values. Closed loop system data: Controller Asset # 0344.					
	LEGEND					
PROPOSE	ED EXISTING					
◯→	Traffic Signal Head					
	Modified Signal Head N/A					
	Sign — Pedestrian Signal Head With Push Button & Sign Signal Pole with Guy					
	Signal Pole with Sidewalk Guy					
\square	Controller & Cabinet					
	Junction Box					
	2-in Underground Conduit					
N/A	Right of Way ————-					
> N/A	 Directional Arrow Curb Ramp 					
$\langle A \rangle$	"U-TURN YIELD TO RIGHT TURN" Sign (R10-16)					
\bigcirc	Type II Signal Pedestal 🛛 🗢					
0	Metal Pole with Mastarm					
	Oversized Junction Box					

Installatior	1		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
repared in the Offices of: Nobility and	NC 24 (Suns	SEAL		
Contraction of the second seco	a Shields Division 3 Sampson Co	SEAL 030530		
Design Section	PLAN DATE: August 2018	REVIEWED BY: ZML	ENCINEER	
reenfield Pkwy.Garner.NC 27529	PREPARED BY: KGP, Jr.	REVIEWED BY:	HARY WINE	
SCALE 0 30 1 "= 30 '	revisions NAdd_new_signal_to_R-23031	- cisnit. DATE E	Docusigned by: 11111111111111111111111111111111111	