PROJECT NO.	SHEET NO.
2021CPT.03.02.10101, ETC.	13

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW EXCAVATION	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONST.	1297000000-E 2" MILLING	1297000000-E 1.5" MILLING	1297000000-E 1" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1519000000-E SURFACE COURSE, S9.5B SHORT OVERLAY	1520000000-E LEVELING COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1526000000-E SURFACE COURSE, S4.75A	1575000000-E ASPHALT BINDER FOR PLANT MIX	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #67 GRANITE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT
										MI	FT	CY	TON	SMI	SY	SY	SY	SY	TONS	TON	TON	TON	TON	TON	TON	SY	GAL
2021CPT.03.02.20101	Brunswick	11	SR 1485 (BELVILLE RD.)	FROM SR 1551 (MAIN ST.) TO END OF MAINTENANCE [MP 0.00 - MP 0.07]	7	2	2WU	NO	NO	0.07	40					1,690				143					10		
TOTAL FOR MAP NO. 11										**0.07**						**1,690**				**143**					**10**		
2021CPT.03.02.20101	Brunswick	12	SR 1551 (MAIN ST.)	FROM PAVEMENT JOINT EAST OF NC 133 TO END OF MAINTENANCE [MP 1.7 - MP 2.00]	7	2	2WU	NO	NO	0.3	22 - 44					8,286				720		20			50		
TOTAL FOR MAP NO. 12										**0.3**						**8,286**				**720**		**20**			**50**		
2021CPT.03.02.20101	Brunswick	13	SR 1701 (ZION CHURCH RD.)	FROM US 17 (OCEAN HWY. E) TO US 17 (OCEAN HWY. E) [MP 0.01 - MP 1.19]	5	2	2WU	NO	NO	1.18	20	173	30	1.77		14,526				1,207		15			82		
TOTAL FOR MAP NO. 13										**1.18**		**173**	**30**	**1.77**		**14,526**				**1,207**		**15**			**82**		
2021CPT.03.02.20101	Brunswick	14	SR 1406 (CHERRYTREE RD.)	FROM PAVEMENT JOINT 0.58 MILES S. OF JOHN DEERE GREEN TRAIL TO SR 1410 (GREEN HILL RD.) [MP 3.55 - MP 8.61	5, 8	2	2WU	NO	NO	6.05	20	200	180	12.10		3,168		670	690	6,188					446		
TOTAL FOR MAP NO. 14										**6.05**		**200**	**180**	**12.10**		**3,168**		**670**	**690**	**6,188**					**446**		
2021CPT.03.02.20101	Brunswick	15	SR 1455 (LINCOLN RD.)	FROM SR 1486 (POST OFFICE RD.) TO SR 1426 (MT. MISERY RD) [MP 0.00 - MP 1.16]	9	2	2WU	NO	NO	1.16	20	106	45	2.31				255	776	1,460					133	17,698	7,080
TOTAL FOR MAP NO. 15										**1.16**		**106**	**45**	**2.31**				**255**	**776**	**1,460**					**133**	**17,698**	**7,080**
2021CPT.03.02.20101	Brunswick	16	SR 1441 (LELAND SCHOOL RD.)	FROM SR 1426 (MT. MISERY RD.) TO SR 1472 (VILLAGE RD.) [MP 0.00 - MP 0.62]	8	2	2WU	NO	NO	0.62	18	60	62					680		544					36		
TOTAL FOR MAP NO. 16										**0.62**		**60**	**62**					**680**		**544**					**36**		
TOTAL FOR PROJ NO. 2021CPT.03.02.20101										**9.38**		**539**	**317**	**16.18**		**27,670**		**1,605**	**1,466**	**10,262**		**35**			**757**	**17,698**	**7,080**
																				10,262							
2021CPT.03.02.20102	Brunswick	17	SR 1419 (NORTHWEST RD.)	FROM SR 1426 (MT.MISERY RD.) TO COLUMBUS COUNTY LINE [MP 1.72 - MP 3.95]	NA	2	2WU	NO	NO	2.23	22										32				2		
TOTAL FOR MAP NO. 17										**2.23**											**32**				**2**		
2021CPT.03.02.20102	Brunswick	18	SR 1422 (BLUE BANKS LOOP RD.)	FROM SR 1426 (MT.MISERY RD.) TO GRIST CREEK WYND [MP 0.00 - MP 2.94]	NA	2	2WU	NO	NO	2.94	20																
TOTAL FOR MAP NO. 18										**2.94**																	
2021CPT.03.02.20102	Brunswick	19	SR 1429 (GREEN LOOP RD.)	FROM SR 1426 (MT.MISERY RD.) TO CUL-DE-SAC [MP 0.00 - MP 1.10]	10	2	2WU	NO	NO	1.1	20													819	57		
TOTAL FOR MAP NO. 19										**1.1**														**819**	**57**		
2021CPT.03.02.20102	Brunswick	20	SR 1420 (PORT ROYAL RD.)	FROM SR 1419 TO END OF MAINTENANCE [MP 0.00 - MP 0.42]	10	2	2WU	NO	NO	0.42	20													291	20		
TOTAL FOR MAP NO. 20										**0.42**														**291**	**20**		
2021CPT.03.02.20102	Brunswick	21	SR 1426 (MT. MISERY RD.)	FROM SR 1428 (DOGWOOD RD.) TO SR 1472 (VILLAGE RD.) [MP 3.80 - MP 8.89]	NA	2	2WU	NO	NO	5.09	21																
TOTAL FOR MAP NO. 21										**5.09**																	
TOTAL FOR PROJ NO. 2021CPT.03.02.20102										**11.78**											**32**			**1,110**	**79**		
																				32							
GRAND TOTAL										**39.3**		**1,106**	**619**	**42.45**	**261,312**	**145,121**	**513**	**3,293**	**1,466**	**20,567**	**32**	**35**	**29,228**	**1,110**	**3,281**	**17,698**	**7,080**
																				20,599							