PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.02.20921.1	35	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BORROW	SHOULDER GRADING	INC STONE BASE	ASB	1½" MILLING	3" MILLING	0" TO 1.5" MILLING	INC MILLING	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXI. PAVEMENT	2'-6" CURB & GUTTER	4" CONC SIDEWALK	RETROFIT EXI. CURB RAMP	CONC CURB RAMP	REM. AND REPL. CURB RAMPS	REM. CURB RAMPS	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOXES	SIGN EREC., RELOC, TYPE E (GRD MNTD)	TEMP. SILT FENCE	WATTLE	SEED & MULCHING	RESPONSE FOR EC	IND. LOOP SAWCUT	PED. CHANNELIZING DEVICES	PED. TRANSPORT. SERV.	AUD. WARN. DEVICE
									MI	FT	CY	SMI	TONS	TON	SY	SY	SY	SY	TONS	TONS	TON	TONS	LF	SY	EA	EA	EA	EA	EA	EA	EA	LF	LF	AC	EA	LF	LF	EA	EA
2021CPT.05.02.20921.1	Wake	1	SR 5878 - N SALEM ST	SR 1613 - DAVIS DR TO APEX PEAKWAY (OMIT NEWLY PAVED SECTION)	3	2	NO	NO	0.37	24-84	19	0.74	19	34	10,642			1,097	1,017		68	25			7		1		1	1		27	70	0.27		1,272			
		2	SR 5878 - OLD APEX RD/N SALEM ST	SR 1614 - SALEM CHURCH RD TO SR 1613 - DAVIS DR (OMIT NEWLY PAVED SECTION)	3	2	NO	NO	0.973	24-60	49	1.95	49	90	14,726			374	1,306		88	32										71	180	0.71	1	1,902			
		3	SR 1139 - DAISEY ST	SR 1011 - OLD US ONE HWY TO CHATHAM CO	2	2	NO	NO	0.21	18	15	0.41	10	9	246			164	193		13	50									22	60	0.22					
		4	SR 1197 - CHAPEL RIDGE RD	PVMT JT 0.04 MI FROM SR 1160 - OLIVE CHAPEL RD TO CUL-DE-SAC	1	2	NO	NO	0.43	20	43	0.41	10					167	399		27	30									63	160	0.63					
		5	SR 1208 - CLARK FARM RD	SR 1197 - CHAPEL RIDGE RD TO CUL-DE-SAC	1	2	NO	NO	0.1	18	10	0.20	5						96		6	5									15	40	0.15					
		6	SR 1613 - DAVIS DR	US 64 TO SR 3111 - FARMPOND RD	3	2	NO	NO	1.1	22-80	44	2.20	55	122	18,163			1,491	1,702		114	175					1				64	160	0.64	1	1,164			
		7	SR 1615 - BEAVER DAM RD	SR 1600 - GREEN LEVEL CHURCH RD TO SR 1605 - GREEN LEVEL RD W	2	2	NO	NO	0.24	20	7	0.48	12	31				625	245		16	90									10	30	0.10					
		8	SR 1615 - HIGH HOUSE RD	SR 1613 - DAVIS DR TO MAURY ODELL PL (SKIP INTERSECTION AT CARY PARKWAY)	4	4	NO	NO	1.49	50-84					52,816			426		4,693	282	70			12		2		1	8						1,765	160	20	12
		9	SR 1615 - HIGH HOUSE RD	MAURY ODELL PL TO RR JOINT @ OLD APEX RD	5	5	NO	NO	1.48	60						54,600		2,564		9,546	574	12	14	5	48		14	1	1	3						1,692			
		10	SR 1639 - KIT CREEK RD	NC 55 TO PVT JT 1600' WEST OF SR 1613 - DAVIS DR	1	2	NO	NO	1.273	26-62	95	1.91	48		346		285	6,211	2,659		178	300			8	1						139	350	1.39	1	806			
		11	SR 1652 - HARRISON AVE	START OF MAINTENANCE TO NC 54 - NW MAYNARD RD	4	5	NO	NO	2.513	62-80		0.24	9	22	106,182			5,275		9,596	576	150			71	2	10		2	2	1					6,192			
		12	SR 3037 - WADE DR	NC 55 HWY TO END MAINT	3	2	NO	NO	0.36	20	36	0.72	18		4,224				368		25	10									52	140	0.52					
		13	SR 3040 - TRELAWNEY LN	SR 1608 - ROBERTS RD TO SR 1601 - JENKS RD	1	2	NO	NO	0.5	20	50	1.00	25					334	426		29	40									73	190	0.73	1				
		14	SR 3093 - DEVELOPMENT DR	SR 1613 - DAVIS DR (PVT JT) TO SR 2153 - LOUIS STEPHENS DR (NEAREST PVT JT)	3	2	NO	NO	0.6	24-54	60	1.20	30		8,448				736		49	152									87	220	0.87	1				
GRAND TOTAL FOR PROJ NO. 2021CPT.05.02.20921.1									**11.639**		**428**	**11.46**	**290**	**308**	**215,793**	**54,600**	**285**	**18,728**	**9,147**	**23,835**	**2,045**	**1,141**	**14**	**5**	**146**	**3**	**28**	**1**	**5**	**14**	**1**	**623**	**1,600**	**6.23**	**5**	**14,793**	**160**	**20**	**12**