PROJECT NO.	SHEET NO.
2021CPT.03.04.10311, ETC.	11

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW EXCAVATION	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONST.	1297000000-E 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1519000000-E SURFACE COURSE, S9.5B (SHORT OVERLAY)	1520000000-E LEVELING COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1526000000-E SURFACE COURSE, S4.75A	1575000000-E ASPHALT BINDER FOR PLANT MIX	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE (GRANITE)	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1880000000-E PATCHING EXISTING PAVEMENT (FULL DEPTH)	1880000000-E PATCHING EXISTING PAVEMENT (MILL)
										MI	FT	CY	TON	SMI	SY	SY	TON	TONS	TON	TON	TON	TON	SY	GAL	TON	TON
2021CPT.03.04.10311	Duplin	1	S. NC 41 HWY (W. MAIN ST.)	(WALLACE) FROM SR 1154 (HC POWERS RD.) TO SR 1165 (N. ROCKFISH ST.) [MP 8.92 - 10.40]	1	4	MU	NO	NO	1.48	45.5				41,958				36	3,633		220			95	
TOTAL FOR MAP NO. 1										**1.48**					**41,958**				**36**	**3,633**		**220**			**95**	
TOTAL FOR PROJ NO. 2021CPT.03.04.10311										**1.48**					**41,958**				**36**	**3,633**		**220**			**95**	
2021CPT.03.04.20311	Duplin	2	SR 1173 (RALEIGH RD. / SOUTHERLAND ST.)	FROM SR 1163 TO NC 41 [MP 0.00 - MP 1.27]	2,3	2	2WU	NO	NO	1.27	20 - 45	40	25	0.90	22,600		2,186					146			75	
TOTAL FOR MAP NO. 2										**1.27**		**40**	**25**	**0.90**	**22,600**		**2,186**					**146**			**75**	
2021CPT.03.04.20311	Duplin	10	SR 1953 (PASTURE BRANCH RD.)	FROM SR 1947 TO NC 50 [MP 0.37 - MP 5.63]	4,5	2	2WU	NO	NO	5.26	19	165	200	10.52		100	5,356					359	12,262	4,905	25	25
TOTAL FOR MAP NO. 10										**5.26**		**165**	**200**	**10.52**		**100**	**5,356**					**359**	**12,262**	**4,905**	**25**	**25**
2021CPT.03.04.20311	Duplin	12	SR 1101 (CORNWALLIS RD.)	FROM NC 903 TO SR 1102 [MP 0.00 - MP 1.81]	4	2	2WU	NO	NO	1.81	23	57	50	1.81		511	2,026		30			138			25	25
TOTAL FOR MAP NO. 12										**1.81**		**57**	**50**	**1.81**		**511**	**2,026**		**30**			**138**			**25**	**25**
2021CPT.03.04.20311	Duplin	13	SR 1109 (BLANCHARD RD.)	FROM SR 1108 TO SAMPSON CO LINE [MP 0.00 - MP 0.28]	4	2	2WU	NO	NO	0.28	20	9	50	0.56		112	273		20			20				
TOTAL FOR MAP NO. 13										**0.28**		**9**	**50**	**0.56**		**112**	**273**		**20**			**20**				
TOTAL FOR PROJ NO. 2021CPT.03.04.20311										**8.62**		**271**	**325**	**13.79**	**22,600**	**723**	**9,841**		**50**			**663**	**12,262**	**4,905**	**125**	**50**
																	9,841									
2021CPT.03.04.20312	Duplin	19	SR 1983 (FRIENDLY DR.)	FROM US 117 TO END OF MAINTENANCE [MP 0.00 - MP 0.34]	8	2	2WU	NO	NO	0.34	19										216	15				
TOTAL FOR MAP NO. 19										**0.34**											**216**	**15**				
2021CPT.03.04.20312	Duplin	20	SR 1182 (EUREKA / SUNSET RD.)	FROM NC 41 TO NC 41 [MP 0.00 - MP 0.33]	8	2	2WU	NO	NO	0.33	18										198	14				
TOTAL FOR MAP NO. 20										**0.33**											**198**	**14**				
2021CPT.03.04.20312	Duplin	21	SR 1992 (MCMILLAN AVE.)	FROM SR 1983 TO SR 1983 [MP 0.00 - MP 0.37]	8	2	2WU	NO	NO	0.37	18										217	15				
TOTAL FOR MAP NO. 21										**0.37**											**217**	**15**				
2021CPT.03.04.20312	Duplin	22	SR 1190 (NEWTOWN RD).	FROM SR 1172 TO END OF MAINTENANCE [MP 0.00 - MP 0.33]	8	2	2WU	NO	NO	0.33	18										193	14				
TOTAL FOR MAP NO. 22										**0.33**											**193**	**14**				
2021CPT.03.04.20312	Duplin	23	SR 2000 (DOBBINS ST.)	FROM SR 1163 TO END OF MAINTENANCE [MP 0.00 - MP 0.26]	8	2	2WU	NO	NO	0.26	20										163	11				
TOTAL FOR MAP NO. 23										**0.26**											**163**	**11**				
2021CPT.03.04.20312	Duplin	24	SR 2004 (LINCOLN ST.)	FROM SR 2000 TO CUL-DE-SAC [MP 0.00 - MP 0.16]	8	2	2WU	NO	NO	0.16	21										110	8				
TOTAL FOR MAP NO. 24										**0.16**											**110**	**8**				
2021CPT.03.04.20312	Duplin	25	SR 1186 (MOORETOWN RD.)	FROM SR 1149 TO END OF MAINTENANCE [MP 0.00 - MP 0.20]	8	2	2WU	NO	NO	0.2	18										117	8				
TOTAL FOR MAP NO. 25										**0.2**											**117**	**8**				
2021CPT.03.04.20312	Duplin	26	SR 1184 (HORNE RD.)	FROM SR 1149 TO SR 1185 [MP 0.00 - MP 0.06]	8	2	2WU	NO	NO	0.06	18										35	2				
TOTAL FOR MAP NO. 26										**0.06**											**35**	**2**				
2021CPT.03.04.20312	Duplin	27	SR 1185 (UNDERWOOD RD.)	FROM SRT 1184 TO END OF MANTENANCE [MP 0.00 - MP 0.04]	8	2	2WU	NO	NO	0.04	18										23	2				
TOTAL FOR MAP NO. 27										**0.04**											**23**	**2**				
2021CPT.03.04.20312	Duplin	34	SR 1155 (SHAW RD.)	FROM SR 1156 TO PENDER COUNTY LINE [MP 0.00 - MP 1.24]	N/A	2	2WU	NO	NO	1.24	20							230				15				
TOTAL FOR MAP NO. 34										**1.24**								**230**				**15**				
2021CPT.03.04.20312	Duplin	35	SR 1128 (POWELL PAGE RD.)	FROM SAMPSON COUNTY LINE TO NC 41 [MP 0.00 - MP 4.29]	N/A	2	2WU	NO	NO	4.29	20							197				13				
TOTAL FOR MAP NO. 35										**4.29**								**197**				**13**				
2021CPT.03.04.20312	Duplin	36	SR 1126 (HUFFMAN/WILLIAMS RD.)	FROM SAMPSON COUNTY LINE TO SR 1102 [MP 0.00 - MP 3.86]	N/A	2	2WU	NO	NO	3.86	20							221				15				
TOTAL FOR MAP NO. 36										**3.86**								**221**				**15**				
2021CPT.03.04.20312	Duplin	38	SR 1192 (CARROLLS RD.)	FROM SAMPSON COUNTY LINE TO SAMPSON COUNTY LINE [MP 0.00 - MP 3.15]	N/A	2	2WU	NO	NO	3.15	20							247				17				
TOTAL FOR MAP NO. 38										**3.15**								**247**				**17**				
2021CPT.03.04.20312	Duplin	43	SR 1119 (GOLD POND RD.)	FROM NC 903 TO SR 1117 [MP 0.00 - MP 0.51]	N/A	2	2WU	NO	NO	0.51	20							242				16				
TOTAL FOR MAP NO. 43										**0.51**								**242**				**16**				
TOTAL FOR PROJ NO. 2021CPT.03.04.20312										**15.14**								**1,137**			**1,272**	**165**				
																	1,137									
GRAND TOTAL										**25.24**		**271**	**325**	**13.79**	**64,558**	**723**	**9,841**	**1,137**	**86**	**3,633**	**1,272**	**1,048**	**12,262**	**4,905**	**220**	**50**
																	10,978									