COMPUTED BY: ABJ DATE: 01/07/20
CHECKED BY: JPM DATE: 01/08/20

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
BR-0118	X-1A

PREPARED IN THE OFFICE OF: KSINGER CAMPO & ASSOCIATES
NC FIRM LICENSE No: C-1506
301 Fayetteville St., Suite 1500
Raleigh, NC 27601
(919)882-7839

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

CROSS-SECTION SUMMARY

Station -L-	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)	Station TL-	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
10+35.00	0		0	10+35.00	0		0
10+50.00	0		3	10+50.00	0		3
11+00.00	0		31	11+00.00	0		22
11+50.00	2		29	11+50.00	0		37
12+00.00	2		24	12+00.00	0		67
12+50.00	0		71	12+50.00	0		126
13+00.00	0		142	13+00.00	0		282
13+50.00	28		122	13+50.00	0		397
13+56.24	7		5	13+68.59	0		63
14+28.49	0		0	14+28.59	0		0
14+50.00	21		24	14+50.00	0		77
15+00.00	31		112	15+00.00	0		253
15+50.00	9		107	15+50.00	0		203
16+00.00	0		47	16+00.00	0		111
16+50.00	2		6	16+50.00	0		42
17+00.00	5		5	17+00.00	0		7
17+50.00	11		3	17+09.22	0		1
18+00.00	25		1				
18+50.00	47		0				
19+00.00	43		0				
19+12.43	5		0				

Note: Approximate quantities only. Unclassified Excavation, Borrow, Fine Grading, Clearing and Grubbing, will be paid for at the contract lump sum price for "Grading."

Note: Embankment column does not include backfill for undercut.

12/06/07

10-MAR-2020 10:48
BR-0118_Rdy_sum_xsc.dgn
dgbone