PROJECT NO.	SHEET NO.	TOTAL NO.
1CPT.03.06.10711, 2021CPT.03.06.20 2021CPT.03.06.10712, ETC.	10	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL	4510000000-N LAW ENFORCEMENT	4685000000-E 4" X 90 M WHITE THERMO	4685000000-E 4" X 90 M YELLOW THERMO	4695000000-E 8" X 90 M WHITE THERMO	4700000000-E 12" X 90 M WHITE THERMO	4700000000-E 12" X 90 M YELLOW THERMO	4720000000-E THERMO MSG SCHOOL 90 M	4725000000-E THERMO STR ARROW 90 M	4725000000-E THERMO LT ARROW 90 M	4725000000-E THERMO STR & LT ARROW 90 M	4725000000-E THERMO RT ARROW 90 M	4725000000-E THERMO U-TURN ARROW 90 M	4725000000-E THERMO STR & RT ARROW 90 M	4725000000-E 24" YIELD LINE TRIANGLE (90 MIL)	4810000000-E 4" WHITE PAINT	4810000000-E 4" YELLOW PAINT	4891000000-E 24" X 90 M WHITE THERMO	4900000000-N YELLOW & YELLOW MARKERS	4905000000-N SNOW PLOWABLE MARKERS (C/R)	4905000000-N SNOW PLOWABLE MARKERS (Y/Y)
								MI	FT	SF	LS	HR	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA	EA
2021CPT.03.06.10711	Pender	1	US 17 NORTH	FROM 0.1 MILES NORTH OF SR 1563 (SLOOP POINT LOOP RD.) TO 0.13 MILES SOUTH OF NC 210 [MP 9.61 - MP 13.48]	1	2	MD	3.87	41	448		125	31,425	20,600	340	20			44	24	4	14	3	2	12				30	473	
TOTAL FOR MAP NO. 1								**3.87**		**448**		**125**	**31,425**	**20,600**	**340**	**20**			**44**	**24**	**4**	**14**	**3**	**2**	**12**				**30**	**473**	
2021CPT.03.06.10711	Pender	2	US 17 SOUTH	FROM .13 MILES SOUTH OF NC 210 TO 0.10 MILES NORTH OF SR 1563 (SLOOP POINT LOOP RD.) [MP 2.48 - MP 6.17]	1	2	2WD	3.69	33	416	*	125	29,645	20,040	485	20			45	33	4	9	3		12				16	473	
TOTAL FOR MAP NO. 2								**3.69**		**416**		**125**	**29,645**	**20,040**	**485**	**20**			**45**	**33**	**4**	**9**	**3**		**12**				**16**	**473**	
2021CPT.03.06.10711	Pender	3	NC 210	FROM US 117 TO NC 133 [MP 28.83 - MP 33.75]	2	2	2WU	4.92	23	560			59,555	23,855			250	12	4	10		5		3				92		41	382
TOTAL FOR MAP NO. 3								**4.92**		**560**			**59,555**	**23,855**			**250**	**12**	**4**	**10**		**5**		**3**				**92**		**41**	**382**
TOTAL FOR PROJ NO. 2021CPT.03.06.10711								**12.48**		**1,424**	*	**250**	**120,625**	**64,495**	**825**	**40**	**250**	**12**	**93**	**67**	**8**	**28**	**6**	**5**	**24**			**92**	**46**	**987**	**382**
													185,120			**290**			**231**											**1,369**	
2021CPT.03.06.20711	Pender	10	SR 1306 (POWERS ROAD/OLD MILL ROAD)	FROM 0.35 NORTH OF SR 1307 (WALLACE AIRPORT ROAD) TO 0.27 SOUTH OF SR 1307 (WALLACE AIRPORT ROAD) [MP 1.60 - MP 2.27]	3	2	2WU	0.67	18	80																14,418	8,844		43		
TOTAL FOR MAP NO. 10								**0.67**		**80**	*															**14,418**	**8,844**		**43**		
2021CPT.03.06.20711	Pender	11	SR 1307 (WALLACE AIRPORT ROAD)	FROM 0.48 SOUTH OF SR 1306 (POWERS RD./OLD MILL RD.) TO SR 1350 (HENDERSON FIELD ROAD) [MP 0.67 - MP 1.70]	3	2	2WU	1.03	20	128																21,520	13,200		66		
TOTAL FOR MAP NO. 11								**1.03**		**128**																**21,520**	**13,200**		**66**		
TOTAL FOR PROJ NO. 2021CPT.03.06.20711								**1.7**		**208**	*															**35,938**	**22,044**		**109**		
																										57,982					
2021CPT.03.06.10712	Pender	14	NC 53	FROM ONSLOW COUNTY LINETO 3 MILES SOUTH OF NC 50 AT SHELTER CREEK QUARRY [MP 0.00 - MP 6.40]	N/A	2	2WU	6.4	24	24																					
TOTAL FOR MAP NO. 14								**6.4**		**24**																					
2021CPT.03.06.10712	Pender	15	NC 53	FROM 3 MILES SOUTH OF NC 50 AT SHELTER CREEK QUARRY TO SR 1318 (CROOMSBRIDGE RD.) [MP 6.40 - MP 11.27]	N/A	2	2WU	4.87	24		*																				
TOTAL FOR MAP NO. 15								**4.87**																							
2021CPT.03.06.10712	Pender	16	NC 53	FROM SR 1318 (CROOMSBRIDGE RD.) TO I-40 [MP 11.27 - MP 16.20]	N/A	2	2WU	4.93	24	24																					
TOTAL FOR MAP NO. 16								**4.93**		**24**																					
TOTAL FOR PROJ NO. 2021CPT.03.06.10712								**16.2**		**48**	*																				
2021CPT.03.06.20712	Pender	18	SR 1759 MIDDLE POINT RD.	FROM SR 1563 (SLOOP POINT LOOP RD.) TO SR 1762 (W. WINDWARD LANDING PL.) [MP 0.00 - MP 0.46]	N/A	2	2WU	0.46	22		*																				
TOTAL FOR MAP NO. 18								**0.46**			*																				
TOTAL FOR PROJ NO. 2021CPT.03.06.20712								**0.46**																							
GRAND TOTAL								**30.84**		**1,680**	**1**	**250**	**120,625**	**64,495**	**825**	**40**	**250**	**12**	**93**	**67**	**8**	**28**	**6**	**5**	**24**	**35,938**	**22,044**	**92**	**155**	**987**	**382**
													185,120			**290**			**231**							**57,982**				**1,369**	