

PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.08.20732.1	3	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	1520000000-E		1575000000-E	1704000000-E	1803500000-E	1820000000-E	1838000000-E	4413000000-E	4457000000-N	4890000000-E		
									LENGTH	WIDTH	LEVELING COURSE, TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, DOUBLE SEAL	ASPHALT SURFACE TREATMENT, FOG SEAL	EMULSION FOR ASPHALT SURFACE TREATMENT	WORK ZONE ADVANCE/G ENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES, 4", 50 MIL	
									MI	FT	TON	TON	TONS	SY	SY	GAL	SF	LS	LF	
2021CPT.05.08.20732.1	Person	1	SR 1314 - ZION LEVEL CHURCH RD/SKYLARK DR	CASWELL CO TO END MAINT	1	2	NO	NO	3.03	20	46	3	32	35,552	35,552	19,554	340	0.27	63,992	
		2	SR 1303 - LEE CHAMBERS RD	US 158 TO END MAINT	1	2	NO	NO	0.54	20	76	5	62	6,336	6,336	3,485	16	0.10	11,404	
		3	SR 1311 - WAGSTAFF RD	SR 1300 - LAMBRETH MEMRAL TO NC 57	1	2	NO	NO	1.56	20	72	5	59	18,304	18,304	10,067	175	0.20	32,948	
		4	SR 1331 - ALLENS CHAPEL CHURCH RD	BEG PVMT TO SR 1326 - WOODSDALE RD	1	2	NO	NO	0.20	20			1	2,347	2,347	1,291	23	0.10	4,224	
		5	SR 1102 - RALPH WINSTEAD RD	SR 1003 - CONCORD CHURCH RD. TO DEAD END	1	2	NO	NO	1.33	20	1			8	15,605	15,605	8,583	149	0.17	28,088
		6	SR 1332 - ROYSTER-CLAY RD	SR 1331 - ALLENS CHAPEL CHURCH RD TO CUL-DE-SAC	1	2	NO	NO	1.41	20				1	16,544	16,544	9,099	159	0.16	29,780
TOTAL FOR PROJ NO. 2021CPT.05.08.20732.1									8.07		195	13	163	94,688	94,688	52,078	862	1.00	170,436	
GRAND TOTAL									8.07		195	13	163	94,688	94,688	52,078	862	1.00	170,436	