

29-MAY-2019 11:58 R:\Structures\FinalPlans\403\_047\_15BPR40\_SMU\_SBR\_B1B\_S3-25\_100705.dgn amlee

+

+

SPAN	В
SPAN	А


AS-BUILT REPA	IR QL	JANTI	ΤΥ ΤΑ	BLE	
BENT 1 SPAN B FACE	QUANTITIES ESTIMATE ACTUAL				
SHOTCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.	
САР	2.1	1.1			
COLUMN	0.0	0.0			
CONCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.	
САР	0.0	0.0			
COLUMN	0.0	0.0			
EPOXY RESIN INJECTION		LIN.FT.	LIN.FT.		
САР		22.5			
COLUMN		0.0			

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MINIMUM OF 1"BEHIND REBAR AND MINIMUM 2"CLEARANCE TO SAWCUT. SEE ``TYPICAL CAP AND COLUMN REPAIR DETAILS'' SHEET.

## NOTES

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE GIVEN BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER SHALL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

CONCRETE REPAIRS MAYBE SUBSTITUTED IN LIEU OF SHOTCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.



SHOTCRETE REPAIR AREA



CONCRETE REPAIR AREA

 $\sim \sim$ 

ERI - EPOXY RESIN INJECTION

PROJECT N	NO. 15E	15BPR.40			
BUN	COMBE				
BRIDGE NO	<b>b.</b> 100	705			





PESSION SEAL 031021
DocuSigned by: MMWD MLue B04B5A4F2FAD484

5/29/2019	REVISIONS			SHEET NO.			
DOCUMENT NOT CONSIDERED	N0.	BY:	DATE:	NO.	BY:	DATE:	S3-25
FINAL UNLESS ALL	1			3			TOTAL SHEETS
SIGNATURES COMPLETED	2			4			36