DocuSign Envelope ID: 0FEC5775-FC6B-4F9A-9246-141C5BDAD0FF

PROJ. REFERENCE NO.	SHEET NO.
B-5671	PMP-1

APPROVED: _____

DATE: 2/4/2020

SEAL

KCI
http://www.kci.com
Engineers • Planners • Scientists • Construction Managers
4601 Six Forks Road, Landmark Center II, Suite 220
Raleigh, NC 27609-5310
Phone (919) 783-9214 • Fax (919) 783-9266

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PAVEMENT MARKING PLAN

EDGECOMBE COUNTY

LOCATION: BRIDGE NO. 87 OVER SWIFT CREEK ON NC 97

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	FINAL PAVEMENT MARKINGS
TA	WHITE EDGELINE	THERMOPLASTIC (4", 90 MILS)
TI	YELLOW DOUBLE CENTER	THERMOPLASTIC (4", 90 MILS)
TH	YELLOW SINGLE CENTER	THERMOPLASTIC (4", 90 MILS)
TF	10 FT. YELLOW SKIP	THERMOPLASTIC (4", 90 MILS)
CH	YELLOW SINGLE CENTER	COLD APPLIED (4", TYPE 2)
CF	10 FT. YELLOW SKIP	COLD APPLIED (4", TYPE 2)
CA	WHITE EDGELINE	COLD APPLIED (4", TYPE 2)

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" – PROJECT SERVICES UNIT – N.C. DEPARTMENT OF TRANSPORTATION – RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS – LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS – TWO-LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS – BRIDGES
1250.01	RAISED PAVEMENT MARKERS – INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS – PERMANENT AND TEMPORARY
1261.01	GUARDRAIL AND BARRIER DELINEATORS – INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS – TYPES AND MOUNTING
1262.01	GUARDRAIL AND DELINEATION

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
–L– NC 97	THERMOPLASTIC	RAISED
–BRIDGE–	COLD–APPLIED (TYPE 2)	RAISED

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

D) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.

E) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS ON THE BRIDGE DECK(s) PRIOR TO PLACING COLD APPLIED PAVEMENT MARKINGS.

F) TYPE III COLD APPLIED PLASTIC MAY BE USED IN LIEU OF TYPE II COLD APPLIED PLASTIC. IF TYPE III COLD APPLIED PLASTIC IS USED, IT SHALL BE PAID FOR USING THE TYPE II COLD APPLIED PLASTIC PAY ITEM.

INDEX

SHEET NO.	DESCRIPTION
PMP–1	PAVEMENT MARKING PLAN TITLE AND SCHEDULE SHEET
PMP–2	PAVEMENT MARKING DETAIL

$$$$$$SYSTIME$$$$$$
$$$$$$$$$$$$$$$$DGN$$$$$$$$$$$$$$$$
$$$$$$USERNAME$$$$