

PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.14.11.10451	11	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4688000000-E	4695000000-E	4700000000-E	4725000000-E	4815000000-E		4895000000-N	
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	6" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	12" X 90 M WHITE THERMO	THERMO STR ARROW 90 M	6" WHITE PAINT	6" YELLOW PAINT	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKERS
										MI	FT	SF	LS	LF	LF	LF	LF	EA	LF
2021CPT.14.11.10451	Henderson	1	US 25 NORTH	FROM .003 MILES NORTH OF BRIDGE #114 TO SC	1	2	MD	5.81	34	907		38,500	32,677	140	3,218	9	54,150	42,768	400
TOTAL FOR MAP NO. 1							5.81			907		38,500	32,677	140	3,218	9	54,150	42,768	400
2021CPT.14.11.10451	Henderson	2	US 25 SOUTH	FROM SC LINE TO BRIDGE #111	1	2	MD	5.765	34	907		38,500	32,677	100	3,218	6	54,150	42,768	400
TOTAL FOR MAP NO. 2							5.765			907		38,500	32,677	100	3,218	6	54,150	42,768	400
2021CPT.14.11.10451	Henderson	3	EXIT 1 RAMP	FROM NORTH TO US 225	2	1		0.25	26	16		2,690	2,690	75		3			27
TOTAL FOR MAP NO. 3							0.25			16		2,690	2,690	75		3			27
2021CPT.14.11.10451	Henderson	4	EXIT 1 RAMP	FROM US 225 TO US 25 NORTH	2	1		0.15	26	32		1,614	1,619			4			27
TOTAL FOR MAP NO. 4							0.15			32		1,614	1,619			4			27
2021CPT.14.11.10451	Henderson	5	EXIT 1 RAMP	FROM US 25 SOUTH TO SR 1104 /US 225	2	1		0.25	26	16		2,690	2,690	52		3			27
TOTAL FOR MAP NO. 5							0.25			16		2,690	2,690	52		3			27
2021CPT.14.11.10451	Henderson	6	EXIT 1 RAMP	ENTRANCE FROM SR-1104/US 225 TO US 25 SOUTH	2	1		0.3	26	32		3,228	3,228						27
TOTAL FOR MAP NO. 6							0.3			32		3,228	3,228						27
2021CPT.14.11.10451	Henderson	7	EXIT 3 RAMP	FROM US 25 NORTH TO SR-1106	2	1		0.25	26	16		2,690	2,690	102		3			27
TOTAL FOR MAP NO. 7							0.25			16		2,690	2,690	102		3			27
2021CPT.14.11.10451	Henderson	8	EXIT 3 RAMP	FROM SR-1106 TO US 25 NORTH	2	1		0.25	26	32		2,690	2,690						27
TOTAL FOR MAP NO. 8							0.25			32		2,690	2,690						27
2021CPT.14.11.10451	Henderson	9	EXIT 3 RAMP	FROM US 25 SOUTH TO SR-1106	2	1		0.3	26	16		3,228	3,228	80		3			27
TOTAL FOR MAP NO. 9							0.3			16		3,228	3,228	80		3			27
2021CPT.14.11.10451	Henderson	10	EXIT 3 RAMP	FROM SR-1106 TO US 25 SOUTH	2	1		0.25	26	32		2,690	2,690						27
TOTAL FOR MAP NO. 10							0.25			32		2,690	2,690						27
2021CPT.14.11.10451	Henderson	11	EXIT 5 RAMP	FROM US 25 NORTH TO .01 MILES SOUTH US 225	2	1		0.095	26	16		1,022	1,022	53		3			27
TOTAL FOR MAP NO. 11							0.095			16		1,022	1,022	53		3			27
2021CPT.14.11.10451	Henderson	12	EXIT 5 RAMP	FROM .02 MILES SOUTH OF US 25 TO US 25 NORTH	2	1		0.2	26	32		2,152	2,690						27
TOTAL FOR MAP NO. 12							0.2			32		2,152	2,690						27
2021CPT.14.11.10451	Henderson	13	EXIT 5 RAMP	FROM US 25 TO US 225	2	1		0.25	26	16		2,690	2,690	153					27
TOTAL FOR MAP NO. 13							0.25			16		2,690	2,690	153					27
2021CPT.14.11.10451	Henderson	14	EXIT 5 RAMP	FROM US 225 TO US 25 SOUTH	2	1		0.25	26	16		2,690	2,690						27
TOTAL FOR MAP NO. 14							0.25			16		2,690	2,690						27
TOTAL FOR PROJ NO. 2021CPT.14.11.10451								14.37		2,086	1	107,074	95,971	755	6,436	34	108,300	85,536	1,124
												203,045				193,836			
GRAND TOTAL								14.37		2,086	1	107,074	95,971	755	6,436	34	108,300	85,536	1,124
												203,045				193,836			