7 P - 1 - 5711

NTRACT: C204352

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN ALAMANCE COUNTY

LOCATION: INTERCHANGE IMPROVEMENTS AT I-40 /I-85
AND SR 1007 (MEBANE OAKS RD) IN MEBANE

PROJECT REFERENCE NO.

I - 5711

SIGN - 1

APPROVED:

Docusigned by:

Budding tung
6868A0DE5257455...

12/17/2019

SEAL

SEAL
032179

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON WOOD OR "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . DO NOT BEGIN FABRICATION FOR TYPES A & B SIGNS MOUNTED ON OVERHEAD STRUCTURES OR STEEL SUPPORTS UNTIL "S" DIMENSIONS HAVE BEEN FIELD VERIFIED.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

		SUMMARY OF QUANTITIES		
ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT.			
4048000000 4054000000 4057000000 4060000000 4066000000 4096000000 4102000000 4108000000 4109000000 4110000000 411000000 4116100000 4082100000 4082100000 4149000000 4152000000 4158000000 4192000000	902 902 SP 903 903 904 904 904 904 904 906 906 907 907 907	REINFORCED CONCRETE SIGN FOUNDATION PLAIN CONCRETE SIGN FOUNDATION OVERHEAD FOOTING SUPPORTS, BREAKAWAY STEEL BEAM SUPPORTS, SIMPLE STEEL BEAM SUPPORTS, 3 LB STEEL U-CHANNEL SIGN ERECTION, TYPE D SIGN ERECTION, TYPE E SIGN ERECTION, TYPE F SIGN ERECTION, TYPE A (OVERHEAD) SIGN ERECTION, TYPE A (GROUND MOUNTED) SIGN ERECTION, TYPE B (GROUND MOUNTED) SIGN ERECTION, RELOCATE SIGN (GROUND MOUNTED RESTAURANT LOGO SIGNS) SUPPORTS, OVERHEAD SIGN STRUCTURE @ -L- 23+15 SUPPORTS, OVERHEAD SIGN STRUCTURE @ -L- 30+75 DISPOSAL OF SIGN SYSTEM, OVERHEAD DISPOSAL OF SIGN SYSTEM, STEEL BEAM DISPOSAL OF SIGN SYSTEM, U-CHANNEL DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2 1 36 1886 317 900 4 51 2 4 6 1 1 1 1 2 56 2	CCCLBLAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAA

ROADWAY STANDARD DRAWING


THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	<u>TITLE</u>
901.10 901.20	TYPE 'A' SIGNS TYPE 'B' SIGNS
901.50 901.70 901.80	ARROWS AND SHIELDS SIGN STRINGERS AND SUPPORT SPACING SIGN MOUNTING DETAILS - FOR TYPE A AND TYPE B SIGNS
903.10 904.10	GROUND MOUNTED SIGN SUPPORTS ORIENTATION OF GROUND MOUNTED SIGNS
904.30 904.50	SUPPLEMENTAL SIGN MOUNTING MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

PLAN REVIEWED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

KELVIN L. JORDAN SIGNING & DELINEATION REGIONAL ENGINEER

ASHLEY K. MATTHEWS, PE SIGNING & DELINEATION PROJECT DESIGN ENGINEER



INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2-2A	REVISED SIGNING ROADWAY STANDARD DRAWINGS
SIGN-3	SUPPORT INFORMATION
SIGN-3A & 3B	STRUCTURE LINE DRAWING
SIGN-4	E AND F SHEET
SIGN-5 & 5A	OVERHEAD SIGN DESIGNS
SIGN-5B-5D	GROUND MOUNTED SIGN DESIGNS
SIGN-6-6A	SIGNING PLAN SHEET

PLAN PREPARED BY:

ACCELERATE ENGINEERING, PLLC

ZHAOLONG (GAVIN) TENG, PE, PTOE PROJECT MANAGER

875 Walnut Street, Suite 316 Cary, NC 27511 Tel: 919.263.5678 Fax: 919.263.5687 NC License No. P-1442

JSERNAME&&&&