BRIDGE DATA

PROJECT NO.	SHEET NO.
2021CPT.09.05.10341 2021CPT.09.06.20341	11

Map No.	Route No.	Route Name	Bridge No.	Feature Intersected	Floor Construction	Clear Roadway Width (Ft)	Horizontal Clearance Under (Ft.)	Vertical Clearance Under	Length (ft)	Posting	Recommended Treatment, From Bridge Maintenance
6	SR1160	Reynolds Rd	196	US421	6.75" RC SLAB	28	NA	NA	241	NA	Do Not Pave on Concrete Deck, incidental mill both ends
5	SR1109	Kinnamon Rd	135	I-40	7" RC SLAB	24	NA	NA	366	NA	Do Not Pave on Concrete Deck, mill up to both ends
8	SR1003	High Point Rd	34	Abbotts Creek	PPC.CS/6" AWS	32.833	NA	NA	163	NA	Mill 1 1/2", Pave 1 1/2" S9.5C
8	SR1003	High Point Rd	400	I-74, US311	8.5" RC SLAB	68	NA	NA	312	NA	Do Not Pave on Concrete Deck, mill up to both ends
8	SR1003	High Point Rd	477	I-74, US311	5.25" RC, 3.5PPC	39.7	48.084	16.083	139	NA	Mill 1 1/2", Pave 1 1/2" S9.5C
8	SR1003	High Point Rd	476	I-74, US311	5.25" RC, 3.5PPC	39.8	48.084	17.25	143	NA	Mill 1 1/2", Pave 1 1/2" S9.5C
7	SR2008	Tyner Rd	57	West Belews Creek	PPC.CS/3.24" AWS	23.917	NA	NA	62	NA	Mill 1 1/2", Pave 1 1/2" S9.5B
2	US311/ US52	US311/US52	218	US311	6.5 RC, 1" AWS	44.86	West 49.00 East 49.00	West 14.8330 East 14.50	127	NA	Mill 1 1/2", Pave 1 1/2" S9.5C