

PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.09.05.10341	14	
2021CPT.09.06.20341		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4810000000-E					4820000000-E				4835000000-E				4840000000-N								4890000000-E		4905000000-N	
										4" WHITE PAINT	4" YELLOW PAINT	8" YELLOW PAINT	8" WHITE PAINT	24" WHITE PAINT	PAINT MSG ONLY	PAINT MSG AHEAD	PAINT MSG STOP	PAINT MSG SCHOOL	PAINT LT ARROW	PAINT RT ARROW	PAINT STR ARROW	PAINT STR & RT ARROW	PAINT STR & LT ARROW	PAINT MERGE ARROW	24" X 90 M WHITE THERMO	SNOW PLOWABLE MARKERS								
										MI	FT	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA						
2021CPT.09.05.10341	Forsyth	1	US311	FROM INTERSECTION AT HARLEY DR TO STOKES COUNTY LINE	2,3	2	2WU	6.868	22-31	74,064	75,000	90								2								50	549					
TOTAL FOR MAP NO. 1											6.868	74,064	75,000	90						2							50	549						
2021CPT.09.05.10341	Forsyth	2	US311/ MARTIN LUTHER KING JR DR	FROM PVT JOINT WEST OF HWY52 TO APPROXIMATELY 200' PAST INTERSECTION OF US311 INCLUDING APROX. 150' OF US311 /NEW WALKERTOWN RD	2	4,5	M2	0.606	24-60	2,761	200			1,694	398					16	1	15	18					398	80					
TOTAL FOR MAP NO. 2											0.606	2,761	200		1,694	398				16	1	15	18				398	80						
TOTAL FOR PROJ NO. 2021CPT.09.05.10341											7.474	76,825	75,200	90	1,694	398				18	1	15	18				448	629						
										152,025		1,784							52															
2021CPT.09.06.20341	Forsyth	3	CLEMENTINE DR SR3104	FROM HAMPTON RD SR2999 TO END OF STATE MAINTENANCE	4	2	2WU	0.374	24-36																									
TOTAL FOR MAP NO. 3											0.374																							
2021CPT.09.06.20341	Forsyth	4	CLOVER DR SR3105	FROM CLEMENTINE DR SR3104 TO END OF STATE MAINTENANCE	4	2	2WU	0.114	24																									
TOTAL FOR MAP NO. 4											0.114																							
2021CPT.09.06.20341	Forsyth	5	KINNAMON RD SR1109	FROM US158 TO S PEACE HAVEN RD SR1891	1,5	2	2WU	1.71	25-42	20,137	24,509	135	170	78	8					10	6	2	2					78						
TOTAL FOR MAP NO. 5											1.71	20,137	24,509	135	170	78	8				10	6	2	2				78						
2021CPT.09.06.20341	Forsyth	6	REYNOLDS RD SR1160	FROM STYERSFERRY RD SR1100 TO LEWISVILLE-CLEMMONS RD SR1156	4	2	2WU	0.915	19-28	600	600																							
TOTAL FOR MAP NO. 6											0.915	600	600																					
2021CPT.09.06.20341	Forsyth	7	TYNER RD SR2008	FROM BELEWS CREEK RD SR1965 TO SULLIVAN RD SR1992	1,4	2	2WU	0.928	20-24																									
TOTAL FOR MAP NO. 7											0.928																							
2021CPT.09.06.20341	Forsyth	8	HIGH POINT RD SR1003	FROM PVT JOINT AT WAUGHTOWN RD SR4315 TO PVT JOINT PAST US66 INTERSECTION	2,3,6	2,5	2WU	8.061	22-56	102,356	103,918	400	382	326		5	4	24		14	7	8	5	8	14		126							
TOTAL FOR MAP NO. 8											8.061	102,356	103,918	400	382	326		5	4	24		14	7	8	5	8	14		126					
TOTAL FOR PROJ NO. 2021CPT.09.06.20341											12.102	123,093	129,027	535	552	404	8	5	4	24		24	13	10	7	8	14		204					
										252,120		1,087							41				76											
GRAND TOTAL											19.576	199,918	204,227	625	2,246	802	8	5	4	24		42	14	25	25	8	14		652	629				
										404,145		2,871						41				128												

Note: All quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities recieved