SUMMARY OF EARTHWORK IN CUBIC YARDS						
Station	Station	Uncl. Excav.	Embank. +%	Borrow	Waste	
17+94.46	29+78.34	2229	658	0	1571	
40+82.09	52+66.33	1754	320	0	1434	
PROJECT TOTALS:		3983	978	0	3005	
GRAND TOTALS:		3983	978	0	3005	
SAY:		3990	980	0	3010	
UNDERCUT EXCAVATION:		0				
SAY:		0				

PAVEMENT REMOVAL SUMMARY

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL	ASPHALT BREAKUP	CONCRETE REMOVAL	CONCRETE BREAKUP
-L-	17+95.46	29+78.34	SEE XS	3569			
-L-	40+82.09	52+66.33	SEE XS	2283			
		TOTAL:		5852			
		SAY:		5860			

4/6/2020 C:\Users\ediedens\Downloads\Green River\15bpr.20_Rdu_psh03B-1.dar

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK IN CUBIC YARDS

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, SHOULDER BORROW, FINE GRADING, CLEARING AND GRUBBING, BREAKING OF EXISTING PAVEMENT AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".

LINE	Station	Station	LENGTH
-L- (LT)	18+98.47	29+78.34	1079.87
-L- (RT)	24+39.66	29+78.34	538.68
-L- (RT)	40+82.09	41+95.68	113.59
-L- (LT)	40+82.09	53+47.91	1265.82
		TOTAL:	2997.96
		SAY:	2998

SHOULDER BERM GUTTER

DOCUMENT NOT CONSIDE		
15BPR.20	<u>3B-I</u>	
PROJECT REFERENCE NO.	SHEET NO.	