


PROJECT REFERENCE NO.	SHEET NO.
W-5600	1C-6
Location and Surveys	


SURVEY CONTROL SHEET

W/EXISTING CENTERLINE ALIGNMENTS PRIOR TO CONSTRUCTION



NC GRID
NAD 83 NA 2011

REVISIONS



DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCDOT FOR MONUMENT "W-5600-3"

WITH NAD 83/NSRS 2007 STATE PLANE GRID COORDINATES OF
NORTHING: 666326.104(ft) EASTING: 2188577.710(ft)
ELEVATION: 203.964(ft)

THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.99988457

THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "W-5600-3" TO -L- STATION 9+99.84 IS
N65°13'59.09"W 13,283.31 FT

ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES
VERTICAL DATUM USED IS NAVD 88

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
2. THE SURVEY CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

12/14/2020 12:58:11 PM I:\SF\B\5600_1c.dwg 01c-6.dgn