

4. INSTALL EQUIPMENT CABINET ON METAL POLE SUCH THAT THE LOWERING SYTEM AND HAND HOLE OPERATE

6. CONTACT ENGINEER TO REQUEST NCDOT SUPPLIED MODEM AT LEAST SIX (6) WEEKS PRIOR TO INSTALLATION.

5. INSTALL NEW GROUNDING SYSTEM AT CCTV-3 AS DESCRIBED ON SHEET ITS-12 AND AS DESCRIBED

FREE OF OBSTRUCTIONS.

IN THE PROJECT SPECIAL PROVISIONS.

NOTE:
ELECTRICAL SERVICE DETAILS AND CONSTRUCTION
METHODS DEPICT FIELD CONDITIONS AT THE TIME
OF DESIGN. CONTRACTOR TO VERIFY ACTUAL
CONDITIONS AT THE TIME OF CONSTRUCTION AND
OBTAIN APPROVAL FROM ENGINEER PRIOR TO MAKING
ANY CHANGES.

PROJECT REFERENCE NO.

W-5600

ITS-6

