PROJ. REFERENCE NO.	SHEET NO.
W-5600	X-1K

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS–SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
155+50.00	24	160	0
156+00.00	33	8	0
Phase 1C - Left Side -L- 158+00 to 179+00 LT			
158+00.00	0	0	0
158+50.00	0	0	0
159+00.00	0	0	0
159+50.00	7	0	0
160+00.00	18	1	0
160+50.00	27	8	0
161+00.00	124	7	0
161+50.00	156	1	0
162+00.00	77	11	0
162+50.00	56	30	0
163+00.00	36	64	0
163+50.00	19	135	0
164+00.00	68	154	0
164+50.00	180	159	0
165+00.00	247	200	0
165+50.00	152	184	0
166+00.00	33	167	0
166+50.00	13	165	0
167+00.00	14	159	0
167+50.00	14	113	0
168+00.00	13	46	0
168+50.00	13	13	0
169+00.00	12	12	0
169+50.00	13	13	0
170+00.00	15	1	0
170+50.00	13	0	0
171+00.00	10	0	0
171+50.00	7	0	0
172+00.00	3	0	0
172+50.00	1	0	0
173+00.00	315	13	0
173+50.00	556	16	0
174+00.00	323	14	0
174+50.00	95	13	0
175+00.00	23	3	0
175+50.00	25	21	0
176+00.00	129	38	0
176+50.00	305	33	0
177+00.00	532	32	0
177+50.00	800	30	0
178+00.00	973	21	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
178+50.00	1005	17	0
179+00.00	890	16	0
Phase 1C - Left Side -Y7- 14+20 to 20+50			
14+20.00	0	0	0
14+50.00	26	1	0
15+00.00	133	5	0
15+50.00	166	14	0
16+00.00	149	24	0
16+50.00	151	26	0
17+00.00	167	26	0
17+50.00	184	21	0
18+00.00	188	13	0
18+50.00	164	17	0
19+00.00	127	23	0
19+50.00	74	20	75
20+00.00	41	11	118
20+50.00	30	27	46
Phase 1C - Left Side -SR4- 10+50 to 18+00			
10+50.00	0	0	0
11+00.00	51	32	0
11+50.00	163	1	0
12+00.00	229	0	0
12+50.00	225	0	0
13+00.00	179	0	0
13+50.00	78	3	77
14+00.00	18	11	130
14+50.00	35	12	131
15+00.00	117	7	160
15+10.00	38	1	32
15+80.00	316	8	227
16+52.50	276	9	235
17+32.50	130	124	130
18+00.00	28	197	0
Phase 1C - Left Side -DR2- 10+50 to 12+70			
10+50.00	0	0	0
11+00.00	0	960	0
11+50.00	0	507	0
12+00.00	0	256	0
12+50.00	0	88	0
12+70.00	3	4	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
Phase 1C - Left Side -Y7LPA- 10+00 to 20+65			
10+00.00	0	0	0
10+49.99	26	11	0
10+99.67	53	15	0
11+49.48	94	21	0
12+01.98	205	68	0
12+42.80	133	104	0
12+90.00	117	75	0
13+20.00	140	2	0
13+50.00	136	1	0
14+00.00	187	2	0
14+50.00	208	4	0
15+00.00	233	5	0
15+50.00	226	1	0
16+00.00	199	0	0
16+50.00	121	4	0
17+00.00	28	88	0
17+50.00	0	262	0
18+00.00	0	501	0
18+50.00	0	749	0
19+00.00	0	1008	0
19+50.00	0	1252	0
20+00.00	0	1325	0
20+50.00	0	1433	0
20+65.00	0	505	0
Phase 1C - Left Side -Y7RPA- 10+00 to 28+40.98			
10+00.00	0	0	0
10+49.93	631	23	0
10+99.93	528	25	0
11+50.00	390	30	0
12+00.05	482	26	0
12+50.10	774	21	0
13+00.18	975	23	0
13+50.34	867	41	0
14+00.66	496	101	0
14+50.97	156	246	0
14+98.36	41	375	0
15+47.69	59	490	0
15+96.86	105	569	0
16+44.01	126	600	0
16+95.00	115	624	0
17+50.00	61	582	0
18+00.00	51	860	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
18+50.00	138	986	0
19+00.00	147	711	0
19+50.00	85	749	0
20+00.00	32	1007	0
20+50.00	0	1283	0
21+00.00	0	1550	0
22+00.00	0	3310	0
22+70.00	0	1469	0
23+41.89	40	459	0
24+05.70	93	100	0
24+64.76	67	141	0
25+20.48	18	342	0
25+73.45	26	414	0
26+25.47	43	417	0
26+75.98	36	460	0
27+25.98	40	481	0
27+75.98	43	520	0
28+25.98	18	722	0
28+40.98	0	308	0
Phase 1C - Right Side -L- 147+00 to 156+00 RT			
147+00.00	0	0	0
147+50.00	446	10	0
148+00.00	461	9	0
148+50.00	609	5	0
149+00.00	784	5	0
149+50.00	858	5	0
150+00.00	762	7	0
150+50.00	576	10	0
151+00.00	482	9	0
151+50.00	598	10	0
152+00.00	628	12	0
152+50.00	313	8	0
153+00.00	64	4	0
153+50.00	30	4	0
154+00.00	24	3	0
154+50.00	8	0	0
155+00.00	0	0	0
155+50.00	0	0	0
156+00.00	29	0	0
Phase 1C - Right Side -L- 158+00 to 179+00 RT			
158+00.00	0	0	0
158+50.00	28	13	0
159+00.00	20	69	0

12/21/2020
W-5600_rdy_xpl_index.dgn
USER:Hefner