

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO. SHEET NO.
W-5600 X-10

NOTE: EMBANKMENT COLUMN DOES NOT
INCLUDE BACKFILL FOR UNDERCUT.

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will
recross-section the work accurately when the project is staked
out. These cross-section notes will be used in computing the
final quantities for which the contractor will be paid.

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
145+00.00	50	1	0	166+00.00	45	0	0	Phase 4 -L- 97+00 to 114+00 MED				Phase 4 -Y5- 12+30 to 12+70			
145+50.00	49	0	0	166+50.00	43	0	0	97+00.00	0	0	0	12+30.00	0	0	0
146+00.00	42	0	0	167+00.00	38	0	0	97+50.00	12	10	0	12+50.00	15	18	0
146+50.00	38	0	0	167+50.00	30	3	0	98+00.00	25	4	0	12+70.00	34	37	0
147+00.00	36	1	0	168+00.00	33	3	0	98+50.00	36	0	0	Phase 4			
147+50.00	30	4	0	Phase 4 -Y7- 20+50 to 25+99				99+00.00	36	0	0	Phase 4 -Y5- 16+90 to 18+20			
148+00.00	33	3	0	20+50.00	0	0	0	99+50.00	40	0	0	16+90.00	0	0	0
148+50.00	34	0	0	21+00.00	21	300	4	100+00.00	49	0	0	17+00.00	5	21	0
149+00.00	28	0	0	21+50.00	23	696	0	100+50.00	56	0	0	17+50.00	47	51	0
149+50.00	28	0	0	22+00.00	22	978	0	101+00.00	59	0	0	18+00.00	60	3	0
150+00.00	30	0	0	22+50.00	21	1050	0	101+50.00	58	1	0	18+20.00	11	1	0
150+50.00	33	0	0	23+00.00	9	876	0	102+00.00	60	2	0				
151+00.00	39	0	0	23+50.00	0	834	0	102+50.00	63	2	0				
151+50.00	51	0	0	24+00.00	0	1447	0	103+00.00	68	1	0				
152+00.00	60	0	0	24+50.00	0	2672	0	103+50.00	76	0	0				
152+50.00	60	0	0	25+00.00	0	3438	0	104+00.00	92	0	0				
153+00.00	61	0	0	25+50.00	0	3694	0	104+50.00	102	0	0				
153+50.00	59	1	0	25+99.00	0	4111	0	105+00.00	93	0	0				
154+00.00	56	2	0	Phase 4 -Y7- 28+05 to 39+00				105+50.00	67	0	0				
154+50.00	53	3	0	28+05.00	0	0	0	106+00.00	35	1	0				
155+00.00	49	6	0	28+50.00	0	4182	0	106+50.00	16	3	0				
155+50.00	49	7	0	29+00.00	0	4779	0	107+00.00	13	5	0				
156+00.00	49	7	0	29+50.00	0	4562	0	107+50.00	15	5	0				
156+50.00	59	3	0	30+00.00	0	4694	0	108+00.00	18	4	0				
157+00.00	74	0	0	30+50.00	0	4277	0	108+50.00	21	4	0				
Phase 3 -L- 157+00 to 168+00 MED				31+00.00	0	2929	0	109+00.00	22	6	0				
157+00.00	0	0	0	31+50.00	0	1404	0	109+50.00	23	7	0				
157+50.00	76	0	0	32+00.00	0	628	0	110+00.00	35	4	0				
158+00.00	60	1	0	32+50.00	146	633	0	110+50.00	46	0	0				
158+50.00	45	3	0	33+00.00	280	653	0	111+00.00	48	0	0				
159+00.00	44	8	0	33+50.00	296	473	0	111+50.00	49	0	0				
159+50.00	49	6	0	34+00.00	481	297	0	112+00.00	51	0	0				
160+00.00	58	1	0	34+50.00	666	153	0	112+50.00	53	0	0				
160+50.00	62	0	0	35+00.00	778	61	0	113+00.00	54	0	0				
161+00.00	64	0	0	35+50.00	489	33	0	113+50.00	57	0	0				
161+50.00	66	0	0	36+00.00	88	26	0	114+00.00	59	0	0				
162+00.00	71	0	0	36+50.00	169	17	0	Phase 4 -L- 156+00 to 158+00 RT							
162+50.00	74	0	0	37+00.00	250	13	0	156+00.00	0	0	0				
163+00.00	71	0	0	37+50.00	196	16	0	156+50.00	46	0	0				
163+50.00	56	0	0	38+00.00	162	19	0	157+00.00	33	0	0				
164+00.00	42	0	0	38+50.00	161	17	0	157+50.00	32	0	0				
164+50.00	37	0	0	39+00.00	87	10	0	158+00.00	32	0	0				
165+00.00	38	0	0												
165+50.00	42	0	0												