PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.16.20731.1	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	0264000000-E SHOULDER GRADING	1220000000-E INCIDENTAL STONE BASE	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1520000000-E LEVELING COURSE, TYPE S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEED & MULCHING	6117000000-N RESPONSE FOR EROSION CONTROL
									MI	FT	CY	SMI	TONS	TON	SY	SY	SY	TONS	TON	TON	TONS	LF	LF	AC	EA
2021CPT.05.16.20731.1	Person	1	SR 1102 - GORDONTON RD	SR 1173 - TOM BOWES RD TO US 158 - LEASBURG RD	1	2	NO	NO	5.556	20	111	11.00	278	821	407		1,900	5,875		394	115	162	410	1.62	1
		2	SR 1364 - CARVER DR/MEMORIAL DR	SR 1363 - RIDGE RD TO SR 1416 - COLLEGE DR	1	2	NO	NO	1.383	20	69	2.77	69	128			223	1,436		96	1,425	101	260	1.01	1
		3	SR 1129 - FRANK TIMBERLAKE RD	SR 1134 - SATTERFIELD RD TO SR 1218 - ROBY BARTON RD	1	2	NO	NO	2.49	20	50	4.98	125	368			2,028	2,744		184	485	72	190	0.72	1
		4	SR 1144 - FLAT RIVER CHURCH RD	US 501-DURHAM RD TO PVMT JT AT BRIDGE	1	2	NO	NO	1.59	20	32	3.16	79	233	222	62	879	1,948		131	80	46	120	0.46	1
		5	SR 1416 - MEMORIAL DR/COLLEGE DR	SR 1605 MAIN ST TO END MAINT	1	2	NO	NO	0.802	22	64	1.60	40	30			59	950		64	894	93	240	0.93	
		6	SR 1300 - CONCORD CHURCH RD	NC 57 - SEMORA RD TO SR 1102 - RALPH WINSTEAD RD	1	2	NO	NO	2.938	20	147	5.88	147	271			903	3,069	45	209	25	214	540	2.14	1
		7	SR 1305 - MILL HILL RD	SR 1343 - LONG'S STORE RD TO US 158 - LEASBURG RD	1	2	NO	NO	2.34	20	47	4.68	117	346			1,456	2,453		164	30	68	180	0.68	1
		8	SR 1551 - GENTRY DUNKLEY RD	SR 1542 -DIRGIE MINE RD TO DEAD END	1	2	NO	NO	1.814	20	27	3.61	90	283		62	150	1,891		127	160	39	100	0.39	1
		9	SR 1703 - LUCY GARRETT RD	SR 1708 - ANTIOCH CHURCH RD TO OLD DURHAM ROAD	2 & 3	2	NO	NO	2.83	24	57	5.66	142	418	40,203		1,447	4,141		277	80	82	210	0.82	1
		10	SR 1740 - ROBERT GENTRY RD	SR 1715 - HELENA-MORIAH RD TO SR 1737 - MOORES MILL RD	1	2	NO	NO	1.24	20	62	2.48	62	115			167	1,268		85	5	90	230	0.90	1
		11	SR 1107 - UNION GROVE CHURCH RD.	SR 1102 - WHEELERS CHURCH RD TO SR 1001 - HURDLE MILLS RD	1	2	NO	NO	4.049	20	81	8.00	202	599	473		570	4,338		291	77	118	300	1.18	1
TOTAL FOR PROJ NO. 2021CPT.05.16.20731.1									**27.032**		**747**	**53.82**	**1,351**	**3,612**	**41,305**	**124**	**9,782**	**30,113**	**45**	**2,022**	**3,376**	**1,085**	**2,780**	**10.85**	**10**
GRAND TOTAL									**27.032**		**747**	**53.82**	**1,351**	**3,612**	**41,305**	**124**	**9,782**	**30,113**	**45**	**2,022**	**3,376**	**1,085**	**2,780**	**10.85**	**10**