



PAVEMENT SCHEDULE	
C	PROP. APPROX. 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 137.5 LBS PER SQ YD
C1	PROP. APPROX. 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 165 LBS PER SQ YD
C2	PROP. APPROX. 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD
F	AST MAT COAT, #78 STONE
V	INCIDENTAL MILLING
V1	MILL ASPHALT PAVEMENT, 1 1/4" DEPTH
V2	MILL ASPHALT PAVEMENT, 1 1/2" DEPTH
U	EXISTING PAVEMENT