

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will
 recross-section the work accurately when the project is staked
 out. These cross-section notes will be used in computing the
 final quantities for which the contractor will be paid.

Note: Embankment column does not include backfill for undercut

CROSS-SECTION SUMMARY

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y21			Y24			Y29			Y31A			RPC		
11+85.00	0	0	14+37.73	0	0	10+09.71	0	0	10+22.53	0	0	15+00.00	0	0
12+00.00	4	0	14+50.00	13	0	10+50.00	30	21	10+50.00	0	104	15+50.00	12	5
12+50.00	20	0	15+00.00	33	6	11+00.00	31	31	11+00.00	0	104	16+00.00	12	17
13+00.00	57	0	15+50.00	15	6	11+50.00	19	22	11+30.00	1	8	16+50.00	11	28
13+40.18	71	0	16+00.00	19	7	11+52.54	1	0				17+00.00	9	30
			16+50.00	19	7				Station	Uncl. Exc.	Embt	17+50.00	8	32
Station	Uncl. Exc.	Embt				Station	Uncl. Exc.	Embt	Y32	(cu. yd.)	(cu. yd.)	18+00.00	10	33
Y21	(cu. yd.)	(cu. yd.)	Station	Uncl. Exc.	Embt	Y29	(cu. yd.)	(cu. yd.)	10+37.50	0	0	18+50.00	13	35
14+15.22	0	0	Y25	(cu. yd.)	(cu. yd.)	12+28.66	0	0	10+50.00	28	23	19+00.00	12	49
14+50.00	9	18				12+50.00	5	6	11+00.00	63	55	19+50.00	8	69
14+80.00	9	8	11+10.00	0	0	12+95.00	18	7	11+22.00	7	4	20+00.00	8	85
			11+50.00	10	10							20+50.00	11	92
Station	Uncl. Exc.	Embt	12+00.00	18	14	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	21+00.00	11	96
Y22	(cu. yd.)	(cu. yd.)	12+50.00	29	11	Y30	(cu. yd.)	(cu. yd.)	RPA	(cu. yd.)	(cu. yd.)	21+50.00	9	96
11+80.00	0	0	12+68.38	12	4	11+20.00	0	0	13+47.27	0	0	22+00.00	10	80
12+00.00	4	0				11+50.00	9	8	13+50.00	1	1	22+50.00	13	76
12+50.00	18	0	Station	Uncl. Exc.	Embt	12+00.00	19	15	14+00.00	10	28			
13+00.00	27	27	Y25	(cu. yd.)	(cu. yd.)	12+50.00	23	11	14+50.00	6	50	Station	Uncl. Exc.	Embt
13+12.62	8	14	13+43.66	0	0	12+53.00	1	1	15+00.00	5	74	RPD	(cu. yd.)	(cu. yd.)
			13+50.00	1	2				15+50.00	4	97			
Station	Uncl. Exc.	Embt	14+00.00	10	9	Station	Uncl. Exc.	Embt	16+00.00	5	121	12+20.00	0	0
Y22	(cu. yd.)	(cu. yd.)	14+05.00	1	0	Y30	(cu. yd.)	(cu. yd.)	16+50.00	33	116	12+50.00	13	2
13+87.64	0	0				13+28.32	0	0	17+00.00	172	78	13+00.00	25	6
14+00.00	2	8	Station	Uncl. Exc.	Embt	13+50.00	23	19	17+50.00	332	45	13+50.00	16	9
14+30.00	8	11	Y26	(cu. yd.)	(cu. yd.)	14+00.00	44	22	18+00.00	255	18	14+00.00	8	15
			11+30.00	0	0	14+50.00	28	1	18+50.00	97	97	14+50.00	55	21
Station	Uncl. Exc.	Embt	11+50.00	6	2	14+85.00	12	4	19+00.00	58	242	14+80.27	62	15
Y23	(cu. yd.)	(cu. yd.)	12+00.00	19	4				19+50.00	31	260			
10+37.52	0	0	12+50.00	35	1	Station	Uncl. Exc.	Embt	19+91.33	11	191	Station	Uncl. Exc.	Embt
10+50.00	2	5	12+70.86	20	0	Y31	(cu. yd.)	(cu. yd.)				TIE	(cu. yd.)	(cu. yd.)
11+00.00	6	9				12+25.00	0	0	Station	Uncl. Exc.	Embt	12+00.00	0	0
11+50.00	12	0	Station	Uncl. Exc.	Embt	12+50.00	4	1	RPB	(cu. yd.)	(cu. yd.)	12+50.00	64	0
11+65.00	5	0	Y28	(cu. yd.)	(cu. yd.)	13+00.00	10	33	11+30.00	0	0	13+00.00	20	456
			15+86.48	0	0	13+50.00	74	81	11+50.00	3	1	13+50.00	10	995
Station	Uncl. Exc.	Embt	16+00.00	39	4	14+00.00	155	103	12+00.00	8	13	14+00.00	2	1142
Y24	(cu. yd.)	(cu. yd.)	16+50.00	103	7	14+50.00	147	110	12+50.00	39	18	14+50.00	0	1278
11+15.00	0	0	17+00.00	54	2	15+00.00	64	80	13+00.00	110	29	15+00.00	3	1529
11+50.00	16	0	17+50.00	54	2	15+50.00	3	57	13+50.00	224	52	15+50.00	37	1590
12+00.00	31	2	18+00.00	50	4	16+00.00	0	69	13+82.18	191	38	16+00.00	83	1430
12+50.00	38	2	18+50.00	38	6	16+50.00	1	100				16+50.00	84	1212
13+00.00	39	0	19+00.00	35	9	17+00.00	2	130				17+00.00	60	932
13+50.00	90	0	19+50.00	31	26	17+35.10	1	90				17+50.00	31	855
13+62.69	37	0	20+00.00	28	48									
			20+50.00	23	44									
			20+68.00	6	8									