

WOVEN WIRE FENCE (47" FABRIC)

LINE	STATION	STATION	LOCATION	LF.	4" POST	5" POST
-RPA-	15+90.23	28+28.00	RT.	1283.00	81	20
-Y1A-	19+48.65	26+12.00	LT.	754.00	46	14
-RPD-	17+80.46	23+50.00	LT.	573.00	35	11
-Y1C-	36+01.27	43+82.55	LT.	735.00	47	11
-Y1C-	36+00.00	42+45.00	RT.	703.00	43	14
-RPB-	20+90.78	22+35.55	RT.	440.00	27	8
				TOTAL:	4488.00	278
				SAY:	4500.00	278

CHAIN LINK FENCE (48" FABRIC)

LINE	STATION	STATION	LOCATION	LF.	LINE POSTS	TERMINAL POST
-RPB-	17+00.00	20+00.00	LT.	300.00	26	6
-Y1A-	19+18.42	21+50.00	RT.	246.00	21	2
				TOTAL:	546.00	8
				SAY:	600.00	8

REMOVAL OF EXISTING PAVEMENT

LINE	STATION	STATION	LOCATION	SY.	
TEMP. PAVEMENT REMOVAL					
-L-	14+86.00	32+19.00	MED. RT.	744.11	
-L-	38+32.00	71+08.00	MED. RT.	1507.78	
-L-	18+73.00	37+13.00	MED. LT.	813.07	
-L-	43+60.00	73+00.00	MED. LT.	1183.67	
-L-	71+58.00	81+17.00	MED.	2024.78	
-L-	78+25.00	80+92.00	LT.	900.22	
EXIST. PAVEMENT					
-L-	14+92.00	68+00.00	MED. RT.	3328.99	
-L-	14+87.00	68+00.00	MED. LT.	3130.98	
-Y1A-	12+53.00	14+44.00	LT.	216.67	
-Y1A-	14+69.00	20+24.00	LT.	1439.44	
-RPB-	20+24.00	20+50.00	LT. / RT.	991.44	
-Y1B-	30+19.00	34+34.00	RT.	1960.11	
-Y1C-	34+34.00	43+32.00	RT.	1530.22	
-L-	14+87.00	37+16.00	RT.	1189.78	
-L-	39+22.00	68+00.00	RT.	1434.00	
-L-	14+89.00	68+00.00	LT.	3101.33	
-Y1C-	41+50.00	44+55.00	CL.	494.67	
				TOTAL:	25,991.26
				SAY:	26,500.00

SHOULDER BERM GUTTER

LINE	STATION	STATION	LOCATION	LF.	
-RPA-	16+57.41	22+75.11	RT.	617.17	
-RPB-	16+85.00	20+50.00	LT.	365.00	
-L-	14+88.04	15+17.59	LT.	29.55	
-L-	17+16.00	20+34.00	RT.	318.00	
				TOTAL:	1330.00
				SAY:	1350.00

EXPRESSWAY GUTTER

LINE	STATION	STATION	LOCATION	LF.	
-RPC-	13+20.49	20+01.09	RT.	670.19	
				TOTAL:	670.19
				SAY:	680.00

MILLED RUMBLE STRIPS

LINE	STATION	STATION	LOCATION	LF.	
-L-	14+88.04	30+06.00	LT.	1,517.96	
-L-	31+91.61	54+37.71	LT.	2,246.10	
-L-	59+57.49	68+00.00	LT.	842.51	
-L-	14+88.04	68+00.00	MED. LT.	5,311.96	
-L-	14+88.04	68+00.00	MED. RT.	5,311.96	
-L-	14+88.04	25+45.82	RT.	1,057.05	
-L-	32+26.79	53+57.84	RT.	2,131.05	
-L-	58+60.34	68+00.00	RT.	939.66	
				TOTAL:	19,358.98
				SAY:	20,000.00

REVISIONS

8/17/99

3/6/2021 3:52:00 PM R-5797_Req_PSH_03B-2.dgn
 USER: RMP