PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.15.20321.1 , 2021CPT.05.15.20322.1	50	

THERMOPLASTIC AND PAINT QUANTITIES

									4413000000-E	4457000000-N	4510000000-N	4685000000-E		4688000000-E	4695000000-E		4720000000-E					4725000000-E				
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	LAW ENFORCEMENT	4" X 90 M YELLOW THERMO	4" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	8" X 90 M YELLOW THERMO	THERMO MSG ONLY 90 M	THERMO MSG SCHOOL 90 M	THERMO MSG RXR 90 M	THERMO MSG STOP 90 M	THERMO MSG AHEAD 90 M	THERMO LT ARROW 90 M	THERMO STR ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR & LT ARROW 90 M	THERMO STR & RT ARROW 90 M
							MI	FT	SF	LS	HR	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2021CPT.05.15.20321.1	Durham	1	E CORNWALLIS RD SR 1158	SR 1118 (FAYETTEVILLE ST) TO SR 2295 (S ROXBORO ST)	1	5	0.642	60	72		40	8,473	1,820		344		8					22	2	8	2	
		2	ERWIN RD. SR 1320	NC 751 TO BUS 70	2	5	2.229	50-65	250		80	25,720	4,450	90	1,365		24					81	40	18		15
		3	MADDEN AVE SR 1457	US 501 - SR 1456 (MILTON RD)	3	2	0.251	20-30	28			2,650	2,650													
		4	TOM WILKINSON RD SR 1458	US 501 TO SR 1456 (MILTON RD)	3	2	0.206	18	24			2,110	2,110		90											
		5	MIDLAND TER SR 1709	SR 1669 (E CLUB BLVD) TO SR 1671 (CAMDEN AVE.	3	2	0.632	24	24		40	6,700	6,700													
		6	MIDLAND TER SR 1827	SR 1800 (CHEEK RD) TO SR 1671 (CAMBEN AVE.)	3	2	0.997	21	111			10,550	10,550													
		7	MEADSTON DR SR 1753	SR 1640 (GOODWIN RD) TO SR 2619 (CHUTNEY)	4	2	0.147	21	17																	
		8	SNOW VALLEY RD SR 1775	SR 1631(SNOW HILL RD) TO EOM	5	2	0.216	20	25																	
		9	LAZYWOOD LN SR 1791	SR 1639 (INFINITY RD) TO CDS	4	2	0.220	20	25																	
		10	BREWINGTON PL SR 1792	SR 1791 (LAZYWOOD LN) TO END MAINT.	4	2	0.112	20	12																	
		11	CHUTNEY DR SR 2619	END MAINT. TO END MAINT.	4	2	0.113	20	12																	
		12	GOODWIN RD SR 1640	US 501 - SR 1639 (INFINITY RD)	4	2	2.193	20	246		40	23,154	23,154													
		13	STALLINGS RD SR 1814	SR 1811 (PATTERSON RD) TO SR 1815 (N MINERAL SPRINGS RD)	7	2	1.829	22-36	205			20,000	19,600	230												
		14	CLAYTON RD SR 1825	NC 98 TO SR 1800 (CHEEK RD)	7	2	1.826	24-36	205		40	19,600	19,600	50		150		12								
		15	SKYLINE DR SR 1779	SR 1778 (WANDERLUST LN) TO EOM	5	2	0.186	20	22	*																
		16	SETERRA BND/POINTE PL SR 1754	SR 1639 (INFINITY RD) TO END LOOP SR 1754 (POINTE PL)	4	2	0.516	20	58																	
		17	WANDERLUST LN SR SR 1778	SR 1631 (SNOW HILL RD) TO EOM	5	2	0.396	20	45																	
		18	E CLUB BLVD SR 1669	SR 1666 (DEARBORN DR) TO AMBRIDGE ST.	8,9,10	2	0.850	24-36	96		40	9,366	7,750	35		125						3				
		19	E CLUB BLVD SR 1669	AMBRIDGE STREET TO US 501 BUS.	11	2	0.489	24-36	44		40	5,200	360	40	100	50						3	2	2		
		20	W CORNWALLIS RD SR 1308	SR 1306 (ERWIN RD) TO US 15-501	13	2	0.932	22-40	105			9,300	9,800	40		100						1		1		
		21	ANGIER AVE SR 1926	NC 55 TO EAST END AVE	12	2	1.387	30-36	156				12,108						8							
		22	FARRINGTON RD SR 1110	NC 54 (MILEPOST 4.045) TO SR 1113	14	2	0.967	24-40	110			1,276	8,311		110	100						17				
		23	DAFFODIL LN SR 1582	SR 1558 (WHITT RD) TO END MAINT.	5	2	0.148	20	17																	
		24	HAROLD DR SR 1566	SR 1558 (WHITT RD) TO END MAINT.	5	2	0.213	18	24																	